


FROM SHADOWS and SYMBOLS to the TRUTH



MARYGROVE COLLEGE  
EX LIBRIS

913.37

P92









913.8  
P92  
The Students' Series of Latin Classics

# THE PRIVATE LIFE OF THE ROMANS

WITH NUMEROUS ILLUSTRATIONS

BY

HARRIET WATERS PRESTON

AND

LOUISE DODGE

οὐ πόλλ' ἀλλὰ πολὺ

BENJ. H. SANBORN & CO.

BOSTON, U.S.A.

UNIVERSITY OF MICHIGAN LIBRARY  
DETROIT, MICHIGAN

COPYRIGHT, 1893,  
By LEACH, SHEWELL, & SANBORN.

Norwood Press :  
J. S. Cushing & Co. — Berwick & Smith.  
Boston, Mass., U.S.A.

## TABLE OF CONTENTS.

---

I.	PAGE
THE FAMILY . . . . .	1
II.	
THE HOUSE AND EVERY-DAY LIFE . . . . .	28
III.	
CHILDREN, SLAVES, GUESTS, CLIENTS, FREEDMEN . . . . .	57
IV.	
FOOD AND CLOTHING . . . . .	77
V.	
AGRICULTURE . . . . .	105
VI.	
TRAVEL, TRANSPORTATION, AMUSEMENTS . . . . .	135
<hr/>	
TABLES OF WEIGHTS, MEASURES, ETC. . . . .	159
INDEX . . . . .	165



## INTRODUCTORY.

---

THE following brief account of the private manners and customs of the ancient Romans, their families and homes, their meat, drink, and clothing, their means of culture, amusement, etc., has been compiled, for the most part, from the latest German authorities on this interesting subject. It is especially based on the encyclopedic work of Marquardt and Mommsen, *Handbuch der Römischen Alterthümer: Siebenter Band, Privatleben der Römer*, von Joachim Marquardt. 2<sup>te</sup> Auflage. Leipzig, S. Hirzel, 1886.

For illustrations of the imperial period, constant reference has also been made to the more discursive but always striking and suggestive work of Prof. Ludwig Friedländer, *Darstellungen aus der Sittengeschichte Roms, in der Zeit von August bis zum Ausgang der Antonine*. Fünfte neu bearbeitete und vermehrte Auflage. Leipzig, S. Hirzel, 1881.

The *Gallus* of Prof. W. A. Becker remains, as it has always been since its first appearance in 1838, an indispensable aid to one who would form a reasonably complete mental picture of the domestic life of classical antiquity.

Great condensation of material has, of course, been necessary; but the endeavor of the compilers has been to seize the salient points, and to furnish, within the prescribed limit of the volumes constituting this series, at least a fairly complete outline of a well-nigh inexhaustible subject.

To facilitate the student's pronunciation of the many unfamiliar Latin names of objects which have necessarily been

inserted in the text, the quantity of all the long vowels has been so marked.

The illustrations have been taken chiefly from Rich's Dictionary of Classical Antiquities: a few from Baumeister, Seyffert-Nettleship, Becker, and other authors; but the source of each will generally be found indicated under the illustration itself.

An appendix has also been added containing tables of Latin weights and measures, and a Roman calendar; with approximate reductions to American measures and values, and to the modern method of computing time.

Wherever Latin authors have been directly cited by our German authorities, the references have been carefully verified. In some few cases other quotations, which appeared to ourselves peculiarly obvious and interesting, have been added; but our aim has been to insert in the present little volume just so many references to original texts as might serve to stimulate the literary curiosity of a youthful reader, yet not enough to bewilder and overpower him.

The chapter on agriculture alone has been compiled almost entirely from original sources, — Cato, Columella, Varro, and Virgil, — aided by a considerable familiarity with the rural life of modern Italy, and those farming processes of to-day, many of which differ so very little in essentials from those of Roman times.

H. W. P.

L. P. D.

LONDON, November, 1893.



# THE PRIVATE LIFE OF THE ROMANS.

---

## CHAPTER I.

### THE FAMILY.

THE first step toward making real to ourselves the life of the great Roman people must be to get a clear idea of the constitution of the family, and the relation and obligations of its members to one another. The family bond, in the eyes of a Roman of the best period, was a peculiarly strong and sacred one, and the worship of the *larēs*, or guardian spirits of the home — often conceived as the souls of departed kindred — and of the *penātēs*, or great gods, in their relation to private and family affairs, was the most vital and heartfelt part of his religion. The family was regarded as both the germ and image of the state. To furnish the state with citizens was a man's first duty. To be the last of one's line was a calamity and a curse. Family life, more especially rural family life, in the early days of the Roman commonwealth was plain and stern and pure, offering singular resemblances, in its spirit and some of its aspects, to the life upon their lonely farms of the first Puritan settlers of New England.

The father of the family was its sovereign in his own right (*suī iūris*). Wife, children, and slaves were his subjects. The legal power of the husband over the wife was expressed by the term *manus*. The bride of those primitive times was merely transferred from her father's rule to that of her husband: she ranked thenceforth as a daughter of her husband's house; she came *in manum suam*, — "into his hand."<sup>1</sup> Her property became his. He might not sell, and, so long as she remained faithful, he might not slay her, but these were the only limits to his power.

The *patria potestās*, or authority of the father over his children, was even more absolute, for it included far down into historic times the legal right to sell, to repudiate, or, in the case of deformed infants and superfluous daughters, to destroy his offspring at birth. When the father lifted the new-born infant in his arms (*tollere*), it was a sign that he acknowledged and would rear and provide for it. The power of the father over his sons and their children ceased only when he himself died or lost his rights of Roman citizenship, — a forfeiture which the Italians still express by the stern phrase *morte civile*, or civil death. The father's power over his daughters ended when they married or took vestal vows. The son also might be emancipated by becoming a *flāmen*, or priest, and in certain cases with tedious and complicated ceremonies, by mutual agreement between parent and child.

<sup>1</sup> The word *manus* was at first applied exclusively to the power of the paterfamilias over the females of his own family. Afterwards it came to be used more loosely, and was often confounded with *potestās*, his power over children and slaves; as we see from the words *ēmancipātiō* and *manūmissiō*.

Livy<sup>1</sup> gives an instance in the year 358 B.C., during the consulate of C. Marcius and Cn. Manlius, of a crushing fine imposed upon a father who had endeavored to evade the law forbidding a citizen to hold more than five hundred *iūgera*<sup>2</sup> of land, by emancipating his son and then sharing with him a thousand *iūgera*.

The authority of the master over his slaves, or *dominica potestās*, was also absolute; but it included, in theory at least, his full recognition of these as members of the family, and of his duties to them as such.

Every member of a Roman household, male or female, bond or free, appears to have had, even in the earliest times, the right to at least two names, his or her own individual appellation, and the genitive of the name of the sovereign father, husband, or master, as *Mārcus Mārcī*, Marcus son of Marcus, *Līvia Augustī*, Livia daughter of Augustus, *Mārcipor*, i.e. *Mārcī puer*, Marcus's boy, precisely in the sense in which the owner of negro slaves but lately used the same term. Later, but still early in republican times, we find the free-born Roman male possessed of three names: his own individual first name, or *praenōmen*, the name of the *gēns*, or great clan, to which he belonged, the *nōmen proprium*, or *nōmen gentilicium*, and a *cōgnōmen*, or surname, which more narrowly defined his family, that is to say, the particular branch or division of the tribe from which he sprung; for instance, Marcus Tullius Cicero, that is Marcus of the Tullian clan, and the family of the Cicerones — originally chick-pea or vetch-growers.

A boy-infant received his *praenōmen* on the ninth day after birth (a girl on the eighth); the child was at the

<sup>1</sup> Liv. vii. 16.

<sup>2</sup> See table.

same time purified by lustration, which included sprinkling with water by means of a branch of laurel or olive, the burning of incense, and the offering of sacrifice, a ceremony plainly pointing to the rite of baptism. But the name thus given was not legally bestowed, nor publicly recorded in the archives, until the boy received the *toga virilis* at the age of sixteen or seventeen, and was publicly proclaimed a citizen of the commonwealth.

The fact that the *nōmen gentilicium*, or name of the great patrician clan, belonged equally to the women, freedmen, and clients of a house, led to a great restriction in the first names bestowed at lustration upon its freeborn sons. At no period were there more than thirty in use; these, in the time of Sulla, had dwindled to eighteen, and even these were distributed by fixed custom among the different clans. Thus Cæso belonged exclusively to the Fabii and Quīntilii, Appius, and Decimus to the Claudii, Māmērcus to the Æmilii, and so on. After plebeians were made eligible to the consulate in 367 B.C., and subsequently to all the curule magistracies, the descendants of plebeians, who had held any curule office formed a class called *nōbilēs* or "known men" (like the Scottish *kent folk*). They were thus distinguished from the *ignōbilēs*, those whose ancestors had never held office, while yet they did not quite attain to the consideration of the patricians, or men of high descent. They acquired the right, however, on which if possible they laid more stress than the patricians themselves, of setting up in their dwellings the images of their ancestors, beginning with the first great office-holder,<sup>1</sup> and, in natural emulation of the patricians, they became quite

<sup>1</sup> This man was neither *nōbilis* nor *ignōbilis*, but *novus homo*.

as strenuous as they in limiting the number of first names which they bestowed upon their sons in infancy. Thus the Domitii were always Gnæus or Lūcius; the Bibuli, Gāius, Lūcius, or Mārcus; and so on. The *cōgnōmen*, or surname, usually in the first instance a kind of nickname bestowed on account of some personal peculiarity, like Nāso, the long-nosed man, Torquātus, the man with a torque or necklace, came to be specially prized by the patricians as indicating in most cases an earlier origin than that of the official nobility. On the other hand, the custom came in of taking new surnames to commemorate some special warlike achievement, like Africānus or Macedonicus,—this was called *cōgnōmen ex virtūte*,—or else upon adoption, when to the three names of the adoptive father was added the gentile name of the child adopted, with the suffix *ānus*. Thus Publius Cornelius Scipio Æmilianus was the son of Lucius Æmilius Publius, adopted by Publius Cornelius Scipio.

**A daughter's name** in early Roman, as in modern times, consisted of her father's gentile name (*nōmen gentīlicium*), that is to say, of the feminine form of it, preceded by a first name of her own,—like Paula Cornelia, Paula of the Cornelian *gēns*; and so long as the old-fashioned marriage rites remained in force, by virtue of which the wife became the adopted child of her husband's house, she assumed at marriage his gentile name, as women still do in Christian countries. But this did not always, or even often, imply a change, because the ancient marriages were usually made between members of the same *gēns*; and in later times, when matrimony had become rather a civil contract than a religious rite, the wife certainly did not take her husband's name. She was known

by that of her father's *gēns*, as Calpurnia, the wife of Cæsar, who was daughter of L. Calpurnius Piso Cæsoninus (a member of the *Caesōnia gēns*, adopted by L. Calpurnius Piso); or as Terentia, wife of Cicero. Even her own individual first name was little used, until a fashion came up, in the time of the empire, of appending it like a *cōgnōmen* to her own gentile name, as Vespasia Polla, Vitellia Rufilla. Sometimes, too, as a matter of family pride, a woman used both the *nōmen* and *cōgnōmen* of her father, like Cæcilia Metella; or one name derived from the father and one from the mother, like Annia Faustina. Only in late imperial times, did women of high distinction aspire to the use of three names, as Furia Sabina Tranquillina.

A slave, as has been said, was originally known only as his master's "boy," — *Mārcipor, Olipor*. The elder Pliny<sup>1</sup> supposes this custom to date from the time when men as a rule had only one slave. It lasted, however, down to the last days of the republic, and the freedman who took his master's first and gentile name must needs append to it the name of his own servitude, as Aulus Cæcilius Oliper; that is, Aulus, formerly the boy of Aulus Cæcilius. When, however, the number of slaves had multiplied enormously, by conquest as well as by natural increase, it became necessary to give individual names to slaves, and these were often royal or mythological names, as Pharnaces, Mithridates, bestowed half in derision, like the "Cæsar" and "Pompey" of the plantation hand; or they indicated the place from which the slave had come, like Ephesius. Now, too, the legal term *servus* replaced the homely and friendly *puer*, and Pharnaces, the slave of

<sup>1</sup> Hist. Nat. xxxiii. 26.

Publius Egnatius, was written *Pharnacēs Egnātiū Pūblii Servus*. When a slave passed by sale or inheritance to a new owner, he or she added to the name of the latter the *cōgnōmen* of the former owner with the suffix *ānus* or *āna*. Thus Anna Liviæ Mæcenatiana was Anna, the slave of Livia, formerly owned by Mæcenas. It then became customary for the freedman to take upon his emancipation both the *nōmen* and *praenōmen* of his former master, or occasionally, in the case of a highly prized slave, the latter paid his former servant the compliment of naming him after some friend of his own. Thus Cicero when he emancipated Dionysius, the tutor of his son, called him not Marcus Tullius Dionysius, but Marcus Pomponius Dionysius, after his dearly beloved Pomponius Atticus, who was also very fond of the accomplished slave. The freedmen of a woman usually took the two names of their mistress's father, as Marcus Livius Augustæ Libertus Ismarus.

All these rules, however, remained strictly in force only so long as the family bond continued to be virtually indissoluble, and the paterfamilias was the undisputed master of his household. In the last days of the republic, with the almost unbounded facilities for divorce, the great increase in the number of freedmen, and the extension of the rights of Roman citizenship to various classes of foreigners, great irregularities in the matter of names came in, affecting alike their inheritance, their adoption, and their arrangement. The *cōgnōmina* of distinguished men were used as *praenōmina*, like Africanus Fabius Maximus, Consul in 10 B.C.; or the several sons of one father would all receive the same *praenōmen*, but would be distinguished by different *cōgnōmina*, in which case



the eldest son usually bore his father's *cōgnōmen* unchanged, while the second son took his mother's gentile name with the suffix *ānus*. Thus Flavius Sabinus had two sons by his wife Vespasia Polla. The elder was called Sabinus after his father, the younger Vespasianus after his mother. Further confusion ensued from the increasing frequency of adoption for political and other purposes, and from the very natural desire of the descendants of a freedman to get rid of the name which was the badge of ancestral servitude. *Novī hominēs*, too, liked to assume names with historic associations, as the parvenu of to-day orders a coat-of-arms; or to make up in the number of their appellations what these lacked in dignity, in so much that we find persons in imperial times who claimed as many as thirty names, one of which would have to be selected for daily use. Finally, the introduction of Christianity brought in names of the order of Praise-God-Barebones, Deogratias, Quidvultdeus, which were declined like regular Latin proper names of the same terminations.

**A iūstum mātirimōnium**, or true marriage, could only be made between Roman citizens (for the woman also reckoned as a *civis Rōmāna*) of the legal age, not too nearly related, and with the full approbation of the fathers who might hold *patria potestās* over the bridal pair. The marriageable age was fixed by law at fourteen for the husband and twelve for the wife, but practically it was later, for the boy was never married before he had received the gown of manhood, and the girl but seldom before fifteen or sixteen. The prohibited degrees of relationship originally included all within the sixth; that is to say, all for which the Latin language had names, and



all which had the *iūs ōsculī*, or within which it was allowable for men and women to kiss.

Such rigid restrictions were especially needful in those early times, when it was so unusual for a man not to marry in his *gēns*, or clan, that he who failed to do so was said to *ēnūbere*, — to marry out, as a Quaker may marry out of meeting. As time went on, the rules relating to the marriage of kindred were much relaxed, and we gather from Livy<sup>1</sup> that after the time of the Second Punic war, relatives of the fourth degree, that is to say *cōsobrīnī*, or cousins german, might marry. When in the year 49 A.D. the Senate sanctioned the union of the Emperor Claudius with Agrippina, the daughter of his brother Germanicus, marriages in the third degree became lawful; but with these restrictions, that a woman might marry her paternal uncle (*patruus*), but not her maternal (*avunculus*), while a man might never marry his aunt, whether on the father's side (*amita*), or on the mother's (*mātertera*).

The marriage contracted under these conditions was of two kinds: the bride either came into her husband's *manus*, or she did not. In the first instance she passed completely out of her father's family and rule into that of her husband; she surrendered her patrimony and became one of her husband's legal heirs. In the second, she remained under the rule (*in potestāte*) of her father, and retained her own property and her right of inheritance in his estate. In the former case, according to Cicero,<sup>2</sup> she became a *māterfamiliās*, in the latter she was simply an *uxor*.

Marriage with *manus* was itself of three kinds. The

<sup>1</sup> Liv. xlii. 34. 2.

<sup>2</sup> Cic. Top. iii. 14.

most solemn and stately, and by far the most aristocratic, was the marriage by *cōnfarreātiō*, which may be compared for pomp of ceremonial to a Catholic wedding with pontifical high mass in a cathedral or collegiate church. Beside the private offerings and taking of auspices, which were seldom omitted in any sort of legal marriage, this included a public ceremony conducted by the Pontifex Maximus and the Flamen Dialis in the presence of at least ten witnesses, and it took its name from the *farreum libum*, or cake of spelt-flour, which was carried before the newly married pair on their return from the wedding ceremony and subsequently broken and eaten between them.

There remained marriage by *ūsus*, in virtue of which the wife came into her husband's *manus* by the mutual consent of both parties, after they had lived together for a year without interruption of more than three successive days; and the marriage by *coëemptio*, which, though usually accompanied by domestic religious rites, as a modern wedding may be solemnized by a clergyman in a private house, must still be looked upon in the light of a civil contract. In this case, the father went through a form of emancipating his daughter, in favor of her future husband, after which the girl made declaration that she entered into the union of her own free will.

*Cōnfarreātiō* was the oldest as well as the most dignified and imposing of the Roman marriage rites. It was long the exclusive privilege of the patricians, and none but the children of such a marriage could ever become *flāminēs māiōrēs*, that is, priests of Jove, Mars, or Quirinus, or vestal virgins. Naturally, therefore, marriage by *cōnfarreātiō* would be the favorite form in the highest social

circles. Marriage by *usus*, as the simplest and least costly, would prevail, roughly speaking, among the plebeians, while the civil marriage by *coemptio* was the one commonly practised by the intermediate classes. But it is plain that with the loosening of the marriage tie, and the progress of what would now be called "advanced ideas," the solemn and ceremonious marriage by *cōnfarrētiō* went more and more out of fashion; so that Tacitus says<sup>1</sup> that in the time of Tiberius (A.D. 14–37) it had become a matter of some difficulty to find men qualified by their birth to fill the vacancies in the great priestly offices.

Marriage was regularly preceded by betrothal rites (*spōnsālia*), and children might be betrothed by their parents long before they were of marriageable age. The engagement might be broken by either party or by the guardians of either, without involving any legal penalty, but while it lasted it imposed certain restrictions. Betrothed people might not testify against one another in the courts, and a son might not marry his father's betrothed bride. The ceremony of betrothal was at first very simple. The amount of the girl's dowry having been agreed upon, the boy bridegroom gave his bride a piece of money or a ring, which she wore upon her third finger. It was only in the later imperial times that written marriage contracts were customary, and the ceremony took place in the presence of invited guests and was followed by a banquet. There were very strong restrictions touching the days of the year when weddings might take place. The whole month of May was forbidden and the first half of June, on account of the great

<sup>1</sup> Tac. Ann. iv. 16.

number of religious festivals occurring in the early summer and requiring the constant attendance of the priests. Nor could marriages be made on the *diēs parentālēs*, from the thirteenth to the twenty-first of February, when there were memorial services for deceased kindred, and offerings to their *mānēs*, nor on the three days of the year when the underworld was supposed to stand open, — namely August 24, October 5, and November 8, nor on the Kalends, Nones, or Ides of any month. Religious holidays in general were considered inappropriate for the marriage of young girls, though widows often chose them.

On the night before her bridal, the maiden laid aside her *toga praetexta*, a simple tunic, edged with purple if she were of patrician rank, and made up apparently width-wise of the cloth; her mother dressed her for the first time in a long white garment with vertical seams, called a *tunica rēcta* or *rēgilla*, and confined her flowing hair in a scarlet net. The true wedding gown, which she would assume upon the morrow, was also a white *tunica rēcta*,



Flammeum  
(Rich).

gathered in at the waist by a woollen girdle which was tied in a *nōdus Hercules*, or true-lover's knot, supposed to be a charm against the evil eye. The *flammeum*, or wedding veil, was of thin, fine stuff and of a brilliant orange red, or flame-color, very ample, first thrown over the head from behind, and then draped gracefully about the person. The girl's hair was also dressed in a peculiar manner for her wedding. The bridegroom himself must divide it into six

strands or tresses, with the point of a curved spear, called the *hasta caelibāris*; ribbons or fillets were bound

between the tresses, which appear afterwards to have been braided and confined to the head. Above the braids and under the veil, the bride wore a garland of natural flowers gathered by her own hand; and the bridegroom also, at least in later times, always wore a chaplet.

The wedding ceremonies proper began in the stillness of the early morning with the taking of auspices; and this was usually done by an *haruspex*, or professional diviner, who was not a minister of the state religion. A victim was then slain for the wedding sacrifice, generally a sheep, and its skin was spread over the stools or chairs, on which the bridal pair was to sit during a portion of the religious rites to follow. The guests now assembled, the marriage contract was accepted in the presence of ten witnesses, and the bride signified her willingness to come into the *manus* of the bridegroom, and, at least theoretically, to assume his name, by repeating the very ancient formula,<sup>1</sup> "*Quāndō tū Gāius, ego Gāia,*" you being Gaius, I am Gaia." The right hands of the pair were then joined by a *prōnuba*, who must have been but once married; and it would seem from existing bas-reliefs, as well as from the rather obscure testimony of ancient writers, that the wedding party then adjourned to some temple or public altar, where an offering—in ancient times it was a bloodless one of spelt-cakes and fruit—was made to Jupiter; and the *flāmen diālis* offered prayers to Juno as the patron of marriage, and to Tellus and other gods of the soil. During the offering the bridal pair sat side by side; during the prayers they moved slowly around the altar accompanied by a servant

<sup>1</sup> Becker thinks that this formula was not pronounced until the wedded pair had entered their new home.

(*camillus*) who bore a basket (*cumera*) which contained the *ūtēnsilia* of the bride,— probably her spinning imple-



Camillus, with Acerra  
(Rich).

ments and marriage gifts. A great feast, usually at her father's house, followed and lasted until nightfall. Then came the *dēductio*, or leading home of the bride. She was removed with a feint (sometimes, perhaps, it needed the reality) of force, from her mother's embrace, and led to her place in the nuptial procession, which was followed, first by the invited guests, and afterward, in most cases, by crowds of the common people. Torch-bearers and

flute-players preceded the bride, and the whole company joined in singing *Fescennīna*, primitive and rather coarse marriage songs, probably so called from the immemorially ancient Etruscan town where they had originated. The *gamins* of the streets flocked about the bridegroom, calling for largess of walnuts as a sign that he himself had put away childish things; while the bride was escorted by three youths, who must be the sons of living parents (*patrimī et mātrimī*). One of these carried her rock and spindle, while the other two bore torches. The bridal torch was not, as other torches, of pine or fir, but must be made of the wood of the white thorn, which was sacred to Ceres, and a talisman against all kinds of harm. There was a contest for the possession of it, among the guests, after the wedding was over. Arrived before her new home, the bride anointed its door-posts with oil and wound them with woollen bands. She was then lifted over the threshold, a reminiscence perhaps of the rape of the Sabine women, and received from her husband in



the *ātrium*, or chief living-room of the dwelling, the symbolic gifts of fire and water. According to some authorities, the two then knelt together and lighted their first hearth-fire from the white-thorn torch. It is certain that the bride said a prayer for married happiness before the symbolic bridal couch, which stood in the *ātrium*, opposite the entrance-door, and which had been previously decked by the *prōnuba*. A supper called the *repōtia* was given by the young people to their relatives on the day after their wedding, on which occasion the bride made her first offering as a matron to the household gods.

The union thus formed and sanctioned by the divine blessing was at first, and indeed for a long while, regarded as indissoluble. It assured to the Roman matron a very noble position; she was subordinate to her husband in their relations with the world, but her sway inside the home was undisputed. Her spouse, no less than her children and servants, addressed her as *domina*, or lady. No servile work was ever expected of her; but so far from being confined to one quarter of the dwelling, like the Græek women, she moved freely through it, overseeing all its activities and arrangements, the preparation of meals, the spinning of her maidens, the lessons of her children. She received her husband's guests, and sat with them at table, while the children, and sometimes even favorite slaves who had been born and reared in the house (*vernae*), were served at a sort of side-table in the same room. It was not thought seemly for a Roman matron to go out without her husband's knowledge or unattended, but upon these conditions she was free to walk abroad; place was deferentially made for her in the public ways, and the *stola mātērōnālis*, or peculiar outside

garment which she wore, was supposed to be a protection from all discourtesy. She attended public games and theatrical representations; her testimony was received in the courts. She might even plead for an accused relative. If she came of a very noble race, she was entitled to a funeral sermon or public oration of eulogy after her death.

Such was the ideal wifehood of the good old Roman times; and there is a sense in which it may be said always to have remained the ideal. Everybody knows that the mother of the Gracchi and the wife of Marcus Brutus were ladies of austere fashions and immaculate minds. Nay, even as late as the fourth Christian century we find St. Jerome endeavoring to shame some of the more lawless lambs of his flock, by examples of private rectitude and dignity in the first pagan families.

But long ere that time the prevalent manners had fatally deteriorated. ✓ The institution of domestic slavery, the license consequent on the servile and civil wars, the enormous increase of wealth, and the habits of Eastern luxury which came in with the Punic and other wars of foreign conquest, all these were prolific sources of corruption; while the study of Greek philosophy, which was affected by the clever women equally with their lords, promoted the growth of novel ideas, and rendered the "daily round and common task" of the olden time particularly irksome. ✓ Marriage with *manus* and religious rites went more and more out of fashion, except for the priestly caste; marriage upon any terms was avoided by many. Divorce, on the other hand, became of daily occurrence, and could be had on the most frivolous pretexts, as the lives of the Romans whom we know most



intimately, Cæsar, Pompey, and their great contemporaries, only too plainly show. Strenuous efforts were made by Augustus to restore the old standards of domestic morality, and in certain matters of personal indulgence he himself, after he was firmly seated on the imperial throne, set an honorable example of simplicity of life. He established penalties for celibacy and rewards and immunities for the fathers of three or more legitimate children; but these remedies were applied too late to arrest the inevitable progress of social decay.

Before proceeding to describe more minutely the daily habits of the Romans, and the houses in which they lived, we will add to our account of the old-fashioned marriage ceremonies a description of the rites of burial.

**Nearly all we know of the funerals** of the earliest historic period is that they invariably took place by night.

Later, when there had come to be much emulation in the matter of funeral expense and display, the obsequies, at least of distinguished people, were often celebrated in the daytime, and it was reserved for the Emperor Julian to prescribe a return to the solemn custom of old, by an edict beginning with the simple words,<sup>1</sup> "Death is rest, and night is the time for rest."

The lighted torch always held its place in the ceremonial, as it does for the most part in Latin countries to this day, and thus it became the symbol both of wedding and of burial. Grand public funerals were the exclusive privilege of eminent men and the scions of the great families; and the funeral procession was so arranged as to afford an opportunity for the most pompous exhibition of wealth, political honors, or long descent. Even as

<sup>1</sup> Cod. Theod. ix. 17.5.

early as 451 B.C. there were laws inscribed on the tenth of the Twelve Tables, limiting the sum which might be expended on incense for burning before the bier, and flowers to be heaped upon it, on the grave-clothes, which were often of extraordinary splendor, on the construction of the funeral-pile (*rogus*) in cases of cremation, on the number of musicians, and the luxury of the funeral feast. In the time of Sulla, further sumptuary laws were passed to the same end. The *aedilēs* were required to exercise a kind of police duty in clearing the way for the procession, and the fire-brigade had to be in attendance in the narrow streets of tall, wooden-roofed houses, to prevent accidents from the flaring torches, as well as to stand guard over the ignited pyre. All these precautions were, however, wildly disregarded in the case of Sulla's own costly and ostentatious funeral.

When a man of rank, whether a patrician or one of the official nobility, had breathed his last, his eyes were closed



Conclamatio.

by the nearest of the relatives present, while the rest lifted up a cry called the *conclāmatio*, in the forlorn hope of awakening him should he merely

have fallen into a trance. The friends then retired, and the body was left in the hands of professional undertakers, or *libitinārii*, who washed, anointed, and clothed it richly, set between the teeth—at least from very early times—the coin to pay Charon, the ferryman of the Styx, and laid it on a couch of state in

the *ātrium* of the dwelling, with feet turned toward the entrance door. Incense was kindled all about, either in trays or on miniature altars (*acerrae*), and flowers were used in profusion. The insignia of office of the deceased, if he had filled public offices, were all displayed, and also the crowns, if any, which he had won in the public games, or which had been decreed him by the Senate for triumphs upon the sterner field of war. Boughs of cypress or pine were then hung up in the vestibule as a token of mourning, and the lying in state lasted from three to eight days, during which time the corpse was visited by kindred, clients, and friends. If the interment or cremation were to be private, the remains were then quickly taken away (*fūnus tacitum* or *plēbēium*). Otherwise a herald summoned those who were expected to join the procession by the solemn and very ancient formula, "*Ollus Quiris lētō datus. Exsequiās quibus est commodum, ire iam tempus est. Ollus ex aedibus effertur.*" "This Roman citizen is surrendered to death. It is now time for the fitting guests to attend his burial. He is carried forth from his house."<sup>1</sup>

The order of the procession was then arranged by a master of ceremonies, called a *dēsīgnātor*. It closely resembled a triumphal march. A band of music went before with trumpets, pipes, and horns (*tubae, tibiae, et cornua*); then came always in ancient times the hired female mourners (*præficiae*), intoning an elegy (*naenia*) on

<sup>1</sup> *Ollus* is merely the ancient form of *ille*. *Quiris* is the obsolete singular of *quirītēs*, the Roman in his civic capacity, or member of one of the thirty *cūriæ*. From association with this mortuary proclamation, the word *quirītātio* came to signify a shriek or sorrowful cry.

the deceased; next, exactly as in a triumphal procession after a victory in the circus, came dancers and mimes, to whom a singular freedom of speech and action, even of jest, was allowed. In the fourth place, came the most significant and imposing part of the whole stately ceremony, the procession of ancestors in their *imāginēs*, or likenesses. When a man of note died, **a wax mask was immediately taken of his features**, and colored in exact resemblance to his look in life and health. This mask was affixed to a bust of wood or marble, enclosed in a marble or alabaster shrine with doors, usually shaped like a miniature house, and set up in the hall of the deceased. On the days appointed for the commemoration of the dead, these shrines were opened, and the busts crowned with flowers; and the greater the number of shrines, of course, the longer and more illustrious the line which they represented. On the occasion of a public funeral, these wax masks were removed and worn by professional actors, hired for the occasion, who might resemble the distinguished dead in stature, and would strive further to impersonate them in speech and action. The dead man seemed thus to be accompanied and ushered to his rest by a guard of honor, composed of all his famous forbears, nor was family pride always content with the images of historical personages merely, but mythical ancestors were also introduced, and Tacitus tells us<sup>1</sup> that Æneas and all the kings of Alba Longa figured in the funeral train of Drusus. The same great writer gives one of his most thrilling descriptions<sup>2</sup> of the grand funeral sixty-four years after the battle of Philippi, of the aged Junia, niece of Cato, wife of Cassius, and sister

<sup>1</sup> Tac. Ann. iv. 9.

<sup>2</sup> Tac. Ann. iii. 76.

of Marcus Brutus: "The images of twenty most illustrious families were carried before her," he says, "but Brutus and Cassius were conspicuous," — nay, his word is stronger, *præfulgēbant*, — "were illustrious, by their absence," being still under attainder on account of their complicity in the death of Cæsar.

After the ancestors, followed the memorials of the dead man's public achievements; if he were a general, the spoils he might have taken in war, and pictures of the cities he had subdued. Then came torch-bearers and lictors with lowered fasces, and, after them, the body itself, extended and exposed in rich garments upon a lofty bier, covered by a magnificent pall, and either borne by sons of the deceased or by slaves who had been set free in his will; or else it was enclosed in a coffin (*capulus*), which was surmounted by a sitting effigy of the deceased arrayed in robes of state. Last walked the mourners, all in black in early times, though white was afterwards allowed to women. The latter wore no ornaments; the men were without fasces, rings, or any insignia of office. The sons went with veiled faces; the daughters unveiled, but with streaming hair. Then came freedmen and slaves manumitted by the will of the deceased, — the latter with shaven heads, — clients, friends, the public generally, just as in a funeral of to-day. Custom imposed no check upon the expression of grief, and flowers and severed locks of hair were freely scattered upon the passing hearse or bier.

If there were to be a public oration, the funeral procession moved first to the forum, where the speech was delivered. Such an oration had to be authorized by a decree of the Senate, and the speaker addressed himself

to the general assembly of *Quirītēs* ("Friends, Romans, countrymen") rather than to the relatives of the deceased. In other cases an informal eulogy was spoken at the place of interment and addressed to the mourners only. It is not certain that any woman of republican times was ever honored by a formal public oration, save those of the Julian *gēns*. The great Cæsar we know made his *début* as an orator, at the age of eighteen, in the eulogy of his aunt Julia, the widow of Marius. Under the empire, however, the practice became common for the women of the reigning family and all others of high fashion or distinction.

From the forum the procession passed on to the place of interment or cremation, which was, with rare exceptions, outside the city walls. All the great highways leading out of Rome had come, in the last centuries of the state, to be lined with family tombs, the vast extent and infinite splendor of some of which may still be judged from the Castle of Sant' Angelo, which was the mausoleum of the Emperor Hadrian, and from the impressive ruins which border the desolate old Via Appia. Some noblemen had private burial places of great beauty, shady with trees, or gay with flower-beds and fountains, enclosed upon their suburban estates; and slaves and other dependants of the family were laid, humbly indeed, and at a respectful distance, but within the same precinct as their betters. The tomb was conceived as at least the temporary dwelling-place of the dead, and often very richly furnished. The walls were frescoed; there were lamps and candelabra, for both illumination and decoration; vases of beautiful shape and workmanship, over and above the cinerary urns, were








TOMB OF CÆCILIA METELLA ON THE VIA APPIA.



tastefully disposed around about. The warrior had his weapons beside him, the civic officer his badges, the great lady her ornaments and toilet articles, the child its toys. All these things helped to give the tomb a home-like appearance, both on the grievous day of burial, and on those subsequent days when religious services were held there in memory of the dead. The remains were either simply deposited with the couch, or *lectus*, on which they had been carried to the grave, or they were enclosed in one of those sculptured sarcophagi of which so many beautiful examples are still to




Sarcophagus.

be seen. The religious rites which followed, called the *fēriæ dēnicālēs*, included both a consecration of the new resting-place and a purification of the bereaved relatives, from their contact with death. A nine-days mourning — the *novēdiāl* — ensued, and was concluded by an offering to the *mānēs*, and a funeral feast, — the *cēna novēdiālīs*, — after which the mourning robes were laid aside, and the ordinary activities of life resumed. If there were funeral games, these too were originally celebrated on the ninth day.

In cases of cremation, the simpler and probably older fashion was to excavate a grave some three and a half feet deep, and fill it with fuel. This was a *būstum*; the corpse was extended on it, the fuel kindled, the bones

and ashes fell into the cavity with the coals of the dying fire, and the former were subsequently collected in an urn, which was set in the midst of the ashes. The earth was then filled in and heaped above in a *tumulus*, and the place was enclosed. These were the "vile obsequies," to use the expression of Tacitus,<sup>1</sup> accorded by Nero to his mother Agrippina, and the historian tells furthermore, to the shame of the Emperor, how the body was burned with indecent haste upon a dining-couch, on the very night of the murder, and how the spot remained for years



Rogus.

unencloded and uncared for. Cremation upon the *rogus*, or funeral pyre, was a much more stately and costly affair. This took place upon unconsecrated ground, but near the family burial place. The *rogus* was often of elaborate and artistic construction, and all manner of articles of luxury, spices, garments, ornaments, and rich wares of every kind, were laid thereon by friends, as last gifts to the deceased, and consumed in the general conflagration. The coals were then quenched with water or wine, a few days' exposure to the Italian sun and air sufficed to dry the ashes, which were collected in an urn or other *cinerarium*, and deposited in the tomb before the end of the nine days' mourning.

Such were the obsequies of the rich and great. The masses laid their dead away silently, as they have done in all times, and we have already seen that *fūnus tacitum* and *fūnus plēbēium* were interchangeable terms. For the comparatively well-to-do there were those vast systems

<sup>1</sup> Tac. Ann. xiv. 9.





COLUMBARIUM.

of *columbāria*, or rows of super-imposed niches, like the nests of a dove-cote, associated chiefly in our minds with their hallowed usage by Christians in the catacombs, but originally a pagan fashion, dating from early Roman times. The *columbāria* were often constructed and owned by joint-stock companies, who undertook to keep them in order and sold or let the separate niches as required. Or a great nobleman would build a *columbārium* for the reception of his slaves, by way of adjunct to the family tomb, as may still be seen in the burying-place of the Volusii near Perugia. For the very poor there were simply vast common pits (*puticuli*) into which the bodies were flung uncoffined, while the bodies of malefactors, even in Horace's time,<sup>1</sup> were exposed unburied to the action of the elements, and to the birds and beasts of prey.

All through the republican period, and probably in yet earlier times, a vast common burial place extended outside the Viminal and Esquiline gates of Rome, covering, roughly speaking, the space now occupied by the railway station and the new quarter beyond it. Mæcenās appears to have been the first to appropriate to private uses a portion of this ancient cemetery, which he transformed into a garden or park. His example was followed by Pallas, a freedman of Claudius, and by others, until the whole region became a place of gardens like the Pincian hill, and the recent dead were probably pushed further afield.

As between burial and cremation, the former was the ancient Oscan and Latian practice, and the innate prejudices of the Latin race appear always to have been in its

<sup>1</sup> Hor. Ep. i. 8, 17.

favor. In semi-Greek Etruria, on the other hand, as may be seen in great numbers of existing tombs, the two customs flourished side by side, and they did so in Rome, certainly from an early historic period. The expansion of the city and the vast increase of its population created powerful sanitary reasons in favor of cremation; but certain great families, like the Corneli, stood out against it to the end. The underlying thought in burial seems to have been that of deep rest on the bosom of the common mother; — in burning, that of consuming the corruptible flesh in sacrifice, while the spirit ascended in vapor to the heaven out of which it came. The latter idea seems at first sight the more pious of the two; but their full belief in the resurrection of the body caused it to be rejected by the early Christians, and with the conquest of the Roman Empire by Christianity the burning of man's mortal remains went wholly out of use.

**It remains to say a word concerning Roman feasts and services** in commemoration, one might almost say in worship, of the dead. These were numerous and religiously observed, some public and some private. To the former belong the *parentālia*, celebrated on the *diēs parentālēs*, or days of kindred, which lasted from the thirteenth to the twenty-first of February inclusive. They began with a service of the vestal virgins at the grave of Tarpeia, and while they lasted the temples were closed, magistrates laid aside their badges of office, and weddings, as we have seen, might not take place. We seem to hear an echo of the priestly functions performed on these occasions, in the voice which weekly in every Roman Catholic church entreates the charity of common prayer for the dead "whose anniversaries occur about this time." Over

and above these public rites, there were many private services in memory of the departed, feasts, like the so-called *rosālēs*, occurring in the spring or early summer, when flowers are most abundant, where friends were invited to a simple funeral banquet of bread and wine, eggs and vegetables at the tomb of the deceased; and roses or violets, as the case might be, were distributed to the guests to be laid upon the grave, and offerings were made there of water, wine, warm milk, honey, or oil. There exists a fragment of a *cippus* or funeral stone, the inscription upon which provides that the sleeper shall be commemorated by sacrifices four times each year; namely, "on the anniversary of his birthday, on rose-day, on violet-day, and during the general *parentālia*," and that a lamp shall be lighted and incense burned at his tomb on the Calends, Nones, and Ides of every month.





## CHAPTER II.

## THE HOUSE AND EVERY-DAY LIFE.

The ordinary Roman dwelling-house had always been, even to the scholar, somewhat of a mystery, until the discovery of Herculaneum and Pompeii, in the middle of the eighteenth century, suddenly threw a good deal of light upon its construction and arrangements. The silent testimony of those partially ruined and long buried homes was all the more valuable because, in Pompeii, especially, they represented the average middle-class dwellings of a provincial town, commodious and even elegant as compared with the farm-houses and cottages of the rural poor, cramped and insignificant beside the costly city mansions, and the yet more extensive and extravagant mountain and seaside villas of the wealthy nobles.

The one essential feature of all these houses, the central point and distinctive mark of the Roman dwelling in all its developments, that which distinguishes it from the Greek and the houses of the farther East on the one hand, and, on the other, allies it with the houses of our own race, was the *ātrium*, long the common living-room of the entire family. The earliest Roman houses may indeed be said to have been all *ātrium*. Here, within the same four walls were assembled the family hearth and altar, the family portraits in wax and the marriage-






STREET SCENE IN POMPEII.

bed, here the meals were cooked and served, the men lounged after labor, and the women span; the very name is probably derived from the black (*āter*) color imparted to the room, and its contents generally, by the circling smoke of the hearth fire, which had to find its way out by open door or perforated roof, since it is certain that down to comparatively modern Roman times chimney-flues were unknown.

The houses thus occupied were small and detached even in the more considerable towns. They were built of wood, or, later, of brick, mostly square in shape, and roofed with wood or thatch, carried up to a point (*culmen*) in the form of a four-sided pyramid; while a yet meaner sort, circular in shape, with conical roof and built of wattled reeds, is still represented by the miserable shelter-huts of the shepherds on the Roman Campagna. It was the typical early Roman house which Virgil conceived as the palace of Evander on the Palatine hill, in the beautiful passage,<sup>1</sup> where he tells how the pauper king was awakened by the light of early morning streaming through the door of his cot, and the singing of birds upon its low roof-tree. Such, too, was the so-called



Sepulchral Urn in form of Primitive House.

*Casa Rōmulea*, long preserved as a kind of sanctuary on the northwesterly slope of the Palatine. But however primitive and promiscuous the life led in these plain dwellings may appear, it was not necessarily vulgar nor

<sup>1</sup> *Æn.* viii. 455 *seq.*

lacking in a certain dignity, as those will readily understand who have entered the common room of a *podere*, or farm, upon the Tuscan hills, or a hospitable farm-house kitchen in Old or New England.<sup>1</sup>

Having thus gotten some idea of what constituted the kernel of a Roman dwelling, let us see what the ordinary town-house had become in the latter days of the republic.

**Its entrance-door** did not open directly from the street, but at the end of a passage called the *ōstium* or *aditus*, paved with tiles and flanked by rooms which were usually let out as shops. The door was of wood, with pillars (*postēs*) upon either side. It had regularly two leaves, or *forēs*, which swung outward into the passage on an arrangement of pivot and socket called a *cardō*, and were secured, when closed, by bolts (*pessulī*) at the top and bottom. This door led sometimes into a short continuation of the passage, divided by a curtain from the *ātrium*, and sometimes directly into the latter, now often called the *cavaedium*, or hollow part of the dwelling, and still constituting its main apartment.<sup>2</sup>

<sup>1</sup> There are scores of verses in both Horace and Virgil which testify to the sentiment of fond reverence and unavailing regret with which the highly civilized and sophisticated writers of the Augustan age looked back upon the plain old-fashioned country-life. One of the finest of these is the exquisite passage near the end of the second Georgic, beginning with the incessantly quoted "*O fortunātōs nimium.*" Cicero says, however (*De Rep.* v. 2), what was doubtless the exact truth, that the men of his time for the most part looked back upon the old republic and its customs as on a noble but dilapidated picture which they no longer cared to restore.

<sup>2</sup> Becker and some others maintain that the *ātrium* and *cavaedium* were distinct rooms; but the latest authorities are against





HOUSE OF TRAGIC POET. POMPEII.



This developed *ātrium* was oblong in shape, and the centre of the floor was occupied by a marble cistern (*impluvium*), with pipes under the floor for carrying off the water. Above this, in the vast majority of cases, there was no roof at all. The tiled covering of the surrounding space was supported by strong cross-beams, and sloped inward upon its four sides for convenience in conducting the rain-water into the cistern below. This, the simplest kind of roof, and the one most employed, was called a *Tūscānicum*, or Tuscan roof. Sometimes a pillar was set at each of the four corners of the *impluvium*, where the beams intersected, in which case the *ātrium* was said to be *tetrāstȳlon*, or four-columned. Sometimes the beams were not extended to the wall, but merely supported by a row of pillars around the *impluvium*. This was a Corinthian *ātrium*. In other cases the *ātrium* was *displuviātum*; that is, the roof sloped outward, and the rain-water ran into gutters under the eaves and was carried off by pipes, as in a modern house; the whole system of roof and pipes being called, in any case, the *compluvium*. The last kind of roof alone was occasionally carried up to a point above the central basin, and the *ātrium*, thus completely roofed in, was called *tēstūdineātum*. How the *ātrium* was lighted in this case we do not exactly know. It is probable that the small flanking chambers, presently to be described, had no

them. Doubtless there were spacious houses with two halls, that is to say, with a sort of ante-chamber between the *ōstium* and *cavaedium*. Pliny's Laurentian villa we know was arranged in this way, but the progress of Pompeian excavation seems to have rendered it certain that the average Roman town-house had no such luxury.

second-story rooms above them, and that there may have been a row of windows or apertures under the roof, like the clere-story windows of a cathedral. In the far more numerous cases where the *ātrium* was lighted simply by the opening above the *impluvium*, there were always arrangements, as in the theatres, for drawing an awning, or *vēlum*, across the open space, as a protection from the sun. The *ātrium* in one or other of these forms was still the place where guests were received, where certain rites of domestic worship were celebrated, and where the dead lay in state. But the cooking was now done in a kitchen (*culīna*) at the back of the establishment, and the hearth-stone, where sacrifices to the household gods had been made in primitive times, was represented by a marble altar, set against the rear wall of the apartment.

On either side of the *ātrium*, down about two-thirds of its length, ran a row of small square rooms, the sitting, sleeping, and guest rooms of the establishment. These opened into the hall either by doors or portières, and from one of them ascended the steep and narrow stairs, which led to the upper story. Beyond this range of diminutive rooms, on either side, the *ātrium* broadened out into two *ālae*, wings or alcoves, in the comparative seclusion of which were now arranged the portrait busts of the ancestors in their several niches or shrines, and so ordered, in cases of long descent, as to present the semblance of a family tree; while bronze tablets, recording the names and deeds of the persons commemorated, were set in the wall beneath their respective shrines.

Between the two *ālae*, directly opposite the entrance-door, was the opening into the *tablinum*, which was usually divided from the *ātrium* by curtains only. In

old-fashioned country houses of the better sort, the *tablinum* had been represented by a sort of open porch or veranda, often a simple *pergula*, roofed by a trellis for vines, which ran all along the back of the modest dwelling, and led to the gardens or orchards behind it. Under the roof of this porch the rustic "Squire," to whom, as always happens, it fell naturally to enact the magistrate, heard complaints and decided differences between his tenants and humble neighbors; and the *tabulae*, or records of his decisions, were deposited there. Later, when the dwelling had considerably developed, and the simple back porch had become only one side of a quadrangular colonnade, surrounding an open court, the *tabulae* were removed to the interior of the dwelling, and the room where they were kept took its name from them, *tablinum*. In this, and the corresponding room of a town-house, other family archives came also to be deposited, and here were put upon record those curious contracts for mutual hospitality — *hospitia privāta*, — which will be described in another chapter. Here, too, stood the strong-box of the master of the mansion, and the *tablinum* was in some sort his study or den. It could be shut off from all the rest of the house, from the *ātrium* by the heavy curtain or curtains already mentioned, from the open court at the back by folding doors; and it was flanked by two narrow passages (*faucēs*) with doors at either end, through which the family and the domestic slaves could pass and re-pass between the *ātrium* and the rear portion of the house. But if the curtains in front of the *tablinum* were withdrawn, and the doors at the back thrown open, he who entered the house from the front had an uninterrupted, and, what must have

been on a bright day, a very charming view across the *ātrium*, filled with the diffused and softly colored light which filtered through the *vēlum* overhead, and down the vista of the *tablinum*, to the fountain, flowers, and shrubbery, which occupied the centre of the great pillared court, or *peristylum*, beyond.

The *peristyle* had now become quite as important a member of the dwelling as the *ātrium*. Whoever has seen the garden-court of an Italian villa or palace,<sup>1</sup> or a green convent or college cloister, and has also seen Pompeii, will have an approximate idea of the general aspect of a *peristyle*.

The ambulatory, or surrounding promenade, was much narrower than the covered part of the *ātrium*, the open space, of course, proportionally larger. From the *peristyle*, and usually on its right, opened the *triclinium*, or principal dining-room of the house, the neighboring kitchen, or *culīna*, and the *sacrārium*, or chapel, where the images of the gods were set up, and sacrifices and other ceremonies of private worship were actually performed; for the altar in the *ātrium* seems rather to have been a reminiscence of the hearth, and an ornamental symbol of devotion, than intended for frequent use.

From under the colonnade on the opposite, or left-hand, side opened storerooms of various kinds and a second stair which sometimes led to inferior sleeping-rooms upon the upper story. At the back of the *peristyle* there was usually an open garden.

Such being the typical arrangement of the Roman dwelling, there was room, as in our modern houses, for great variations of detail, and it is easy to understand

<sup>1</sup> The beautiful court of the post-office at Rome is a good example.





PLAN OF A ROMAN HOUSE. (After Ad. Schill.)



the sort of change which would be introduced by the increase of wealth, the adoption of Eastern fashions, and the enormous growth of private luxury. **To begin with the entrance:**—the shallow, sunken porch before the *ōstium*, formed by the projection of the shops on either side, would now be expanded into a spacious vestibule with marble floor, richly adorned with statues and portrait-busts, prizes of prowess and trophies of arms, even the state chariot which had borne the master of the house on occasions of public triumph sometimes found a place here; and it was here that the countless throng of friends, clients, and other *protégés* and dependants who hung upon the footsteps of a distinguished citizen in later days, waited, sometimes from before daylight, to give the *salūtatiō*, or morning greeting, to the great man when he came out. The plain door-posts were now sheathed with rich carvings (*antepagmenta*), or adorned with intricate and costly inlaid work.<sup>1</sup> There were no shops, of course, attached to houses of such grandeur; but the rooms on either side of the entrance became, the one a lodge for the *ōstiārius*, or porter, while the other was often used by the master of the mansion as a species of office, where he received and examined the accounts presented by the stewards of his various rural properties, and took the money for his valuable crops. The town-palace of an Italian nobleman has, to this day, a similar room upon its ground-floor used for almost precisely the same purposes.

The stately dwelling we are now considering had an indefinitely increased number of living, withdrawing, and guest rooms, opening off the *cavaedium* and peristyle.

<sup>1</sup> See Verg. G. ii. 463.




There were bedrooms for rest both by day and by night (*cubicula diurna* and *cubicula nocturna*) and dining-rooms with different exposures for summer and winter, and with dimensions to suit the various numbers of guests which might be entertained. There were often (we find instances even in provincial Pompeii) two peristyles, in which case the anterior usually gave access to a picture-gallery (*pinacothēca*) and a library (*bibliothēca*), the names betraying that the fashion was adopted from Greece.

The earliest private *bibliothēcae* were small and plain, seemingly intended as mere depositories of books, and not at all as luxurious retreats for study or literary recreation. The walls were lined with low cupboards (*armāria*) or cases of open shelves, for the reception of papyrus rolls; and sometimes a double row of such receptacles occupied the centre of the room. Not much before Cicero's time did men begin to vie with one another in the elegance of their library appointments, and to adorn the room with pictures and statues.

The substance on which the books of this time were written was almost invariably the fine bark (*liber*) of the Egyptian papyrus, of which the long fibres were first woven together basket-wise, and then spread upon some flat surface and pressed into the proper consistency. The sheet thus obtained was dried in the sun, smoothed, and cut into strips (*pāginae*), which were written upon one side only, glued together at the ends and tightly rolled over a hollow reed. The width of the strips varied from six to thirteen inches, and if a yet broader page were required it was made by gluing these together lengthwise, after they were written. The text was thus presented in parallel columns which were usu-

ally divided by scarlet lines. Through the hollow of the reed ran a rod (*umbilicus*), which furnished the axis on which the book turned in rolling or unrolling. The projecting ends of this rod were called the *cornua*, and they were often painted or gilded, or furnished with metal or ivory nuts. The ends of the papyrus roll itself were carefully evened and dyed black; and the outer covering was of parchment, which was colored in some brilliant hue, usually purple or yellow, while the title of the book was written in scarlet ink upon a small separate slip of parchment and attached to one of the *cornua*.

We hear of instances in which an entire work, like the Iliad or the History of Thucydides, was copied upon a single roll, that of the historian being more than eighty-eight yards long. But such a book would, of course, be too unwieldy for ordinary use, and the common way was to divide the works of a prolific writer into several rolls, or *volūmina*, which were all kept for convenience in one light cylindrical wooden box, a *capsa* or *scrinium*, somewhat resembling a modern band-box. The ink (*ātrāmentum librārium*) was rather thick, and made, like the ink of the Chinese, of lamp-black or sepia; the pens were slender reeds, or *calamī*, cut and pointed like a goose-quill. After parchment came into general use, the custom of rolling was for the most part abandoned, and the *pāginae* were simply fastened together at the back like a modern book. Such an arrangement was and is called a *cōdex*.




Writing Materials.

The domestic slaves were lodged in tiny cells around the posterior peristyle, rather than on the upper floor, where the regular sleeping-rooms of the family seem usually to have been. There would be extensive and beautiful grounds at the rear of such a mansion, laid out in the perpetual Italian taste, embellished with trellises, fountains, and statues, and often overshadowed by magnificent trees, like the six ancient and enormous lotus trees in the town-gardens of the orator Crassus upon the Palatine, which were valued at three million sesterces, or about \$20,000 apiece, and which lived and flourished until they were consumed by Nero's fire in 64 A.D.

In Rome and the larger towns, however, as in modern cities, especially those of the continent of Europe, the detached dwellings came to be far outnumbered by the *insulae*, or apartment-houses, which were often several stories high, with shops upon the street level, and lodgings of various grades behind and above. The crowded tenements of the very poor were to be found in the meaner of these *insulae*, while there were others in the more expensive wards (*regiōnēs*) where young men of fashion, like Cicero's friend Cælius, had commodious apartments, which probably corresponded very fairly with the bachelor quarters occupied by men of the same class to-day.

In trying to represent to ourselves more exactly the interior aspect of a completely appointed Roman house, we have first to remember the rich effect of its marble-wainscoted and frescoed walls; the broad panels of pure deep color, usually yellow or red, with graceful central figures, and surrounded by brilliant and delicate arabesques, which we find almost universal in Pompeii,





WRITING TABLETS, SHOWING INSIDE AND OUTSIDE.

even in houses of modest pretensions. There was color also and grace of design in the various kinds of mosaic floors, of which so many specimens are still to be seen, and though the furnishing of the rooms may seem simple and even scanty to our jumbled modern ideas, the separate pieces were for the most part so excellent in design and so beautiful in workmanship that they well deserved to be set wide apart and relieved, each one, against an artistic background.


**The articles of furniture** in common use may be comprised under a very few heads: *lectī*, beds and couches; *sedilia*, or seats; *mēnsae*, tables; *arcae* and *armārii*, chests and cabinets; *lucernae*, lamps, whether standing or depending.

Couches included the *lectī triclīniārēs*, or low dining-couches covered with tapestry and heaped with cushions, on which both men and women reclined at formal meals; the *lectī cubiculārēs*, true beds of rest, for slumber at night or siesta by day; and the *lectulī* or *lectī lūcubrātōrii*, which had commonly two arms and no back, and were used chiefly for reading or writing at night, when the student reclined his back against one of the arms and supported his tablet or manuscript upon one uplifted knee. And since it was thus that inveterate letter-writers like Cicero and the younger Pliny carried on most of their correspondence, this may be as good a place as any other in which to describe the form of the Roman letter.

**The tablets** in question were light, rectangular boards with slightly elevated frames, like a modern slate, and they were spread with a thin coating of wax, on which written characters were traced with a *stilus*, or pointed

stick of wood or ivory. One such tablet would serve for the jotting down of hurried notes, or for a schoolboy's exercise. A lengthy letter was composed of several, united at the back, like the leaves of a *cōdex* or a modern book, by means of straps or strings passed through holes in the frame. The inner tablets might be waxed and written upon both sides; the outer, upon the inside only. They were bound together by a strong cord, which for greater security was passed through one or more holes bored in the tablet itself; the ends of the cord were fastened down with wax, which was imprinted with the writer's seal, and the message was conveyed to its destination by a *tabellārius*, or letter-carrier. In later times these rather unwieldy tablets were superseded by sheets of papyrus.

The frames of the various kinds of couches were regularly made of wood, often carved or inlaid with



Lectus Cubicularis.

ivory or brass, and supported sometimes upon ivory feet. The frames were strung with girths or bands (*fasciae, lōra*), on which were laid a mattress (*torus*) and a bolster (*cervical*) and *vestēs strāgulae*, or coverings, of more or less magnificence.

Beds for slumber, though tolerably broad, were open for the most part upon one side only, being provided with a tall back and arms, like an old-fashioned sofa; and they stood higher upon their carved or elaborately turned legs than even the four-posters of our own ancestors, insomuch that they could only be scaled by



help of a footstool, or even a step-ladder. Bedsteads of bronze and even of the precious metals were used in later times; and seats and chairs were made of all these different materials and often decorated with great luxury, while in form they ranged from the simple *subsellium*, or four-legged stool, to the *cathedra*, or deep, commodious chair, like that in which the elder Agrippina may be seen sitting with so much grace and dignity in the museum of the Capitol at Rome, or Livia, the exquisitely beautiful, in the seclusion of the Torlonia gallery.

Under the general head of tables were included the *abacus*, or side-board, in shape somewhat like a pier or console table, the *mēnsa delphica*, or three-legged table, and the *monopodium*, supported on a single standard in the centre. Tables of the latter shape were often small, extremely precious in material, and elegant in design; and one such formed part of the furniture of every decent bedroom, and supported, from the time when candles of tallow or wax went somewhat out of fashion, one of the boat-shaped oil lamps of pottery or bronze, with gracefully turned handle (*ānsa*) at one end, and at the other an opening (*rōstrum*, *nāsus*) for the wick (*ellyphnium*), which abound in Pompeii and in existing tombs. A *candēlābrum* was a tall slender stand of wood or metal, usually provided with three claw feet which rested on the floor. In shape and size it corresponded with the standard of a piano-lamp of the present day, which, indeed, is often exactly copied from it. The *candēlābrum* carried atop either a small tray for supporting such a lamp as has been already described, or a spike for a large wax candle, like an altar candlestick.

A shorter kind of *candēlābrum*, often very elaborately wrought, stood upon a chest or sideboard, and had two or more branches from which small hanging lamps were suspended.



Bronze Lamp.

The chest and the cabinet offered, as they have always done, a favorable field for the most elaborate and costly decoration; and these massive articles doubtless possessed in a handsome Roman house exactly the importance which they still retain in grand Italian interiors.

**The table-ware** of the affluent had become, in the last days of the republic, extraordinarily luxurious. Something more will be said upon this head in the chapter on food. Here it may suffice to remark that, to judge by the revelations of Pompeii, almost every household implement in daily use at the time of the catastrophe had an artistic significance due to the beauty of its design, over and above its practical value. But the fashion of these articles was to some extent exotic. Their shapes were borrowed from the booty taken in foreign conquest, or else they were the handiwork of

Greek captives, or of artisans who had learned their methods from them.

In primitive Roman times the day was divided in the simplest manner, so as to meet the needs and facilitate the labors of the tiller of the soil. The husbandman rose at sunrise, worked a certain number of hours before his morning meal, returned to the field after this, and worked until noontide, when he ate again and slept awhile, arising refreshed for another period of labor in the cool of the afternoon, which lasted until sunset and supper-time. Relief to the monotony of this daily round came in the shape of numerous holidays, both public and private. To the former class belonged the general celebrations, bearing more or less of a religious character, like the *Compitālia* in January, the *Mātrōnālia* in March, the *Vīnālia Rūstica* in August, and the *Sāturnālia* in December; to the latter, all the birthday, betrothal, wedding, house-warming, and New Year's gatherings, with their appropriate suppers and sacrifices, and exchange of gifts and congratulations, as well as the reception given when a youth assumed the garb of manhood, and the banquets already noted in commemoration of the dead.

But with the rise of great towns, the growth of commerce and manufactures, the introduction of new industries, and of new diversions also, and the ever-increasing complexity and expense of existence, the old bucolic arrangement of the day passed wholly out of date, especially among the so-called privileged classes, insomuch that in the time of Nero we find a would-be philosopher like Seneca complaining<sup>1</sup> that, whereas human occupa-

<sup>1</sup> Sen. Ep. cxxii. 10.

tions used to be regulated by natural laws, now the object appeared to be to make one's habits as artificial as possible. Daybreak, he says, is bedtime. As evening approaches we begin to show signs of activity. Toward morning we dine. "*Nōn oportet id facere quod populus,*" "Come what may, we mustn't do as the common people do."

Up to the time when the first sun-dial appeared in Rome, 263 B.C., there was no division of the day into hours; and even after this the Romans continued to make a distinction between the natural and the civil day. The former was reckoned from midnight to midnight—twenty-four hours; the latter from sunrise to sunset—twelve hours. Practically, the period of daylight still fell into the four natural divisions established by the necessities of rural life, of morning, forenoon, afternoon, and evening; while the four military watches (*vigiliae*) measured the night. But in the course of the ensuing century, sun-dials (*sōlāria*) and hour-glasses (*clepsydrae*), whether for sand or water, came into general use; and some sort of time-keeper, or *hōrologium*—a name which comprised both dials and hour-glasses—was to be found, not merely upon all public squares and buildings, but in every private house. There was this great difference, however, between the Roman measurement of time and our own—an hour was not a fixed period of unvarying length. It was always considered as the twelfth part of the time from sunrise to sunset, and again of that from sunset to sunrise. The hours of a winter day were therefore actually short, while those of a summer day were long; the converse, of course, being true of the nights. At the equinoxes, when the days and nights

were of the same length, a Roman hour contained sixty of our minutes. At the summer solstice the hours of the day contained seventy-five and a half, and at the winter solstice forty-four and a half minutes. In the former case day began at 4.27 A.M., according to our reckoning, and ended at 7.33 P.M.; in the latter it began at 7.33 and ended at 4.27. This peculiarity must always be borne in mind, when one would fix in the memory the hour at which a given event occurred.

Seneca's lament to the contrary notwithstanding, **the Romans were for the most part early risers.** Only the idle and the very luxurious, or those who had to sleep off the debauch of the previous night, were wont to lie in bed even until broad daylight. Artisans and shop-keepers went to their work by candle-light. Men of letters, like Cicero, Horace, the elder Pliny, the Emperor Marcus Aurelius, preferred to all others the hours before sunrise for reading and writing. The schools began at a very early hour,<sup>1</sup> so did theatrical representations (*prīmā lūce*), and all the family festivals already noted; and in Christian times the daily morning service in the churches. The courts of justice sat from the third to the tenth hour; that is, roughly, from seven to five in summer and nine to four in winter. On the days of general election, the *comitia* began, or, as we should say, the polls opened at sunrise, and did not close till dusk. The sessions of the Senate also began early and continued till sunset.

In primitive times the master of the house expected to receive good-morrow from his children and servants

<sup>1</sup> "Up," says Martial, in the last epigram of his fourteenth book; "for the baker is selling the schoolboys their breakfast, and chanicleer proclaims the dawn."

at daybreak, after which he offered the morning sacrifice, and then assigned to his various people their duties for the day. A reminiscence of this custom appears always to have survived in certain of the old families, and it was adopted in the strictly ordered households of the Antonine Cæsars. Out of it grew the ceremonious *salūtātiō* of late republican and early imperial times, the self-interested compliments of the morning offered to an influential citizen by the clients and other lesser folk, who thronged his hall and competed for his favor; and the earlier the *salūtātiō* could be made, the better. We read therefore of the Roman streets being alive before light in winter with the hurrying figures of carefully attired clients, who elbowed one another in the stately vestibule of their patron, until the doors were flung open into the *ātrium*, where he stood to receive them. They then defiled before him, each making his bow and uttering his *avē, domine*, to which the magnate responded by a hand-shake and a word of courtesy — sometimes by a kiss. He made a point of addressing each man by name, and if he hesitated for one instant, he was prompted by the *nōmenclātor* at his ear, a slave whose business it was to know the proper appellation of every person present.

Before going through with this wearisome performance the patron had probably taken his *iēntāculum*, or first breakfast, in the privacy of his own chamber. The client would have to snatch his where he could in passing from one house to another, — for many paid their daily court to more than one great man, — often doubtless in the bakeries or cake-shops patronized by the schoolboys. **This first meal of the day** was invariably, as it still is in Latin countries, a very simple one. It



consisted of bread with salt, or dipped in wine, olives or dates, possibly honey, and a bit of cheese. Hearty food, such as warm and cold meats, fish, vegetables, fresh fruit, and wine, was rarely taken much before mid-day. In early times, and always among the farming population, this mid-day meal constituted the *cēna*, the dinner, or principal meal of the day, while a supper, or *vesperna*, was served in the evening after work was done. The exigencies of city life caused the noon *cēna* to be replaced by the *prandium*, lunch or second breakfast, consisting indeed of much the same sort of viands, while the dinner, or *cēna* proper, became vastly more elaborate, and was deferred until toward evening.

Three meals a day were perhaps the rule among the well-to-do, yet physicians often counselled only two, except for the old and weak, and many city-folk — even the comparatively affluent — confined themselves to a *prandium*, taken about eleven o'clock, and a late *cēna*. The natural Roman appears to have been, like the average Italian of to-day, an abstemious creature. Only the wanton and extravagant *gourmands* of the decadence dreamed of adding to the interminable courses and fantastic luxury of their *cēna* a late supper, or *cōmissātiō*, served often in the “wee sma’ hours ayant the twal’.”

After the *prandium*, the world retired for its *merīdiātiō*, or **mid-day slumber**. This custom was well-nigh a universal one. It belonged both to city and to country life, and dated from the earliest historic period. Only the Senate and the courts took no recess at noon, and even there we may believe that, save in times of high excitement, business went on but drowsily. It was during this hour of general repose, which, by the way, was




deemed only less favorable than midnight for the seeing of spectres, that Alaric surprised Rome in the year 410 A.D.

Refreshed by his *merīdiātiō*, the Roman of highly civilized times rose and proceeded directly to **that capital event of the day, his bath.** The ringing of a bell announced the opening of the great public baths, *balneae* or *thermae*, but it does not come within the scope of this work to describe minutely these characteristic institutions of ancient Rome. They were vast in extent, intricate in structure, and enormously costly, and they tended, as time went on, to become always more and more artistic and luxurious in their arrangements. Yet the price of admission, even to the most splendid of these establishments, was so trifling that they were virtually open to all, — a *quadrāns*, or quarter-*as* (that is to say less than one cent) for a man, and two for a woman, while children as a rule were admitted free.

There were usually separate departments for men and women, but there were porticos and gardens adjoining all the great *balneae*, where bathers of both sexes might meet and gossip after the bath was over, as in the casino of a modern watering-place; and to the *thermae*, at least, were often attached libraries and fine art galleries, *palaestrae* for gymnastic exercise, and *sphaeristēria*, or courts for playing ball.


The plain, private dwelling of an earlier period had possessed merely a common *lavātrīna*, or wash-room, situated near the kitchen for convenience of introducing both hot and cold water, and where the different members of the family took turns in performing their simple ablutions. But subsequently, after the bath had come to





FRIGIDARIUM OF THE BATHS OF CARACALLA. (After A. Gnauth.)

be regarded as the greatest of luxuries, it was customary to have a *balneārium*, or miniature bathing establishment, somewhat on the plan of the great *balneae*, attached to every private house, and especially to every country house having any pretensions to splendor. Traces of such are to be found all over Europe, wherever the Roman rule extended, for Roman governors and other high officials made a point of carrying with them into their provincial exile the personal habits of the capital. A private bath of this kind, small but remarkably well



Roman Bath, after ■ drawing of the 16th century.

preserved, dating from the time of Constantine the Great, was discovered in 1855, at Caerwent, in Wales, and may be taken as a type of them all. It was very nearly square in shape, and its entire dimensions were only thirty-one Roman feet by thirty-four. The included space was, however, divided into the usual rooms, or *cellae*,—viz. an *apodytērion* for undressing, a *tepidārium* provided with seats for the hot air or vapor bath, a *caldārium* with a large tub for the hot-water bath, and a *frīgīdārium* for the cold-water bath.

A bather was twice rubbed down by attendant slaves,

once after the vapor or sweating bath, and again after the cold bath, and after the latter he was also anointed. In more elaborate establishments there were separate rooms for these processes, the *dēstrictārium* and *ūnctōrium*.


The private bath in question was heated on the same principle as the great *thermae*, that is to say, by means of a furnace (*hypocaustum*, *fornāx*) provided with pipes, through which heated air was conducted underneath the floors and between the walls of the different rooms. The floors were double, the upper one being supported on pillars of clay piping about two feet high. The intervening space was made intensely hot, and the whole ingenious arrangement was termed a *suspēnsūra*, and is claimed by Cicero as the invention of one of his own early friends, Gaius Sergius Orata. The heat was graduated for the different *cellae* by their relative distance from the central furnace, and the varying thickness of their upper floors. The *caldārium* was situated nearest the fire, the *apodytērium* farthest from it of the heated rooms, and the succession of hot-air, hot-water, and cold-water baths was the order regularly observed in bathing establishments of every grade.

About an hour after the bath came the *cēna*, or principal meal of the day. Once it had been served in the *ātrium* and had consisted, save upon state occasions, chiefly of bread or porridge, and vegetables. The father and mother and other adult members of the family sat at table, while children and servants occupied stools or benches at their feet or behind them. Long before the close of the republican period, however, the *cēna*, or dinner, had developed into as dainty a meal as the means of the householder would permit; separate din-

ing-rooms were found indispensable in a life of the slightest elegance, and the custom of reclining at table had become universal among the well-to-do. Columella lays it down as a rule that a farm-bailiff should recline at his meals upon high holidays only, and Plutarch, in his life of the younger Cato, tells us that the latter—always a bit of a fanatic—insisted, by way of self-mortification, on *sitting* at table throughout the period of mourning which followed the battle of Pharsalia.

The ordinary dining-table was square, surrounded on three sides by the same number of one-armed couches, while the fourth side remained open for convenience of serving. Each of these three couches accommodated three persons, who reclined

upon the left arm, supported, the one by the arm of the couch, the other two by heaps of cushions, and always with the feet turned outward. In the assignment of places a strict etiquette prevailed. The couches, or *lecti*, all



From Kiessling's edition of Horace.

more or less handsomely draped, were distinguished as *medius*, or the one which stood opposite the open side of the table; *summus*, the couch adjoining the head of the *medius*; and *imus*, that upon the other side. The *medius* and the *summus* were assigned to guests; the *imus* accommodated the master of the house, his wife, and one of the elder children or a favorite freedman.



The *medius* was the couch of honor, and the highest place upon it, as also upon the other couches, was the one nearest the arm. The third place, or that at the foot of the *lectus medius*, was, however, called the *locus cōsulāris*, and was usually assigned to the most important public officer present, both for convenience in the matter of receiving and sending messages and despatches, and because it brought him next the host, who leaned upon the arm of the *īmus*, or lowest couch. Nine was the full number that could be properly served at such a table; a place might be vacant, but to crowd a couch with more than three people was considered the height of vulgarity. Large parties of guests were entertained in spacious dining-halls, or sometimes in summer in the pleasant *sōlāria*, or open *loggie*, on the roofs of the houses, at separate small tables, each accommodating the orthodox number.

**Round tables** with couches fitted so as to form a semi-circle came into fashion in Cicero's time — extravagant objects, for which men paid an insane price. They were made of rare imported woods, preferably from a slab or section of the massive trunk of the so-called citron-tree, a species of African cypress, very beautifully mottled, and the most admired were supported on a single pedestal of solid ivory. Cicero himself had one such for which he paid 500,000 HS. The philosopher Seneca is said to have possessed five hundred. The couches of this luxurious period had often silver feet, and were inlaid with the same precious metal or with ivory and tortoise-shell. The custom had likewise been introduced from the East of hanging the walls of the dining-room with richly embroidered stuffs, and the




most sumptuous of all had a very peculiar arrangement of the coffered ceiling. It had long been the fashion to construct this of cross-beams, the square, sunken spaces, or *lacūnāria*, between which were carved, gilded, or otherwise ornamented. These *lacūnāria* were now made in the form of sliding panels, which could be withdrawn for the purpose of scattering flowers, or trifling keepsakes for the guests, upon the table.

*Mantēlia*, or table-cloths, came into use much later than napkins (*mappae*), which last the fashion of eating rendered rather a necessity than a luxury, and they were either brought by the guest or his personal attendant, or offered him by the servants of his host.

The *triclīniārii*, or dining-room servants, were under the supervision of a *triclīniārchēs*, or butler, and the finer the establishment, the more numerous they were. It was their business to arrange the room for the feast, to set forth upon the *abaci*, or sideboards, the imposing array of silver, gold, glass, and jewelled vessels, for both eating and drinking, which would be required in the course of the meal, and accurately to place in the centre of the table its principal ornament, the massive *salinum*, or salt-cellar. This article, which even the comparatively poor contrived to have made of silver, possessed a certain sacred significance; inasmuch as every table was consecrated to the gods, and the *salinum* contained not merely salt for seasoning the viands, but a tray (*patella*) for the *molae salsae*, or sacrificial cakes, which were offered to the Lares, and then probably broken and distributed, as a kind of grace, after meat. Silver vessels for vinegar and oil also formed a part of the permanent furniture of every handsome board. The carving and cut-

ting of the meats was done at side-tables; the meal was served in courses (*fercula*), which were brought in by the servants on trays (*repositōria*), which had sometimes two or three shelves or stories, and were presented to the guests from behind. The wine-cups were replenished in like manner, "over the shoulder," and these admitted some variety in form, but were usually shallow, with two handles, and often very beautiful in workmanship.

The implements actually used in eating were few and



Spoons.

simple, only the right hand of the guest being free to wield them. They consisted chiefly of two kinds of spoons, the *ligula* and the *cochlear*. The former was shaped very much like our own table-spoon, the latter had a much smaller bowl, circular in shape, and flat or only slightly hollowed, and the handle was pointed for convenience in detaching the meat of shellfish, or picking up particles of food. Knives and forks

were certainly not employed in Rome as table implements before the second century of our era.

A handsome dinner was served in three principal divisions, each of which might consist of several *fercula*, or courses. The introductory part was called the *gustus*, or *gustātiō*, and its object was merely to whet the appetites of the diners for the richer food to follow. It consisted

mainly of eggs, pickled vegetables, salads in great variety, oysters, raw or cooked, salted fish, mushrooms, artichokes, asparagus, or melons, eaten with salt and pepper. A beverage, *mulsum*, compounded of honey and must, was often served with the *gustātiō*.

The main part of the meal which followed fell also into three divisions, — the *prīma*, *altera*, and *tertia cēna*. It consisted of fish, meats, and game, both native and foreign, cooked with endless varieties of seasoning, — salt, pepper, ginger, cinnamon, sweet herbs, and wine. The fish was usually served with a costly imported sauce (*garum*), prepared with salt water, of which the flavor was highly prized. Some of the viands were eaten steaming hot; others had to be cooled with ice or snow before they were deemed truly palatable.

There was a pause after this portion of the meal was concluded, during which the *mola salsa*, already mentioned, was offered to the Lares, after which the *secunda mēnsa*, or dessert, was brought in. It consisted of pastry, confectionery, and fruit, both home grown and imported, and concluded the banquet proper — whence the expression, “*ab ōvō ad māla*,” from the egg to the apples, became proverbial for the whole of anything, from the beginning to the end.

Wine was taken in moderation with all the courses, rarely clear, sometimes iced, but oftener mixed with warm water. The business of regular drinking began only after the dessert had been removed. Those who affected Greek fashions were now perfumed and crowned with garlands. The wine was no longer mixed to taste, in the separate *pōcula* of the guests, but in a huge vase, or *crātēr*, whence it was ladled out by the servants in

*cyathī*, one-handled cups or ladles. The *cyathus* was the unit of measure for a systematic drinker, who, though he often used a goblet of the capacity of several *cyathī*, always reckoned his feats by the number of the latter which he consumed.

The *cōmissātiō*, or late supper of high-livers, which has been already mentioned, was little more than a drinking-bout. It was enlivened, as was also the *cēna*, by the performance of hired musicians, mimes, and dancers; but conversation, though it found a place, at least in the earlier meal, was never in Rome the fine art and the main entertainment that we find it among the Greeks.

## CHAPTER III.

## CHILDREN, SLAVES, GUESTS, CLIENTS, FREEDMEN.

THE *lūstrātiō*, or naming with religious rites, of a boy infant whom his father had formally acknowledged, occurred on the ninth day after his birth, a girl's upon the eighth. A sacrifice was offered for the child upon the family altar, or it was presented in one or more of the temples of the gods and recommended to their especial protection. As a defence against the evil eye and such mysterious ills, there was also hung round the baby's neck by a ribbon or chain, a small locket, usually heart-shaped or circular, sometimes crescent or cruciform, made of gold if the parents were wealthy, otherwise of some inferior material, and containing an amulet.

This was the *bulla*, of which so many specimens are to be seen in various museums, and which never fails in the picture of a well-born lad. The custom was probably of Etruscan origin, and applied originally to the children of patricians only; but it was subsequently extended to those of knights and of the official nobility generally. A boy wore his *bulla* constantly until he received the gown of manhood; a girl hers until her marriage. But the ornament was always carefully cherished and occasionally resumed, and it is a curious fact

that a *triumphātor* invariably put on his *bulla* upon the great day of his public glorification, as a protection against the envy of his fellow-citizens. There was no



Bulla.

such thing as a public registry of births, for civic purposes, before the time of Marcus Aurelius; but a private record of the *lūstrātiō* appears, in most cases, to have been kept, and was sometimes appealed to for purposes of identification.

The child received its first instruction at home. Either the mother was the teacher, or, in cases where several mar-

ried sons lived on under the paternal roof, some freed-woman or female relative of the family acted as nursery governess to all the little ones. In this manner they were taught reading, writing, the elements of arithmetic and of the laws. "When we were boys," says Cicero,<sup>1</sup> "we had to learn the Twelve Tables by heart like a species of hymn. Nobody does it now."

But far more important than even his modicum of book-learning, was held, at least in all the olden time, that practical education which the child received by

<sup>1</sup> Cic. De Leg. ii. 23. 59.

association with his elders, and admission, as he grew older, to their activities.

Thus the girl learned at her mother's side to spin, to weave, and to sew; the boy, of his father or elder brothers, the mysteries of planting and harvesting, swimming, riding, boxing, and the use of weapons. If the father were a *flāmen*, or priest, the son was early trained to assist at sacrifices as his *camillus*, or bearer of the sacred vessels. If the mother offered a sacrifice, her daughter acted as *camilla*. Were the father of a station to receive clients in his *ātrium*, his boys stood beside him during the ceremony, and so learned to know the names and faces of his political and social following. On days of family triumph or mourning, when the shrines were opened, and the images of the ancestors displayed, the children were always present. They took part in the family meals, when these were simple and there were no guests, and sometimes they helped serve at table.

Very early also in the history of Rome we find mention of both boys' and girls' schools. Plutarch seems to imply that even Romulus and Remus went to school at Gabii, and the unhappy Virginia was on her way to school when her precocious beauty attracted the fatal notice of Appius Claudius. Virginia was, however, of plebeian rank, and her mother was dead.

**The primary teacher** (*litterātor*) was usually a slave or freedman, who acted as private tutor, or instructed a small class in the *pergula*, or veranda attached to a house or shop. Schooling of this kind was paid for by the month, occasionally by the year, and very poorly paid; insomuch that the *litterātor* had often to eke out



his income by some other employment, such as the writing of wills. Under Diocletian the monthly fees of a pupil were limited to fifty *dēnārii*.<sup>1</sup>

The school year consisted of eight months, with a long vacation comprising July, August, September, and October. There were also special holidays, such as the feast of Minerva, and the *Sāturnālia*, New Year's Day, and the twenty-second of February, the great day of commemoration of the dead.


The substance of what was taught in these primary schools was the same as that which an old-fashioned or more carefully secluded child acquired at home,—reading, writing, and the elements of arithmetic, while the laws of the Twelve Tables, as we have already seen, were long committed to memory like a sort of catechism.

The Roman system of numerals, in which values are expressed by the collocation of different letters of the alphabet, appears, beside the simplicity of the Arabic, a very clumsy one; and the regular employment of duodecimal fractions, or division of the unit into twelfths, increased yet more the difficulties of reckoning. We are not surprised therefore to learn that even grown men often had recourse to a teacher of arithmetic, or *calculātor*, who was much better paid than the common school-master, nor that the boy at his desk was allowed to assist his ciphering by using the fingers of both hands, as well as by the *abacus*, or counting-machine.

Reckoning with the fingers, not yet wholly disused in the East, proceeded upon the basis of expressing by

<sup>1</sup> It is not exactly known what a *dēnārius* was worth under Diocletian. Mommsen computes it at nine German *pfennige*, which would make this maximum monthly price about one dollar.

eighteen different motions of the left hand, nine units and nine tens, and, by similar movements of the right hand, nine hundreds and nine thousands. The term *abacus*, which we have already seen applied to the side-table of a dining-room, was also used both for a board strewn with sand, on which



Abacus.

geometrical figures were drawn with a pointed stick, or *stilus*, and for one on which balls representing figures were moved about in grooves representing denominations of figures. This kind of *abacus* had also a contrivance for reckoning fractions.

The Roman monetary system had practically two units of value, the *sēstertius* and its quadruple, the *dēnārius*. Large sums were commonly computed in the former and reckoned by a decimal system. Small sums were expressed in the latter and its duodecimal fractions. The difficulty which must have arisen from the simultaneous use of the decimal and duodecimal systems was diminished by rules and tables for reducing the one kind of fraction to the other, and these rules and tables apparently found a place in the curriculum of the elementary schools.

The simple instruction, purely practical in its aim, of these primitive establishments was deemed all-sufficient

for the youth of Rome down to the time of the second Punic war. But after that period there grew up an ever-increasing demand for the services of Greek grammarians, who not only taught their own language, but introduced a more scientific method of studying the Latin itself; and who succeeded, after a time, in imbuing the Roman mind with something resembling the broad ideal of Greek culture,—that is to say, of the harmonious and equal development of all a man's faculties, both physical and mental.

**The principal text-book** of the Greek *grammaticus* was Homer. The master read aloud, with proper accent and inflection, a passage from the poet. This the pupil had first to commit to memory, and afterward to stand a certain examination, not merely upon its grammar and prosody, but on all the various questions in geography, astronomy, history, and mythology which it might suggest. Written exercises had also to be prepared, translations from poetry into prose, and original themes.

The criticism of these last must have involved some elementary teaching in rhetoric, but a further pursuit of the various branches of learning comprehended under this head was reserved for the higher schools of the rhetoricians.

The grammatical course was deemed equally appropriate for boys and girls, and a good number of the latter attended the grammar schools; although there was plainly always a prejudice in favor of home education for them.

To get the full benefit even of this amount of instruction it was needful that the pupil should both understand and speak Greek, and this the children of the wealthy

learned to do in infancy from domestic slaves of that nation, as those of the Russian nobility learn French and English from their nursery governesses to-day.

As soon as a boy was old enough to **begin his public education**, he was placed under the special charge of a servant, called *paedagōgus*, whose business it was to help him prepare his lessons, and go with him to school, and who continued to be his personal attendant until he received the *toga virilis*.

Long after this period a young man might, and often did, frequent the schools of rhetoric, which, like the grammar schools, were an importation from Greece, and conducted mainly upon the Greek method, and where music and the higher mathematics were taught, as well as the arts of composition and oratory.

Yet it is evident that a dull but deep-seated objection to all this outlandish culture lingered throughout the whole republican period, not merely among the masses, but in the minds of enthusiasts for the old Roman spirit and traditions, like the elder Cato; and when Atticus, the friend of Cicero, published a collection of Greek anecdotes, we find Lucullus congratulating him upon the barbarism of some of his expressions, on the ground that it did not become a good Roman to know Greek too well.

After the Romans came to have a literature of their own, there grew up a class of *grammatici Latīnī*, who made a business of teaching Terence, Horace, and Virgil, and who were much frequented. The corresponding class of Latin *rhētorēs* had never found favor, either with individuals or with the state. Their teaching was of a very inferior order, and their influence upon manners

was considered so bad that as early as the year 92 B.C. all such Latin schools of rhetoric were closed by order of the Censors, Domitius and Cassius.

Every well-bred Roman boy learned to ride, to run, to leap, to box, and to swim, as a necessary preparation for his military service, and the Campus Martius was assigned for the practice of these and all other athletic exercises.

Under ordinary circumstances a lad was supposed to have finished his regular schooling by the end of his seventeenth year, at which time also he ceased to be *puer* and became *iuvenis*, and liable for military duty. Already, in the vast majority of cases, he had laid aside the *toga praetexta*, or simple woollen tunic with a broad purple stripe (*clāvus lātus*) down the front, worn by both boys and girls of rank, and had been ceremoniously invested by his father or guardian with the *toga virilis*, or *toga pūra*, the plain white garment of manhood. No precise age was fixed for this solemnity, and the time of the year was also optional, although the religious feast of the *Liberālia* — March 17th — was undoubtedly a favorite season. The *bullā* was first removed from the boy's neck and consecrated to the *Larēs*, and an offering was then made for him in the family chapel, after which, accompanied by a train of relatives and friends, he was led into the Forum and formerly presented to the public. His full name was afterwards inscribed in the list of citizens kept in the *Tabulārīum* upon the Capitol, or among the archives of his province; a sacrifice was offered for him at some public altar, and a banquet followed, accompanied, in the case of imperial and other very distinguished youth, by

a largess to the people. The maiden of quality continued to wear her *tunica praetexta* until marriage.

For the young man there usually remained, after the ceremonial introduction to public life described above, a finishing year, the *tīrōcinium*, of special preparation for the calling which he had elected to pursue. If he were to be a lawyer, or aspired to public life, as almost all the law students did, he attached himself to the train of some eminent statesman, as did Cicero to that of the great Augur, L. Mucius Scaevola, and Cælius afterward to Cicero's, and learned by observation his manners and methods. If he had chosen the military career, he obtained a place, in some respects resembling a staff-position, in the cohort of some famous general, and, without being subjected to all the drudgery of a common soldier, he learned the régime of camps and the duties of an army officer. The former kind of apprenticeship was called *tīrōcinium forī*, the latter *tīrōcinium militiæ*.

Boys of the middle and lower classes went directly, as they do now, from school to the business of life.

Some uncertainty exists as to the time at which a free-born youth obtained the *iūs suffragiī*, or became qualified to vote in the general elections. He was legally free to marry, to contract debts, to receive a legacy, or make a will, from his fourteenth birthday, — a girl from her twelfth, — but so long as he was *praetextatus* he certainly did not vote. It is altogether likely that his introduction to the Forum constituted his political majority, but it must be remembered that the suffrage lost its significance after the state was no longer free, that is to say, in those imperial times about which we know so much more than of any other; and this is prob-



ably why under the empire the investiture with the *toga virilis* became more and more a matter of parental caprice; so that it was sometimes bestowed, as in Caracalla's case, as early as twelve, or, again, as in Caligula's, withheld until nineteen.

**The subject of slavery** among the Romans is too large a one to be treated otherwise than very cursorily in so small a manual as this. Slaves there always were in the Roman commonwealth from the earliest historic period; and the master had legal power of life and death over his human chattels. But the servitude of the olden time, when even a patrician tilled his own fields with the help of his own sons, was practically a light enough order of bondage. The vast majority of masters held only one, or, at most, two or three slaves, who were treated in some sort as members of the family, sleeping under the same roof, and taking their meals in the same room, if never at the same table. Similar social conditions are wont to mark the modest beginnings of any state, but in the nature of things they cannot endure.

A servile population always increases faster than a free one. Great towns grow up and become centres of civic and commercial activity, and the landed proprietor finds it convenient to pass a part or the whole of his year in them, leaving the main business of agriculture to his rustic dependents. Small freeholds are gradually absorbed by extensive estates, which are worked by great gangs of laborers under the supervision of men who have risen from their own ranks. Habits of luxury and ostentation among the privileged class grow fast with the increase of wealth, calling for armies of servants with highly specialized functions. All these changes



were either accomplished, or in rapid process of accomplishment, in the Roman state, by the year of the city 550; that is to say, two centuries before the Christian era. The dominant passion of the race for foreign conquest had also its influence in developing the institution of slavery. On the one hand a slave could not be drafted into the army, wherefore his services were all the more indispensable in any and every department of home industry. On the other, among the countless prisoners taken in foreign war, and thereby reduced to slavery, there were many from highly civilized Greece, and the farther Orient, who were capable of instructing their comparatively rude conquerors, not merely in the finer arts and crafts, but in every department of human knowledge. Whence it came to pass that a large majority, not merely of the skilled workmen of Rome, but of the teachers, readers, and amanuenses, employed by the wealthy who aspired to culture, were slaves of foreign extraction.

The first step in the social revolution thus achieved was the division of a man's slaves into the *familia urbāna* and the *familia rŭstica*, a classification corresponding roughly with that of the negro slaves into domestic servants and field hands; while the same degradation was implied in the transference of a member of the former class to the latter.

The whole body of "rustic" slaves, often extremely numerous, was under the general supervision of a *villicus*, who also in most instances kept the farm accounts, and rendered them either directly to the master or to a *prŏcŭrātor*, or steward. Each gang of slaves which was told off to any department of farm-labor had its own overseer

(*magister operae* or *operārum*). Slave labor on the farm, as in the house, was specialized just as far as the extent of the estate and the wealth of the proprietor would permit. In ideal conditions we not only find each kind of animal under the care of a separate servant or staff of servants (*bubulcī* for the oxen, *asinārii* for the donkeys, *subulcī* for the pigs, etc.), but each variety of feathered creature — hen, pigeon, pheasant, as the case might be — had its own special attendant, *gallinārius*, *columbārius*, or *phāsiānārius*. There would be *piscātōrēs* to look after the fish-ponds, a *topiārius* to lay out gardens, a *hortulānus* to cultivate them, an *apiārius* to manage the bees, and an *aquārius* to keep the water-works in order, and many others, of whom and of their duties we shall have more to say in another place.

With regard to the great staff of slaves who raised the crops, there seems some reason to suppose that the vineyards were occasionally cared for by men who did no other work; but usually the agricultural laborer passed on, as the season changed, from one kind of work to another, as he does to-day, and the use of such terms as *fossor* (trencher), *messor* (reaper), *putātor* (grafter), etc., is to specify not a different individual, but the use of a different tool.

The rural slaves worked under overseers who were almost of necessity hard and cruel, and they were often little better lodged than the beasts for which they cared. Now and then there would be a fanciful and kind-hearted master, like the younger Pliny, who piqued himself on having made the slave-quarters in his Laurentian villa "nice enough for guests";<sup>1</sup> but it may be taken for

<sup>1</sup> Plin. Ep. II. 17. 9.

granted that such philanthropists were not exceptionally numerous in ancient Rome.

The modest corps of house servants maintained by a distinguished Roman in the earlier time was headed by an *ātriēnsis*, or steward, who also kept the house-accounts. Later, as the style of living grew more elaborate, these duties had to be divided, and the *ātriēnsis* became a mere major-domo, who had enough to do in exercising a general supervision over the arrangements of the dwelling itself. The ever-increasing crowd of menials under him fell into different classes, each with an overseer of its own. The *cubiculārīi* performed the duties of housemaids, the *triclinārīi* waited at table, the *supellēctārīi* kept the furniture and table-ware in order, the *culinārīi* were kitchen drudges, while the *balneārīi*, or those who served the baths, formed another distinct class. The functions of valet and ladies' maid were distributed amongst *ōrnātōrēs* and *ōrnātrīcēs*, *tōnsōrēs*, or barbers, and *cinīflōnēs*, or hair-crimpers, and *calceātōrēs* who took care of the feet. There were *dēlicātī*, or pages, more or less pampered, to run on errands, an *invītātor* to summon guests, a *servūs ab hospitīis* to look after their lodgement, a porter (*iānitōr* or *ōstiārius*) who was sometimes chained in the vestibule like a dog. Were the master of an artistic or literary turn, he had people whose special duty it was to look after his pictures and statues,—servants *ā pinacothēcā* and *ā statuīs*,—*tabellārīi* to convey his letters to their destination, *lectōrēs* to read aloud to him at meals, in the bath, or in bed.

The number of slaves who should accompany a great man or a great lady when he or she went abroad, was matter of lively emulation. Those who walked had *ante-*

*ambulātōrēs*, and *pedisequī* or *pedisequae* to go before and behind them. If they took the air in litters, they were borne by *lectāriī*, the most fashionable being Syrians or Cappadocians of unusual stature, who, like the pages, wore a brilliant livery. The boy, as we have seen, had his *paedagōgus* to attend him to school, the daughter of well-to-do parents had her Greek maid, who performed the same office. There was often a *capsārius* besides to carry the books and tablets.

All these functionaries were slaves, a limited number being of the comparatively privileged servile class called *vernae*; that is to say, slaves born in the house and usually trained for the personal service of its children, many of whose educational and other privileges they shared. The freedman who had been *verna*, always held himself superior to other manumitted slaves.

A highly prized slave was occasionally set free, by pure grace, or in gratitude for some signal service, either during the lifetime of his master, or in his will. The right of the slave to his own small savings (*pecūlium*) was also practically recognized and these might be applied to the purchase of his freedom; but their accumulation, very slow at best, was yet farther hindered by the master's claim upon the little horde, for making good certain pecuniary injuries which he might sustain through the slave. After the number of bondmen had increased enormously, so that one man sometimes owned many thousand souls, it became advantageous for the master to educate them wholesale in trades and crafts for which they might show some aptitude, and then let them out to master-mechanics, bankers, seamen, theatrical managers, or masters of the amphitheatre, as the case might be.

Sometimes, too, the master directly advanced the capital for setting his slave up in business, allowing the latter a share of the profits, out of which he might hope some day to buy his freedom.

**The common punishment of a refractory slave** was beating. If a runaway were caught, as he could hardly fail to be, since there were extremely heavy penalties for harboring and assisting him, he was either branded or had an iron collar like a dog's welded round his neck, or his legs were fettered, or in exaggerated or repeated cases of offence he was at once turned into the arena or otherwise put to death. If he attempted to take personal vengeance upon his master for any wrong whatsoever, his whole family shared his fate, and the regular form of capital punishment for a slave was crucifixion under the most ignominious and agonizing circumstances.

The institution of slavery reached its greatest development in Rome in the last century of the republic, when slave-traders and slave-markets flourished both in the capital itself, and in all the great ports visited by Roman ships.

Already, however, in the early days of the empire, the spread of philosophic and humanitarian ideas had softened the theory of human servitude, and modified the slave's position. Marriage was made legal for him; he was empowered to testify in certain courts, and to lodge complaint, if treated with outrageous cruelty. Kind masters, like Pliny, respected the provisions of his testament; under Claudius, if his master abandoned him when he was old or ill, he was thereby set free; under Hadrian, the wanton slaughter of a slave by his master was forbidden; under Constantine, this crime was made

one of homicide; and so finally, with the formal conversion of the empire to Christianity, the long-declining slave-system of Rome received its death-blow.

We have considered briefly the position and mutual relations of the ordinary members of a Roman household, or of what may be called the inner family circle; but there was a sense in which the Roman family might be said to embrace an indefinitely larger number of persons connected with it by ties more or less remote. To this outer circle, or secondary order of members, belonged the authorized guests of a house, its clients, and its freedmen.

The term *hospitium* embraced not merely the spontaneous welcome to bed and board of a man's near kindred and personal friends, but a contract for mutual hospitality, written or otherwise attested, which might be made either between two communities, or between two individuals, on behalf of themselves and their dependents, or between an individual and a community. The practice was one of extreme antiquity in Italy, older certainly than the rise of the Roman people. The contract was drawn up and presented by accredited messengers, attested by a hand-shake or by a formula of words called the *spōnsiō*, and accurately recorded, and it remained binding upon the posterity of the contracting parties until formally and publicly annulled.

*Hospitium* between two communities, that is, between the inhabitants of certain towns or districts, was called *hospitium pūblicum*. It was recorded by engraving on copper or bronze tablets,<sup>1</sup> of which duplicate copies were

<sup>1</sup> It seems altogether probable that a part at least of the famous Eugubian tables — the bronze tablets exquisitely engraved in ar-



preserved in some temple, or other sacred place, in either town. In Rome the depository of such tablets was the *Aedēs fidei populi Rōmāni*.

They entitled the stranger to free board and lodging for a certain period, to a physician's attendance in illness, to decent burial if he died.

Such contracts were in force between Roman and Greek communities as well, and they involved no light charge upon the latter in the days when foreign travel had become a fashion among the Roman magnates. But some — like Cicero when he went as proconsul to Cilicia — preferred to remain independent, and would not avail themselves of the privileges of a public guest.

*Hospitia prīvāta*, or contracts for hospitality between individuals, were also sometimes engraved and either inserted in the wall of the *ātrium* or suspended on it. Usually, however, a simpler device was employed by private persons. The guest presented a small engraved ticket (*tessera*), of which the host had a duplicate, and was at once made welcome to the privileges of the house. He was given a bath and a meal; an offering was made for him at the family altar; he was assigned a bed, and became thenceforth, for an indefinite period, a member of the family. So far from fretting under this as an imposition, the great Roman statesman was ambitious of harboring as many such guests as possible, and it was a matter of policy with him to look well after their comfort and interests on the ground that they increased his own influence in the provinces and abroad.

chaic and hitherto only partially deciphered characters — discovered under the ruins of an ante-Roman theatre, and now preserved in the *palazzo pubblico* of Gubbio in the Marches, were records of *hospitia publica*, dating from Etruscan or even Pelasgic times.



Originally, and so long as the state remained free, the **relation of client and patron** was also a sufficiently honorable one, resting like that of guest and host, on pledges of mutual service. There was this difference, however, between the position of a client and that of a legal guest, that the latter was a free citizen in his own community, while the former had usually no civic rights whatever. Either he was in banishment from his native place, or he belonged to a tribe or city which had been vanquished in war, and so disfranchised; or he was a freedman (*libertus*) whose manumission gave him no political status. In either case he needed the protection of some powerful personage, and was only too glad, in return for the same, to take the name of his patron, engaging to fight his battles both at home and abroad, and to assist him out of his own private means — if he had such — when extraordinary payments, as of ransom or dowry, were to be made, or the patron was in any way pressed for money. Clients and patrons might neither accuse nor testify against one another in the courts, and the laws of the Twelve Tables made it a capital offence for a patron to betray his client's interests. It was no uncommon thing for the entire population of conquered cities and states voluntarily to seek such a relation with the general who had subdued them, and with his descendants. Thus the Marcelli became the hereditary patrons of the Sicilian towns, the Fabii of the Allobrogian, Cato Uticensis of the island of Cyprus, and so on. The freedman either continued to reside in his patron's house and perform his old functions, or he was endowed by the latter with a capital for starting in business, or with some small freehold property. In case of subse-

quent impoverishment, they were still bound to assist one another. The patron always paid for the funeral of his freedman, was his legal heir if he died childless, and the *ex officio* guardian of his children if he left any under age.

The relations of patron and *libertus* remained virtually the same throughout the imperial period; those of patron and client, on the other hand, altered materially, and, from a moral point of view, very much for the worse. When the number and strength of a patron's following had ceased to have any political significance, and no longer increased his importance in the state, it became largely a matter of senseless ostentation on the one side, and of self-interested sycophancy on the other. The hangers-on of a great man received their maintenance, and this, in most instances, was all they wanted. They were of every rank and condition, men of letters from whom a certain tribute was expected in the way of flattery, soldiers of fortune, and professional legacy-hunters, scions of the great families, who had early run through their patrimony, the idle of every grade, with a tatterdemalion fringe of the congenitally and hopelessly poor. A few favored individuals out of this motley regiment might be invited to the patron's own table, but all claimed as their right, and regularly received, either one substantial meal in a day, or its equivalent in money. Occasionally the mass of the clients was regaled at a public feast (*epulum publicum*), where the viands were supplied by a contractor (*maniceps*) at so much a head. This was called *acēna rēcta*, and was, originally, at least an exceptional arrangement, for days of public celebration; as when Julius Cæsar,

on the occasion of his triumph, in 56 B.C., entertained the entire male population of Rome at 22,000 *triclīnia*. A more common custom was to appoint a place where a species of dole was distributed to all the *clientēle*. This practice was called *epulum dīvidere*, and the dole itself *sportula* from the basket in which the food was taken away; the same name being applied in imperial times to the small money-payment, which had now universally replaced the alms in kind. The average amount of this daily allowance, under the earlier emperors, was twenty-five *assēs*, or about thirty-three cents of our money. On special occasions, like the patron's birthday, a larger sum was given. Martial<sup>1</sup> mentions one such where it was trebled, but adds contemptuously that it was doubtful whether the man had a right to any birthday at all. On the other hand if the great man were ill and could not receive his clients, there appears to have been no distribution; but even so, a client who managed to make a number of successive salutations, and to keep well with several patrons, as many did, might secure, without further exertion, a modest maintenance for a rising family.

<sup>1</sup> Mar. Epig. x. 27.

## CHAPTER IV.

## FOOD AND CLOTHING.

BREAD, wine, and oil, — on these three abundant and beautiful products of the Italian peninsula the mass of its inhabitants lived and throve in ancient times as they do to-day. Wheat was the grain most grown by the Romans, and wheaten porridge or bread their staple food. In very ancient times the grain of wheat was not even ground, but merely pounded in a mortar, mixed with water, and cooked to the consistency of a thick pulp, called *puls*. The slaves who pounded the grain were *pīstōrēs*, or *pīnsitōrēs*. Even after the superiority of baked bread had been discovered, the baking continued for a long time to be done at home, and was regarded as the special business of the house-mother, or of the chief cook, according to the rank and means of the family. The first public bakery of Rome was established in 171 B.C., after which time home-made bread went gradually out of use in cities, though it had still to be prepared on rural estates by slaves appointed for the purpose. Later it became one of the recognized functions of the general government (it had long been held such in times of scarcity) to regulate, year by year, the food supply of the nation; and to see that the mass of the people was provided with cheap and wholesome

bread. The bread-makers of Rome were now organized into a college or guild, under the presidency of the *Praefectus Annōnae*, and vast establishments, comprising both mills and bakeries, were built and let out to them by the State.

The members of this guild enjoyed special privileges and immunities, which were extended, after the general decline of agriculture, when grain had to be imported in vast quantities, to the ship-owner and seamen (*nāviculārīi* and *caudicārīi*), on whose enterprise the supply of bread-stuffs largely depended. Trajan, we are told,<sup>1</sup> gave the *ius suffragiī* to every man who had worked for three years a *pīstrīnum* (grain-mill) in which at least one hundred *modiī* of corn had been ground daily. But it must always be remembered that even under that excellent emperor the suffrage did not mean what it had done when the state was free.

As early as the times of the Gracchi (130 B.C.) there had been a monthly distribution of grain among the people. Four hundred years later, under the Emperor Aurelian, there had come to be a daily distribution of baked bread, either gratuitous or at a nominal price, with which, and the perpetual exhibition of games in the Circus ("*pānem et Circēnsēs*"), the Roman burgher of those degenerate days found his absolute needs both of body and mind satisfied without further exertion upon his own part.

Different qualities of bread were provided even at the great public bakeries. The best was the *pānis siligineus*, made from *silīgō*, or wheat flour of the very first quality; the *simila* or *similāgo* was also a fine white flour, only a

<sup>1</sup> Gaii. Inst. 1. 34.

little inferior to the first. Coarser varieties of bread, — the *pānis cibārius*, *plēbēius*, *rūsticus*, as also the *pānis castrēnsis*, or bread of the common soldier, — were made by mixing flour of the second quality with bran, or wholly of bran, or sometimes of inferior grains like millet.


Besides the great public magazines of bread, there were many small cake-shops, where cakes, pastry, and confectionery, and, in general, all the dainties which are summed up by the modern Italian under the comprehensive term *dolci* (sweets) were made and sold. But these establishments were conducted by private enterprise, and their keepers were *dulciārīi*, *placentārīi*, *libārīi*, *crūstulārīi*, as the case might be. These were the shops which we have already seen besieged by the school-boys in the early morning hours; but the choice of the young students was probably limited, and they had to content themselves for the most part, no doubt, with the harmless *quadra pānis*, a plain, round cake quartered off by two lines like a hot-cross bun, of which plenty of illustrations exist, and of which specimens were found at Pompeii.



Panis (Rich).

**The grain-mills** of the ancients were of three kinds, the *molae manuāriæ*, or hand-mills, the *molae asināriæ*, turned by asses or mules, and the *molae aquāriæ*, or water-mills. The first two were identical in principle, and differed only in size. They consisted of two parts, the *mēta*, or nether, and the *catillus*, or upper mill-stone; but their construction was very unlike that of the mills of modern times. The *mēta* was a solid cone of stone

resting upon a firm base with an iron rod projecting a little way from its apex. The *catillus* consisted of two hollow stones, united in the form of an hour-glass. The lower half fitted over the cone of the *mēta* like an inverted cup. It had a socket at the narrowest part,



Mola (Rich).

which received the rod aforesaid, and was made to revolve upon it by means of a projecting handle or lever. The grain was poured into the upper cup, and falling between the lower and the solid cone through holes bored for the purpose, it

was ground by the revolution of the *catillus*. If the mill were large and worked by horse-power, there was only one lever, to which the animal, whose eyes had first been bandaged to prevent its becoming dizzy, was harnessed. The smaller hand-mills had a lever projecting on either side, and were worked by two slaves. Water-mills did not come into general use in Rome before the fourth century of our era, when there was a group of such at the foot of the Janiculan hill. The actual machinery for grinding was still substantially the same as that already described, but the power was now supplied by streams of water falling from an artificial reservoir at the top of the hill upon a large water-wheel (*rota aquāria*) with float-boards, and having attached to its axis a pair of cog-wheels (*tympāna dentāta*) whose motion turned the *catillus*. It was that able and resourceful general, Belisarius, who, during the siege of Rome by



the Goths in 536, devised a system of floating corn-mills, whose wheels were turned by the current of the Tiber somewhat like those which may be seen in such numbers upon the Danube to-day between Vienna and Buda-Pesth.

Bacon and the sweet, nutty oil of the country were used to impart a relish to porridge and coarse bread, and the ordinary drink of the peasant was milk or must, the unfermented juice of the grape. Moreover, even the comparatively poor man had access to an almost infinite variety of vegetables, — beans, peas, lentils, cabbages, beets, turnips, radishes, carrots, asparagus, artichokes, chiccory, onions, leeks, garlic and parsley, melons and cucumbers. Lettuce, mallow, cress, and many other plants were largely cultivated for salads; and for seasoning, mustard, anise, fennel, mint, and so on.

Beans and onions were the vegetables most extensively raised in ancient times, the name of the Fabian gens and the cognomen Cæpio being derived from these crops. Beans, however, — forbidden altogether by Pythagoras to his disciples, — were considered too heavy food for any but smiths, gladiators, and farm hands; and though Varro maintains that the men of old were at their raciest when their talk smelt of onions and garlic, the taste for these fierce condiments declined fast with the progress of refinement; insomuch that Horace devotes an entire epode (the third) to his execration of the latter, and Nævius reproaches the gods for not having confounded the gardener who first grew an onion. The finest of all vegetables to the elder Cato was cabbage, which seems quite consistent with what we know of his character.

The natural fruits of Italy, apples, pears, plums,

quinces, olives, and grapes, were carefully cultivated from very early times, and Lucretius, Varro, and Virgil agree in describing the land as literally covered with vineyards and orchards: "*tōta pōmārium*," says Varro. These common fruits were cheap enough in their due season, and found a place upon almost every table; but as luxury increased, there came to be great emulation on the part of the horticulturists in the forcing of early fruit, in the production of new varieties, which were often, then as now, called after distinguished men, as the Matian apple for Gaius Matius, and the Appian from an Appius Claudius; and lastly in the introduction and naturalization of foreign fruits, as the pomegranate (*grānātum*) from Carthage, the fig and almond (*fīcus*, *am̄ygdala*) from Greece, the peach (*mālum Persicum*) from Persia, the apricot (*mālum Armeniacum*) from Armenia, the pistaccio nut (*pistāchium*), unknown before the time of Tiberius, and many others.

■ Dried figs, dates, and damson-plums were largely imported, and both the native and the naturalized fruits of Italy were introduced by Roman colonists into far distant provinces, as the cherry (*cerasum*) into Britain and the pistachio (*pistāchium*) into Spain.

**The diet of the early Roman**, though never exclusively vegetarian, appears to have been about as largely so as that of the Italian peasant of to-day. The slaughter of neat cattle for food was long regarded as a crime; mutton, pork, and goat's flesh were the meats most in use. As time went on and taste became more sophisticated, the craving for animal food increased, and accomplished cooks like him in the Pseudolus of Plautus came to regard vegetables as merely accessories to it, and fitter upon the whole for the nourishment of animals than men.

The taste for game also developed rapidly, until the sportsman's bag no longer sufficed for its gratification, but all great country-seats in the last years of the republic had their *vivāria*, or preserves. The kinds of wild flesh most esteemed were hare (*lepus*), wild-goat (*caper*), though this was condemned by Galen as unwholesome, the wild boar (*aper*), which was roasted whole and so served at sumptuous tables, and even the wild ass (*onager*), and a certain species of dormouse (*glis*).

Over and above the ordinary kinds of domestic fowl, feathered game was also in great request, such as the *lagōpūs* or white grouse, the *scolōpax* or snipe, the *attagēn Iōnicus* or woodcock, which was considered a marvellous delicacy, besides thrushes (*turdī*), partridges (*perdicēs*), ortolans (*miliāriae*), pheasants (*phāsiānī*), cranes (*gruēs*), and *pāvōnēs*, or peacocks. These last indeed seem to have been regarded in the year 46 B.C. as the *ne plus ultra* of table luxury in this line, for it was then that Cicero wrote to his old friend Papirius Pætus, concerning the banquets to which he was perpetually bidden by certain young men of fashion, "whom he taught to declaim, while they taught him to dine,"<sup>1</sup> that he had "eaten more peacocks"<sup>2</sup> that winter than Pætus had "ever eaten pigeons." And a little later he tells how he endeavored to pay off his obligations by a handsome dinner to the same set of youths. "However," he adds, "I did not attempt to have peacock."<sup>3</sup>

**For fish there seems to have been no demand** whatever in early Roman times, although the taste for it subsequently grew, as artificial tastes are wont to do, into a passion;

<sup>1</sup> Cic. Ad Fam. ix. 16.

<sup>2</sup> Cic. Ad Fam. ix. 18.

<sup>3</sup> Cic. Ad Fam. ix. 20.

so that the word *obsōnium*, originally applied to any kind of cooked food except bread, came to signify fish exclusively. Already, in the elder Cato's time, fish was dearer than beef; unheard-of sums were paid to import alive the fish of other countries, and fish-tanks and fish-ponds (*piscīnae*) for the cultivation of choice varieties became one of the favorite extravagancies of the wealthy. Among the most prized of the native species were the *acipēnser*, a kind of sturgeon; the *asellus*, which seems to have resembled our cod; *lupus*, a species of pike, so named from its voracity, but of which those only were approved by epicures which were taken in the Tiber, — *inter duōs pontēs* — that is, in the neighborhood of the island; the *mūllus*, or mullet, especially the bearded mullet, which, though seldom weighing more than two Roman pounds, often fetched an enormous price; the *rhombus*, a kind of turbot; and later, the river-fish of North Italy, of the Danube, the Rhine, and the Moselle. There was, moreover, a vast importation of different kinds of salted and pickled fish from various Mediterranean ports, those which came from Spain, Sardinia, and Pontus being most esteemed. The common name for all these preparations was *tarīchos*, a word borrowed from the Greek, and under this head were comprised many different sorts and grades. There was *tarīchos* made from fat fishes and *tarīchos* made from lean; there was a delicate variety made entirely from the young fry taken in the spring, and a coarser but still highly appetizing kind made from the large slices (*Melandrya*) cut from the back of the *thunnus*, or tunny-fish; first salted and dried in the sun, then cooked in sea-water or oil, and eaten with vinegar and mustard, by way of *gustātōrium*, at the beginning of a meal.

Salted fish was of course a cheaper food than fresh, and there was a certain savory dish, the *týrotarichus*, made of some kind of *tarīchos*, eggs and cheese, or spices, which was the subject of endless jests between Cicero and his friends, as a kind of symbol of resolute frugality.

**Oysters** (*ostreae*) were considered as great a delicacy in Roman times as now. Imported in the first instance from the East, and especially from Abydos, they came to be extensively cultivated in the neighborhood of Naples, especially in the Avernine and Lucrine lakes, and subsequently in the remotest parts of the western provinces. In the time of Ausonius, the oysters of Burdigala (Bordeaux) in Gaul were particularly relished. An important industry also grew up out of the manufacture, in seaport towns, of three kinds of fish-sauce, *garum*, *muria*, and *allex*, which greatly tickled the sophisticated Roman palate. *Garum* was made chiefly from sturgeon or mackerel; *muria* from tunny. Their preparation is not perfectly understood, but in both cases the fish appears to have been slightly cooked in sea-water, and allowed to ferment for several months. The resultant mixture was then strained, and the clear liquor, which was very costly, constituted *garum* or *muria*, the residuum *allex*. The word *muria* was also used for any brine, and there was a cheap sort of *allex*, home-made from ordinary fish, which was given to slaves as a relish with their porridge.

**Sugar and butter** were unknown among the Romans, their place being supplied by honey and oil.

A few words only need be given in this place to the comprehensive subjects of oil and wine; since the mode of manufacturing, from the olive and the grape, these

important articles, or at least accessories of a Roman diet, will be fully described in the chapter on Agriculture. The cultivation of the olive for oil was as old in Italy as the time of the Tarquins. It spread thence to Gaul and to Spain; but the Italian oils were always considered the best in the world, and they were profitably exported in ancient times, as they are to-day. **The vine was native all over the peninsula**, and always esteemed a peculiarly sacred product of the soil. It was under the direct patronage of Jove, in whose honor were celebrated, on the twenty-third of April and the twentieth of August, the feasts of the *Vinālia Urbāna* and the *Vinālia Rūstica*; and the vintage was opened by the *flāmen diālis* with a religious ceremony. These pious, old-fashioned customs, however, had reference merely to the production of the ordinary sour wines of the country, like Horace's *vīle Sabīnum*, or that acrid wine of the Alban Mount, which excited the merriment of Cineas, the ambassador of Pyrrhus.<sup>1</sup> The careful and expensive culture of the vine for the production of choice local varieties did not begin in Italy until after that of cereals had notably declined.

The elder Pliny tells us in his Natural History,<sup>2</sup> that at the time of his writing, which was probably about 50 A.D., there were some eighty varieties of good wine in the Roman market, of which number nearly two-thirds were grown in Italy. Excellent kinds were raised, on all the southern slopes of the Alban hills, at Velitræ, at Præneste, and notably at Formiæ upon the coast. Among the Sabine wines, the once renowned Cæcuban, which Augustus considered the noblest wine on earth, and which chiefly came from the neighborhood of Terra-

<sup>1</sup> Plin. Nat. Hist. xiv. 3.

<sup>2</sup> Plin. Nat. Hist. xiv. 11.



cina, was no longer grown in Pliny's time, and its name had become a kind of general expression for any particularly excellent vintage. The yet more famous Falernian in all its varieties, brown and pale, sweet and dry, had also lost something of its prestige, owing to the fact that it was unscrupulously adulterated. But the product of the Mons Massicus, so often and melodiously praised both by Horace and Virgil, still held its pre-eminent place among the wines of the South, and fine varieties were grown upon Vesuvius, in all the environs of Naples and Pompeii, at Cumæ, and at Sorrento. The wine of the latter place was much recommended by physicians, but it took twenty-five years to ripen, and Tiberius called it "a noble vinegar." There was a brisk demand for certain Sicilian wines, especially those of Messala, Taormina, and Syracuse, and also for those of Central and Eastern Italy, from the vineyards about Spoleto, Ancona, and Cesena, near Ravenna, where, indeed, wine was not merely more wholesome, but cheaper than water. From Aquileia in the North came the *Vinum Pūcinum*, to the use of which Livia ascribed her eighty-two years of exceptional health, and the excellent wine of Istria. The Tuscan wines, as a whole, were considered inferior; the best was that which came from the higher levels of the Mediterranean coast, near the white marble city of Lūna. The Rhætic wine of Verona was particularly esteemed among those of Cisalpine Gaul.

Wines of Spain, Provence, the Mediterranean islands, Greece, and Asia Minor, were always to be found in the Roman market, but those of the East were always prepared for transportation by a treatment with sea-water and resin. Wines which ripened slowly, as those of the



far South almost always do, were often taken when unfermented, and either cooked or exposed to the sun or the action of smoke; and there were Gallic wines, which, like the Scotch whiskey of to-day, always retained a peculiar flavor due to the latter process.

Among the cheaper fermented drinks relished by the Romans were cider, perry, date and mulberry wines.

Mention has already been made of the beverage called *mulsum*, which was compounded principally of wine and honey, and sipped at the beginning of a meal; but other condiments were added to this mixture in almost infinite variety; a species of mulse flavored with pepper, and hence called *pipperātum*, was a special favorite, while more than fifty kinds of distilled liqueurs were manufactured from the juices of different aromatic plants.

---

**The first thing to be noted about the dress of the Romans** is that its prevalent material was always woollen. Sheep-raising for wool was practised among them on an extensive scale, from the earliest historic times, and the choice breeds of that animal, originally imported from Greece or Asia Minor, took so kindly to the soil and climate of Italy that home-grown wool came even to be preferred to the foreign for fineness and softness of quality. Foreign wools were, however, always imported more or less, partly because the supply of native wools seems never to have been quite sufficient, partly because the natural colors of wools from different parts varied so considerably as to render the art of the dyer to some extent unnecessary. Thus, the wools of Canusium (Canossa) were brown or reddish, those of Pollentia in

Liguria were black, those from the Spanish Bætica, which comprised Andalusia and a part of Granada, had either a golden-brown or a grayish hue; the wools of Asia were almost all red; and there was a Grecian fleece, called the crow-colored, of which the natural tint was a peculiarly deep and brilliant black.

**Goats' wool** was rarely used for articles of clothing. Peasants, and especially shepherds, wrapped themselves in goat-skins, as they still do; but only the wool of the long-haired foreign varieties from Spain, Africa, and Asia Minor<sup>1</sup> was regularly woven into rough and heavy cloths, which were used for tent-coverings, for bagging in commerce, for blankets and warm overshoes, and to protect the outer walls of houses in stormy weather against the wind and rain. Ropes and cables were also made of goats' hair.

**Linen cloth** made from the fibre of flax was undoubtedly an Egyptian invention; but the cultivation of the plant was ancient all over Italy, as well as the weaving of home-spun linen fabrics, for the undergarments both of men and women, and the belts and girdles of the latter, for the bandages needed in medical practice, and the awnings (*vēla*) which were used as a protection from the sun. Linen threads were also made, and cords for hunting and fishing-nets. The finer grades of woven linen required in later and more luxurious times for handkerchiefs, table-cloths, napkins, and bedding, and, finally, for entire suits of garments, were always manufactured abroad, especially at Damascus, Laodicea, Tarsus, and Alexandria; and the later Emperors had private

<sup>1</sup> The hair-shirt of later times, *cilicium*, got its name from the Cilician goat.

linen factories both in the East and at Vienna (Vienne in France), where imperial slaves were kept at work to supply the requirements of the court.

**Cotton and cotton fabrics** came always from the far East. Introduced into Greece by the returning soldiers of Alexander the Great, late in the fourth century B.C., they were certainly known in Rome not much more than a hundred years afterwards, for we find the word *carbasi* applied to a stuff by the comic poet Cæcilius Statius in 191 B.C.; now *carbasus* was the technical word for Indian muslin, and it is identical with the Sanscrit name (*karpâsî*) of the cotton-plant. The term was no doubt often loosely employed by Roman writers for linen as well as cotton fabrics; but the latter had the great advantage for the ancients of receiving more readily the blue and purple dyes which they specially affected, and they came on this account to be even preferred by many for purposes of personal adornment.

**Silk** (*sericum*), too, was an article of Eastern luxury, and hardly known in Rome before the end of the republic. The Roman soldiers had indeed seen in 54 B.C. the fluttering of silken banners wrought with gold, and borne before the advancing Parthians; but not until the time of Augustus do we find frequent mention of silken garments, of which three varieties are distinguished, — the *vestēs Coae*, the *vestēs bombȳcinae*, and the *vestēs sēricae*. The Coan robes were extremely costly, transparently fine and thin in texture, purple in color, and usually embroidered with gold. They came from the cocoon of the Chinese worm, and derived their name from the Ægean island, where the silken yarn was spun, dyed, and woven. The *vestēs bombȳcinae* came chiefly from Assyria, where

the native silk was yellowish in color, not silvery white like the Chinese. *Vestis sērica* was a more general term, referring doubtless to the Chinese product,<sup>1</sup> which, however, was more often imported raw or in loose fabrics, which were subsequently unravelled and mixed with linen or wool, then rewoven into light and supple stuffs for the so-called *vestēs subsēricae*. By the fourth century of our era these mixed fabrics had come into rather general use; but *vestēs holosēricae*, or garments of pure silk, were still regarded as a great extravagance, used only by very luxurious persons, on state occasions, or for sumptuous gifts. It was the Emperor Justinian who in 552 imported the first silk-worms into Byzantium, whence their culture spread slowly into Western Europe, although only one out of the dozen or more varieties native in China and Japan, the *bombŷx mōri*, or mulberry silk-worm, ever became thoroughly naturalized and profitable there.

**The spinning and weaving** of early times was, for the most part, done at home, and was the special business of the mistress of the house, and the maids whom she directed. The spinner held the distaff (*colus*), wrapped about with carded wool, in her left hand, under her left arm, or fastened in her waist-band, while with the right hand she drew out the fibres, fastened them to a hook at the top of the spindle (*fŷsus*), and, twirling them slightly between the thumb and forefinger, imparted to

<sup>1</sup>The word *Sēres* meant first silk-merchants, but came afterward to be applied to all Chinamen. So that when Virgil speaks (Georg. II. 121) of the *Sēres* who gather off the trees the soft, fleecy threads which the native worms have left hanging there, he may have used either a commercial or a geographical expression.

the hanging spindle a rotary motion, which continued of itself to twist the lengthening thread. As soon as

the spindle touched the floor, it was lifted, the thread already spun was wound around it, and the process repeated. When the spindle was quite full, the thread was removed and laid in the *calathus*, or spinning-basket.



Colus (Rich).



The most primitive looms of all were vertical, and the weaver worked standing.

They were very simple in construction, consisting of two parallel bars, to which the threads of the warp were attached, above and below, while the shuttle containing the thread of the woof was passed in and out between them, and back and forth. In such a loom the web might be woven either upwards or downwards. The term *sūrsūm versum*, regularly applied to the *tunicæ rēctæ*, which young people of both sexes assumed at maturity, is thought to indicate that they were woven from the bottom up. Later on, horizontal looms were introduced, at which the weaver sat. They were identical in principle with the hand-loom of every age and country, and substantially the same in arrangement; and there is scarce a mountain village in Italy to-day where a *contadina* may not be seen tending a fac-simile of the old Roman machine.

All woollen cloths, and, most of all, the home-made fabrics of the early republican period, had to be finished

by the fuller (*fullo*) before they were fit for use. They were soaked in pits (*lacūnae*) constructed for the purpose, treated with chalk and other alkalis, dried, washed, and dried again; beaten and carded until the separate threads were no longer visible; finally, brushed, shorn, and pressed.

The fullers were early organized into a guild (*collēgium*), with Minerva for their patroness, and an annual feast upon the fifteenth of March; and their art was applied not only to the preparation of new cloths, but to the cleansing and restoration of old garments. A toga made of new cloth, with a full nap, was called a *pexa vestis*; after it had begun to be threadbare it was said to be *trita* or *defloccāta*; when it had been whitened and restored by the fuller, it was a *toga interpolāta*.

The time soon came, of course, when homespun goods no longer sufficed for the clothing of Rome, and then large factories (*officinæ*) had to be established for the weaving both of woollen and linen cloths. Meanwhile it is certain that, with one very important exception, the art of the *tinctor*, or dyer, was seldom employed upon the old-fashioned home-made fabrics. The natural tints, already noted, of sundry foreign wools, furnished all the variety of color demanded by the taste of a primitive time, especially after it became customary to import colored flocks, which were kept strictly separate from the white home-breeds.

The one exception refers, of course, to that historic purple, which was so highly prized as a mark of social and official rank; whose use at Rome the elder Pliny believes<sup>1</sup> to have been coeval with the city itself, and

<sup>1</sup> Plin. Nat. Hist. ix. 39.



borrowed by her early kings from the conquered sovereigns of Etruria. This famous dye, in all its infinitely varying shades, was obtained from two kinds of shell-fish, common in almost every part of the Mediterranean Sea, — the trumpet shell (*būcinum* or *mūrex*) and the true purple-shell<sup>1</sup> (*purpura* or *pelagia*).

The juice of the first was crimson, that of the second nearly black. It was collected, mixed with salt, and heated in metal vessels by the introduction of warm vapor. The color of the *būcinum* was brilliant, but not lasting. By mixing with the darker *purpura* it became fixed, and those violet or amethystine tints were produced which appear to have been preferred for the *clāvus lātus* and the striped borders of white garments. The true Tyrian purple, first introduced into Rome about the middle of the last century B.C., was produced by a double process of dyeing, first in half-boiled *purpura*, and then in *būcinum*. A fabric thus dyed appeared nearly black in shadow, but the high lights upon its folds were of a glowing red.

A pound of amethyst or violet wool in Cæsar's time was worth about \$20; a pound of real Tyrian, more than ten times as much. At a later period, the *blatta* came into use for both grades of purple, and paler shades than those of the original dye, as well as a whole range of blues, were produced by mixing it with different animal and vegetable substances. Clear scarlet was obtained from the *coccus ilicis*, a species of cochineal, and from the red *fūcus*, or rock-lichen. The *trabea*, or robe worn by augurs, and on certain occasions by *equitēs* (knights),

<sup>1</sup> The latter is the *buccinum lapillis*, the former the *murex brandaris* of modern conchology.



was of striped scarlet and purple. The *palūdāmentum*, or short military cloak worn by a Roman general over his armor, was of a reddish purple, but robes made entirely of *blatta*, or fine pure purple, were considered strictly appropriate only for *triumphātōrēs*, who also had them richly embroidered, and later for imperial personages. That their use was constantly affected by others is, however, evinced by the prohibitive decrees of different emperors, as well as by a very curious passage in Ovid<sup>1</sup> in which he gives it as his opinion that costly robes of pure purple are unbecoming to a woman. He advises instead pale sky-blue or rose pink, a very faint amethyst, or sea-green. Otherwise the deep tint of the Paphian myrtle, the soft gray of a crane's plumage, the brown of acorns or of almond-shells. All this proves very good taste on the poet's part, and that the superiority in costume of half-tints over pure colors was already acknowledged by the truly æsthetic.



Paludamentum  
(Rich).

We come now to the form of garments both masculine and feminine. From the earliest historic period the Romans appear to have worn at least two articles of clothing, — a tunic and a toga. Some wore instead of the *tunica* an under-garment called the *subligāculum*, which was little more than such a bandage as the gymnasts wore when exercising, and which was preferably, if not always, made of linen. The tunic was necessary indoors, however, where it was considered bad manners not to lay the toga aside. The tunic was a species of woollen

<sup>1</sup> Ov. Ars Am. iii. 169–188.

shirt, made with front and back pieces, which were sewn together on the shoulders and under the arms. Either it had no sleeves, or the sleeves were short, not reaching below the elbow. Long-sleeved tunics



Tunica (Rich).

(*tunicae manicātae* or *manuleātae*) were considered the height of effeminacy, and never came into general use before the third or fourth century of our era. The tunics of the common people were belted in above the hips, and did not hang below the knee. Those who were entitled to the *clāvus lātus*, or broad purple stripe down the front, which was always so arranged as to hang outside the girdle, wore them somewhat longer; soldiers and

travellers, even shorter. In the time of Plautus it had become customary to wear also an undershirt or tunic, called the *tunica interior* or *subūcula*, which was also regularly made of wool, never of linen, until late imperial times.

We have already seen how the toga was first put on at the age of maturity, with public and impressive ceremonies. It remains to say a few words concerning the shape and arrangement of this celebrated garment. It was of white woollen cloth, which in the case of curule magistrates had narrow purple stripes inwoven for a border. It appears to have come from the loom in an oblong form, and afterwards to have been rounded at the corners into that of an ellipse. Its length must be three times the wearer's height measured downwards from the shoulder. Its breadth varied greatly with time, fashion, and the quality of the cloth. The toga of the early

period was comparatively narrow, and the rough, coarse fabric of which it was made permitted no artistic arrangement. In those days the toga was the garment of war as well as of peace, and when worn in the field it had no loosely hanging ends, but was bound tightly around the body in what was called the *cinctus Gabinus*. Later, after the introduction of the *sagum*, or short square military cloak, fastened upon the shoulder with a *fibula*, or brooch, the toga became the distinctive garb of peace, and gave scope for enormous vanity, both in its texture and in the mode of wearing it. It was made of ever finer and finer cloth, the supple folds of which were assiduously studied and arranged. The broader the cloth, it was observed, the more graceful the effect which could be given these folds, hence the fashionable toga increased in width, until it became nearly circular, and Horace jeers<sup>1</sup> at the freed-man who paraded the Sacred Way in a toga four yards (*bis trium ulnārum*) wide, to the scandal of the passers-by.



Cinctus Gabinus  
(Rich).

This elliptical garment was first folded, not exactly on its longest axis, but so as to leave the edges a little way apart. One end of the folded cloth was now flung over the left shoulder from behind so as to fall to the feet in front. The remaining two-thirds of its length were then brought around under the right arm, and the folded cloth so spread as to cover the right side from the armpit to the calf of the leg. It was then gathered and carried up

<sup>1</sup> Hor. Epod. iv. 7, 8.

across the breast, to be thrown backward over the left shoulder. The diagonal breast-folds constituted the *sinus*, which often served the purposes of a pocket. The portion of the toga first thrown over the left shoulder, and lying beneath the *sinus*, was in later times pulled up so as to hang a little way over it in what was called the *nōdus*, or *umbō*. This precaution was supposed to give firmness to the whole arrangement; but the toga must always, one would think, have been fastened to the tunic, at least upon the shoulder, else it is impossible to conceive how the wearer could have had any freedom either of locomotion or gesticulation. There seems some reason to believe that the toga of imperial times was cut out in the form of a semi-ellipse, and partially fitted to the person, while a portion was pressed into fine folds by the fuller before wearing. At the opening of the temple of Janus at the Ambarvalia, or ceremony of blessing the fields for a good harvest (which was observed on May 27th, and is still observed in most Latin countries), and upon certain other solemn public occasions, the Gabinian or girded toga was regularly worn.

Candidates for office derived their name from the custom which required them to appear in a *toga candida*, or pure white toga, either quite new or freshly treated with chalk. The mourning toga was originally black; later the darkest blue was also worn.

The working-classes used, for defence against the weather, an outer cloak called *paenula*, made of thick, hairy, dark-colored frieze, or even of leather. It had no sleeves, but was usually provided with a hood (*cucūllus*), and hooked or buttoned closely all down the front. The obvious convenience and snugness of this garment caused



THE EMPEROR TIBERIUS, WEARING THE TOGA.



it eventually to be adopted as a travelling wrap by men, and even women, of all ranks, and the host's first duty to a guest was to unfasten his *paenula*.<sup>1</sup>

The *birrus* or *burrus* was another outside garment of similar cut, made usually of rough, red cloth. The *lacerna* was of lighter and more elegant material, and worn outside the toga, less for use than for show. Evening-dress, as we understand it, was represented by the *vestis cēnātōria*, which appears to have been an exceedingly light and airy mantle, presumably of rich material, and almost always gaily colored, — green, blue, crimson, and variegated. It was easily thrown on and off and sometimes changed several times in the course of one ceremonious dinner.

The primitive Roman, like the barbarian everywhere, was long-haired and long-bearded. The razor and the shears — *novācula* and *forfex* — are indeed mentioned early, the former in the reign of Tarquinius Priscus; but we are expressly told by the elder Pliny,<sup>2</sup> that Scipio Africanus was the first Roman who ever shaved daily, while the beard of Augustus was always cut. The first hair cut from the head of a child, and a youth's first beard, were consecrated to the gods; but the coins of the late republican period show plainly that young men usually wore a beard, though carefully trimmed and dressed, and were seldom clean-shaven before forty. To

<sup>1</sup> Hence, too, *scindere paenulam* (to rend the cloak) became proverbial for giving a visitor a pressing invitation to remain; and we find Cicero saying to Atticus (Ep. xiii. 33) of an unwelcome guest, "*Sed ita feci, ut non scinderem paenulam,*" meaning that he sent him about his business without delay.

<sup>2</sup> Plin. Nat. Hist. vii. 59.



let the beard grow long was a sign of mourning, whether for private loss or public calamity, and continued to be so regarded until the Emperor Hadrian re-introduced the fashion of the full beard even for middle-aged and elderly men.

There were frequent changes, also, in the mode of masculine hair-dressing. In Cicero's time it was elaborate, and depilatories and hair-tongs (*psilōthra* and *calamistrī*) were among the barber's regular weapons, whether the latter were a house-slave, or the keeper of a *tōnstrīna*, or barber's shop. In the time of Marcus Aurelius the artificially curled and perfumed head was no longer considered in good taste. Later, it became fashionable for even imperial personages to wear the hair close-clipped, like athletes and the Stoics.

For head-gear the Romans had the *pīleus* and the *petasus*. The former was a close-fitting felt cap, worn by



Pileus (Rich).

sailors and artisans, by a freedman as the sign of his emancipation, and by the whole population on the Saturnalia, but otherwise used by the upper classes

only when journeying. The *petasus* was a felt hat with a round brim, worn principally by comic actors, and by the spectators in a theatre, as a protection against the light from above. A well-born Roman of the best period, however, — whether man or woman, — usually disdained any species of hat or cap, but walked abroad uncovered.



Petasus (Rich).

For the clothing of their feet, the Romans made use both of shoes (*calcei*) and sandals (*sandalia*). Every Roman order and every great tribe or *gēns* had a distinctive kind of shoe. The ordinary *calceus patricius*, or patrician shoe, also called *mūlleus*, was made of red leather, with a high heel, and straps to fasten it about the ankle. It had also a crescent-shaped ornament upon the front, called the *lūnula*, which was of very ancient origin, and seems, like the *bullā*, to have had the force of a charm.



Shoes and sandals (Becker's Gallus).

The second grade of shoe, only a little less dignified than the *mūlleus*, was the *calceus senātōrius*, which was of black leather, with four straps and no *lūnula*. Another kind of shoe, called the *pēro*, and rather resembling a boot, worn in wet or snowy weather, and always by the *equitēs*, was also black, and fastened by a simple tie. The ladies of the higher classes wore, out of doors, *calcei*, made of a fine leather called *alūta*, and richly embroidered in silk and gold. At home, both men and women preferred to wear sandals, or simple soles, bound to the foot with straps or ribbons, but it was long regarded as a great breach of etiquette to wear sandals abroad. The craft of the *sūtor*, or shoemaker, was always a particularly respectable one, and

theirs was one of the original colleges founded by Numa.

The civilized Roman lady, like her lord of the same period, wore three garments, — a *tunica intima*, a *stola*, and a *palla*. The woollen undergarment was virtually the same for both sexes. The *stola* was much longer



Euterpe with stola and palla  
(Baumeister).

than the masculine tunic, slit open at the top on either side for the passage of the arms, fastened again upon the shoulders with clasps or brooches (*fibulae*), which were often articles of great value. It was usually finished at the bottom by a ruffled border or flounce called the *instita*, which admitted of embroidery or other decoration. Sometimes it had tight sleeves reaching to the elbow and fastened together on the back of the arm with gold or jewelled buttons, a charming mode, represented upon many existing statues. The *stola* was confined at the waist by a girdle, but pulled up so as to conceal the latter by its falling folds (*rūgae*). This

beautiful garment was the matron's robe of honor, and only married women of unblemished reputation were allowed to wear it.





MISS ROMAN PALLA.

The *palla* was the outer garment which took the place of the *toga*, and was worn in a similar way. It was a square or oblong piece of stuff, thrown forward over the left shoulder and falling to the feet, then carried around the back, either above or below the right arm, and again thrown backward over the left arm or shoulder. Like the *toga*, it could, if necessary, be drawn up over the head. Women of the lower orders, or those not privileged to wear the *stola* wore, directly over the under-tunic, a *palla* made of woollen cloth, turned over at the top and folded round the body under the arms, then drawn up and fastened upon either shoulder with clasps or simple buckles. It thus lay double over the breast and back, but fell in a single thickness to the feet. To judge by the management of the folds in existing illustrations, the stuffs most affected for their outer garments by Roman women who aspired to elegance, were always fine and thin. The mixed fabrics already described, of silk and wool or silk and linen, were probably most employed, pure silk being always an article of great luxury, while the very fine linen and cotton stuffs to which the word *byssus* was indifferently applied, were a late fashion and fit only for summer garments.

We have already learned from Ovid how wide was the range of colors from which a Roman belle could choose. She enjoyed hardly less latitude in her hair-dressing, the styles of which were infinite. The graceful antique fashion had been to gather the hair altogether in a knot at the back of the head, sometimes low in the neck, but oftener lifted high upon the crown, and we find the early fathers of the Christian Church, — Jerome, Tertullian, Prudentius, — pleading earnestly for a return to this


decent and simple mode, and sternly denouncing the ugly and costly artificial structure of cushions, braids, and curls then greatly in vogue. Entire wigs (*capillamenta*) were much worn in the first century, and those made of blonde hair brought very high prices.

**Gold and jewelled ornaments**, *annuli* (rings), *monilia* (necklaces), *armillae* (bracelets), worn either at the wrist or above the elbow, with a sleeveless tunic, were affected both by men and women of fashion, and were often of exquisite workmanship. All the principal precious stones, diamonds, rubies, emeralds, opals, were known to the Romans, but the gem which they prized above all others was the pearl; and unheard-of prices were paid for large single specimens, to be worn as ear-drops or upon the brow. Julius Cæsar is said to have given to Servilia, the mother of Marcus Brutus,<sup>1</sup> a solitaire pearl for which he paid six million sesterces (\$262,500), while Caligula received with his wife Lollia Paulina a complete *parure* of pearls and emeralds, which was an heirloom in her family; a part of the spoil taken in Eastern war by her grandfather, Marcus Lollius, in the year 2 B.C., and valued at forty million sesterces<sup>2</sup> (\$2,180,000). Slippers embroidered with seed pearls were common among the rich, and sometimes affected, as the elder Pliny complains, even by the comparatively poor.

<sup>1</sup> Suet. Caes. 50.

<sup>2</sup> Plin. Nat. Hist. ix. 35.





JEWELRY AND TOILET ARTICLES.



## CHAPTER V.

## AGRICULTURE.

SMALL holdings were certainly the rule among the early Romans. Tradition even averred that Romulus had allotted to each of his followers but two *iūgera*<sup>1</sup> of land. After the expulsion of the kings, the tribune Licinius was said to have decreed an allowance per capita of seven *iūgera*. This did not apparently prevent a proprietor from increasing his possessions if he saw fit, but laws more decidedly restrictive had soon to be passed. Five hundred *iūgera* was fixed as the maximum holding, and one of the reforms which the Gracchi favored was a further reduction to two hundred.

The former number remained the nominal maximum down to historic times, and even after the restrictive law had become a dead letter, there was a sentiment in favor of small holdings. "Praise large farms, but till a small one," is the witty precept of Virgil.<sup>2</sup>

Naturally, as the farm increased in extent, the mode of working it became more complex. Two *iūgera* the owner could manage without assistance; when his possessions increased to seven, he may have had a slave or two to aid him, and perhaps an ass; but seven *iūgera* would certainly not support a pair of oxen, and indeed

<sup>1</sup> About 1½ acres: see table.

<sup>2</sup> Geor. ii. 412-18.

the spade always held its own against the plough in Roman agriculture.

In the management of large holdings three methods appear to have been practised. A farm might be let for a fixed money rent, or let on shares with the rent paid in kind, or the owner might choose to be his own farmer, making use of either slave labor or free, or what was perhaps most common of all, having a permanent staff of slaves, and supplementing these with hired hands at the seasons when work pressed, as at the vintage.

**In choosing a farmstead**, the chief thing to be avoided, was an unhealthy district. A marshy soil was always to be shunned, and so was a river-bank, though an ample water-supply was indispensable. The ideal situation was a hillside gently sloping to the east. Here the master's residence could be adapted to receive the sun in winter and the breeze in summer, drainage was easily managed, and the very best soil for vineyards and olive-orchards secured. Facility of transportation for the farm-produce was a great desideratum, yet Columella<sup>1</sup> advises against a situation immediately on a high-road, both on account of the depredations of the casual passer-by, and because of the perpetual calls on the owner's hospitality.

The estate purchased, the proprietor's first care was to have its boundaries clearly established. There was a pleasant fashion of following its outer line with a close-set row of trees all of one kind, as elm, ash, or cypress; or it might be enclosed with hedge or fence, or by a ditch and earthen bank. Otherwise its limits were indicated merely by boundary stakes.

The next point to be considered was the choice of a

<sup>1</sup> Col. De Re Rus. i. 5.

crop adapted to the soil, and we find great difference of opinion among the writers on agriculture as to those which promised the best return. All agree, however, in lamenting that so many estates were given over to the grazing of cattle and sheep, to the detriment of agriculture proper. The majority follow Cato in giving their first preference to a choice vineyard, though the vine required more labor than any other crop. To one hundred *iūgera* of vineyard Cato allows ten laborers, one ox-herd, and one yoke of oxen, one ass-driver with three asses (two for the carts and one for the mill), a swine-herd, and a man to look after the willow plantations, from which came the withies for binding the vine, while all the osier baskets required in stripping the vines, gathering the grapes, etc., were woven on the premises.

Two hundred and forty *iūgera* of olive-orchards were stated by the same authority to require five laborers, three ox-herds for as many yoke of oxen, a pig-tender, an ass-driver with four asses, and a shepherd with a hundred sheep.

**The farm-hands**, whether many or few, were always under the supervision of a *vilicus* and *vilica*, an overseer and a housekeeper, as we might say.<sup>1</sup> This pair was often, though not invariably, husband and wife. The overseer had to keep a sharp lookout over the slaves by night and day, provide their food and clothing, see that the farm-tools were in good condition, and in general that everything might be ready for the master's inspection at any moment. The sphere of the *vilica* was within doors, except for the care of the *gallinārium*,

<sup>1</sup> These offices are perpetuated on the Italian villa farm, where a *fattore* and *fattoressa* are always to be found.

or poultry-yard, where, if there were ever a dearth of fowls or eggs, she was the person held responsible. She saw to the cooking and sweeping, the pickling and preserving. She was also warned to be no gad-about, and not to presume to offer any sacrifices; for the master of the house undertook the religious responsibilities of the whole *familia*. Yet on feast-days, and on the Calends, Nones, and Ides of each month, she was to adorn her hearth with a wreath of flowers, and offer to the *Larēs* her prayers for plenty.

The food of the *familia rústica* consisted of a liberal daily allowance of bread, wine, oil, salt, and some sort of relish, such as pickled olives or fish. Every two years the hands received a pair of wooden shoes, and on alternate years a tunic and a hooded cloak of shaggy cloth (*sagātus cucūllus*). They were also supplied with patchwork coverings called *centōnēs*, made up by the female slaves from the sound bits of all sorts of cast-off garments, which might be used either as bedding, or by way of protection from the rain. Special favors in the matter of diet and clothing were often shown to highly deserving slaves; but the punishment, even of trifling offences, was frequently barbarous.

The slaves were divided into those who worked in fetters (*compeditī, alligatī*), and those who were allowed liberty of motion; and a great distinction was made in their housing; for while the latter had a large common room where they might meet in the evening and on rainy days, and separate cells to sleep in, airy, above ground, and with a southern aspect, the former were lodged in basements lighted only by narrow windows too high to be reached by the hand, and in these underground

chambers refractory cases were kept at indoor work by day. There would also be upon large properties a separate *balneum*, or bath, for the slaves.

The farmer is earnestly warned against over-building; but the constructions prescribed as necessary for the farm activities seem to furnish an ample allowance. The rapid increase of luxury in the two hundred and fifty years between Cato and Columella is clearly shown by the difference in their provisions. The buildings enumerated by the latter are certainly more elaborate than anything to be found upon Italian farms to-day, though many of his precepts are still implicitly obeyed. And since he, too, prefaces his description by strenuous injunctions not to build too extensively, his account may be taken as affording a fair idea of an affluent Roman farmstead.

The master's dwelling, or villa proper, stood a little apart from the rest of the buildings, with long ranges of rooms for summer and winter, covered galleries, and a separate bath. Nearly all the other structures were grouped about a great central court-yard (*cors*), which was carefully enclosed, and had but a single gateway, affording the only means of entrance not merely to the court-yard itself, but to the surrounding stables and store-houses. Over this gateway in large establishments a porter or janitor always presided. In those of less pretension, the *vilicus* had his rooms there, and it was his place to see that no one passed after dark without his knowledge. Here, too, was chained the watch-dog, with the broad spiked collar, familiar to us from old mosaics, who had been carefully trained to his duties of defence. On this same side of the court-yard were the slaves' quarters and the farm-kitchen.



The court-yard was always kept strewn with litter which was removed from time to time, and added to the manure-heaps. These last were built within the court, and allowed to ripen for at least a twelvemonth, before being applied to the land. Here, too, was a pool of fresh water, not only for watering the stock, but large enough for oxen to bathe in. It was supplied by running water, where this was practicable, in other cases, by rain-water, which the Romans well understood the art of collecting and utilizing.

First in importance among the *stabula*, or buildings for sheltering the animals, were the *būbilia* for the oxen and cows. These were long, narrow buildings, usually set at right angles with one side of the court-yard, and they accommodated only a single range of cattle, with room for a passage-way before their mangers. Six or seven feet above the ground ran a horizontal beam, to which the animals were tied. The flooring was of wood or stone, and well bedded with coarse hay or straw, and the barn seems often, if not always, to have had a loft for storing fodder.

Cattle were bred rather with a view to their powers of draught, than for beef, as is clearly seen in the points given of a model ox. The favorite color was red or dun, though we find frequent allusions to the fine silver gray breed of Central Italy, still extensively maintained. On account of the difficulty of acclimatizing foreign breeds, the farmer who wished to form a herd was advised to buy young cattle in his own neighborhood, and to make the following stipulation with the vendor:<sup>1</sup> "Do you answer for it, that these two-year-olds are perfectly

<sup>1</sup> Varr. R. R. ii. 5.

sound, and from a healthy herd, and that the purchase of them will involve me in no trouble?"

Bullocks were usually broken to the plough when three years old, and this was most carefully and thoroughly done, as was indeed necessary, seeing that the man who held the plough drove as well. This slave, the *būbulcus*, also took care of his yoke of oxen, washing and carding them, and giving them a sort of *massage* treatment, supposed to prevent the skin from adhering to the flesh. He is further recommended to give them each a quart of wine if they come back tired from the field.<sup>1</sup>

The working of from eighty to a hundred *iūgera* was given to one yoke of oxen; but in ploughing, they were only allowed to draw, without breathing, what seems to us the incredibly short furrow of one hundred and twenty Roman feet.<sup>2</sup> The yoke (*iūgum*) was sometimes fastened to the horns in the present Italian fashion, by which all the draught comes upon the forehead; but more often rested, as with us, upon the neck; but in place of a closed wooden bow, leathern thongs (*lora*) were tied around the neck. Neither oxen nor horses were shod, as we understand the term, but they often wore a sort of leathern boot (*solea*), which was strengthened upon its sole by strips of metal. This fashion seems to have been later than Cato, who recommends protecting their hoofs against cracking, on long journeys over the paved high-roads, by daubing them with pitch.

In many parts of Italy the climate was genial enough to afford fresh fodder all the year round; in which case

<sup>1</sup> In England, hunters are often given beer after a hard run.

<sup>2</sup> See Tables.

a farmer was advised to double the number of his yokes of oxen and work and pasture on alternate days. When stable-fed, the oxen received hay, straw, barley, and other grain. But besides these staple articles, many others figure in their diet, such as beans and acorns, the refuse of the vintage, and the freshly plucked leaves of many trees.

A hundred was considered the extreme limit in number of a herd of cows, and these were chiefly kept for breeding; for it must be remembered that butter was unknown to the Romans, though cheese was a common article of food.

Very singular and sometimes very unpleasant remedies are recommended by the Roman authorities for the various diseases to which neat flesh is liable. The following is declared by Cato<sup>1</sup> to be an almost universal panacea: "a raw egg swallowed whole, to be followed next morning by an onion bruised in a half-pint of wine. Let a fasting man see that the ox drinks this fasting,

and let both man and beast stand while it is being swallowed."

The *būbilia* were required to have a southern exposure for warmth in winter, and a shady yard adjoining, where the cattle might be turned out in summer.



Equile, stable (Rich).

Many of the same general prescriptions held good for the *equilia*, or stables for horses and mules; but these were

<sup>1</sup> De Re Rus. lxxi.

also provided with separate cribs fitted with racks, and though single stalls seem to have been unknown, it was customary to divide the horses by a swinging pole called the *longurius*, which prevented their interfering with one another. The breeds of horses were innumerable, some being preferred for one purpose and some for another.

**Race-horses** commanded the highest prices, choice mules the next, then ordinary animals, whether intended for carriage, saddle, or draught. These last might be broken in at two years old; but the race-horses waited another year, and nearly as much more time was spent in their training, so that they were four when they went upon the track. Horses were carefully cleaned and rubbed down each day; but it seems to have been thought necessary to give them bedding only if their stable had a stone floor. Columella says, however,<sup>1</sup> that oak-wood is much better.

The high feeding of horses is insisted upon; also broad meadow-lands, where the grass is short and sweet, and the water-supply unfailing, are recommended for their pasturage. The Romans, like ourselves, judged of a horse's age chiefly by his teeth, and their knowledge of his anatomy was surprisingly accurate; but the medicaments with which he was treated when out of condition show a very elementary stage of equine pathology.

**Asses were much used upon a Roman farm**; for, besides serving as beasts of burden,—and, if fitted with a pair of paniers, they can carry a surprisingly heavy load,—they were also used for light ploughing, to turn the mill, and to raise water from the wells. Black or spotted

<sup>1</sup> Re Rus. vi. 30.

asses were preferred to mouse-colored, merely because they were more rarely found.

Nothing could be more generally useful upon a Roman farm than a flock of sheep. Lamb and mutton, it is true, appeared only upon the tables of the rich, but the milk of ewes, and the cheese made from it, were important articles of diet, and their fleece furnished the clothing of the family. White was the color preferred, though certain breeds of black and brown found some favor, and fancy breeds of various colors, notably a reddish yellow, from Baetica in Spain, were raised as curiosities. Sheep were also broadly divided into two classes, soft and harsh fleeced, of which the former were more delicate, and their wool more valuable. Out of many breeds, the farmer is recommended to choose that which may best suit the pasturage at his disposal, and to be careful that the stock is pure, for the one perfectly worthless fleece was grizzled or spotted. So, in a white flock, lambs were to be rejected, not only if they had any spots of dark color on fleece or skin, but if their tongue and palate were black—an infallible sign of mixed breed.

Sheep were turned out to pasture during some part of the day, nearly all the year round, the morning and evening frost being avoided in winter, and the mid-day heat in summer. For the same reason, though the sheep-fold (*ovile*) was built low and narrow to protect the flock in winter, it had always a large and shady yard adjoining, where they could be turned out in summer. The fine-wooled sheep, as those of Tarentum, were chiefly fed indoors, while the reverse was true of the coarser breeds; but the shepherd is warned that his

wards must never under any circumstances go hungry, and also that they will soon weary of any kind of food and fall seriously ill unless they have an abundance of salt. If the sheep were to browse, the pasturage must be free from those thorny brambles which were so injurious both to the fleece of the animal and to its skin when freshly sheared. The shepherd is also to keep a sharp lookout for snakes. Virgil recommends smoking them out of their holes by fires of cedar and other aromatic woods, but Columella considers it a more efficient precaution frequently to burn women's hair or stag's horn in and about the fold.

**The Romans sheared their sheep**, as we do, in the spring; but they preferred that lambing-time should come in the autumn, winter being considered a less dangerous season than summer for young flocks. A thousand head of sheep might be folded together with safety, but a shepherd was allotted to every hundred, and each shepherd seems to have been accompanied by a dog. These dogs were apparently the direct ancestors of those who guard the flocks upon the Roman Campagna to-day, and no one who has made the acquaintance of the latter can read without a grim smile the following suggestion of Columella:<sup>1</sup> "The shepherd prefers to have his dog white, as this color contrasts with that of wild beasts. And it is important to have some such broad distinction, or else when he is driving off the wolves in the dim light of dawn, he is likely to hit the dog instead of the beast." It may be noticed that docking a dog's tail was supposed to be a preventive of hydrophobia.

The shepherds and goat-herds also set up temporary

<sup>1</sup> Re Rus. vii. 12.



huts of conical shape (*casulae*) for shelter, as their successors do to-day ; but one object now aimed at, that of raising themselves sufficiently from the surface of the ground to be out of the reach of the malarious fogs which only rise a few feet above the Campagna soil, did not exist when the region was generally and very efficiently drained.

Next in importance to the sheep came the black-coated, silky goats, from whose hair ropes were woven, and a fabric cheaper and coarser than cloths manufactured from sheep's wool, but to a certain extent water-proof. They were less delicate, too, than sheep and could be pastured on rougher ground, and it was probably for this reason that a goat-herd had charge of only half as many animals as a shepherd. He was to be a sturdy man, with a quick eye and a sure foot, for his flock had to be led, not driven, by him, as was the case with most other creatures. Cheese was made from the milk of goats as well as from that of ewes and cows, and there were several varieties, from the simple curd for immediate use, to one which would keep indefinitely and even bear transportation over sea. Cheeses made from ewes' milk were considered more digestible though less palatable than those made from cows' milk, while the reverse was supposed to be the case with goats'-milk cheeses.

Black-haired pigs were insisted upon for cold districts ; but if the climate were mild, the more tender white breeds might be raised. Each sow was given a separate pen opening on a central yard, where there was a tank of water, but this opening had a barrier so high that while the sow could get over it, her pigs could not. They were driven to woodland pasture nearly all the year, and



even when kept in, acorns were still the chief article of their diet, though beans were also given them. They were thought fit for sacrifice when ten days old (whence *sacer* was the name of a ten-days-old pig among the early Romans); and if there were a market-town near by, it was considered most profitable to sell them as sucking pigs. Hogs were also fattened for the sale, and Varro mentions with admiration that they were sometimes made too fat to stand upon their feet.

So far, the arrangements of the farm show merely a legitimate development from the early Roman methods; but when we come to its feathered denizens, we perceive at once the overweening influence of Greek fashion. Greek names, in their original form, or barely Latinized, are continually employed, while the Romans quite vaunt themselves on having stood out against the Grecian practice of cock-fighting. The game-cock was, however, the favorite breed in Italy as well as in Greece. **Two hundred hens were considered a fair number for a flock,** and one man, with a child's help, could take care of so many. The following was the most approved way of housing them. The central hen-coop (*gallinārium*), seven Roman feet on each of its three dimensions, was flanked on either side by a wing of the same breadth, twelve feet high and twelve feet long, divided into two stories by a flooring seven feet from the ground. These wings had no outer door, but communicated through the central coop, which opened on the court-yard, where the fowls were turned out, to scratch and feed through the day. The walls were pierced with windows, which were, however, securely barred against the incursions of evil beasts. Two fashions of providing the hens with nests

obtained: the first was to hang osier baskets along the walls; the other, and more approved method, was to build these walls so thick that rows of nests could be hollowed out of them, like the niches in a columbarium. In either case, a *vēstibulum*, or perch, was provided before each nest, so that the hens might not break their eggs by flying straight upon them. Notched stakes served them for stairways to the upper stories of the wings, and the whole coop, like all *aviāria*, was to be coated within and without with highly polished cement, as a precaution against cats and snakes.

Cleanliness was greatly insisted on, as well here as in the more elaborate geese and duck yards (*chēnoboscīa* and *nessotrophīa*). Hens were fed upon various kinds of dough, and their water-dishes were fitted with covers pierced with holes large enough to allow the head to pass easily through, whereby, also, the water was kept clean.

The dove-cote (*columbārium*) was arranged on the same general principles, except that it was constructed high above the ground, and the purchase of white pigeons as well as that of white hens was discouraged because of their being conspicuous objects to birds of prey. Pigeons certainly commanded fancy prices, *ducēnī nummī* (about nine dollars) being thought a fair amount for a pair of perfect birds even in Varro's time, while five times this amount was not uncommon.

Thrushes (*turdī*) were caught and fattened for the markets, as were also blackbirds (*merulae*), ortolans (*mīliāriæ*), quails (*cōturnīcēs*), and other wild fowl. This class of winged creature was all housed together, often to the number of several thousand. The *ornīthon*,

as their place of confinement was called, was often built along a covered walk, and separated from it only by a netting, so that the owner might admire his treasures as he took his daily exercise; but this is not recommended by all authorities, some being of opinion that the spirits of free-born birds were depressed in captivity by the sight of vegetation.

**Peacocks** also (*pāvōnēs*) were kept for show from early times, but after Quintus Hortensius had set the fashion of eating them, their cultivation became one of the most profitable industries of the Roman farmer; for their eggs fetched ten dollars a dozen, and the birds themselves seventeen dollars a pair. Their coops and feeding-ground were usually, however, at a considerable distance from the farm-yard.

This was also the case with water-fowl, for whose well-being the most elaborate arrangements were made. They had great yards set apart for them, surrounded by high and smoothly polished walls, and covered by a strong netting. In the yard was a pond, fed by running water, supplied with gently sloping verges, and planted with all the most palatable water-weeds, while around its grassy brim, nests were built, separated from each other by box-hedges and furnished with troughs for the daily supply of grain.

In the luxurious days of Rome, fish and wild animals were preserved even on comparatively modest estates, and a snail-yard was rarely absent.

**Bee-culture** received great attention from the Romans, in whose diet honey took the place of sugar. The superlative excellence of pot-herbs, and above all thyme, for flavoring honey, was insisted on by all writers, but no

one has described this branch of agriculture so charmingly as Virgil.


To return to the court-yard and the buildings about it. There were sheds for the housing of unthreshed grain and unpressed olives, granaries and storerooms for fruit, wine, and oil. Fodder was more often stacked than housed, but farm-implements were kept under cover, and the more portable of them under lock and key. In small tools the farmer of those days was perhaps deficient, but for working the land his means were abundant. The long prevalence of hand labor probably accounted for the astonishing variety of spades, mattocks, and rakes,



Rutrum (Rich).

for whose Latin names it is not always easy to find exact English equivalents. The *rutrum*, the weapon with which Remus was killed, was a kind of shovel. They had a sort of spade called the *pāla*, both with iron and wooden blade, and this implement was sometimes made with a

cross-bar for the foot to rest on. The latter tool is called in Italian *vanga*, a name which is also found in late Latin. For digging, spading over the land, breaking up fresh soil, etc., the Romans used tools of the nature of the mattock, which, while they did the work of a spade, were handled like a hoe. Under this head came the *ligo* (also used as a hatchet); the *bidēns*, with blade notched into two teeth; the *capreolus*, where these two teeth were curved inward like a goat's horns, and the *rāster*, which looks like a horseshoe tied to a handle. These were all heavy enough to do the work of the plough,



Bidens (Rich).

and were indeed thought to break up the ground more efficiently.

The names of *ditcher* and *ditching* (*fossor* and *fossio*), given to the man who thus dug over the ground and to the work which he performed, shows that the earth must have been thrown in successive cuts from one side to the other of a perpetual trench, and there was a clever little machine, the *cicōnia*, for testing the faithfulness of the labor and making sure that this trench was kept straight and of unvarying depth and width.

Of lighter weight than the tools already mentioned were the *marra*, with broad, notched blade, and the *sarculum* and *āscia*, which nearly corresponded to a long and short handled hoe. The *rāster* was also found with several teeth, and its diminutive, *rāstellum*, was a wooden rake; the *pecten* was yet another rake, perhaps of iron.

*Falx* is the general name for scythe, sickle, hedge-bill, or other agricultural implement of like nature. Most curious of all was the *falx*

*vīnitōria*, the vine-dresser's pruning-hook, with its many edges. Columella<sup>1</sup> gives a minute description of this tool, which would very well describe the more elaborate of English hedge-



Falx denticula (Rich).



Falx vinitoria (Rich).

bills. The *falx denticulāta* must also be noted, a sickle with saw-toothed blade, for cutting the grain just below the ear, a practice recommended as facilitating its threshing. The Romans had both a two-pronged iron fork (*furca*) and a wooden one with many teeth, used

<sup>1</sup> De Re Rus. iv. 25.

for tossing the straw lightly about the threshing-floor, that the wind might detach the chaff, and hence called *ventilābrum*.


Leaving the hand-tools we pass to those which had to be worked by cattle. Of these, the most important was, of course, the *arātrum*, or plough. In its primitive form



Arator (Rich).

it was made entirely of wood. A stout-branched sapling was chosen, with a sharp curve, one end was pointed for the *vōmer*, or share, while the other end was left long enough to serve as a pole (*tēmo*) for the oxen; at the point of

junction (*būris*) between *tēmo* and *vōmer*, a handle (*stīva*) was inserted, which the ploughman (*arātor*) held in guiding. A plough hardly more elaborate than the one here described is still used in the wilder and remoter parts of Italy. Virgil's plough<sup>1</sup> is certainly a slight advance on this, and in later Imperial times the Romans had



Arātrum (Rich).

ploughs with nearly every feature of our own, though ruder in construction. They had ploughs with coulter and without, ploughs both with and without wheels, ploughs with no mould-board, with one, and with two, some with broad shares, and some with narrow, to suit the nature of the soil, and their two-fold service of

<sup>1</sup> Virg. Geor. i. 169–175.



breaking ground and ploughing in seed. It appears clear, however, that the plough in common use could not turn over a furrow when held in an upright position, but must be guided a little obliquely, that the weight of the beam might bear on the freshly cut earth. This process made a sloping narrow furrow, and in order thoroughly to work the ground, good farmers commonly turned back (as the double face of their share permitted) and ploughed a full, upright furrow in the same line. The necessity for going twice over the ground made the advantages of the *arātrum* over the *bidēns* much less than those of the plough over the spade. A bas-relief found in the island of Magnesia shows one of the ploughs which were adapted for covering in the seed, and making a channel for water between the ridges, an instrument which was in constant use in the palmy days of agriculture about Rome. The plough here depicted has for share-beam (*dentāle*) a narrow plank some four feet long, shod at its forward end with an iron share (*vōmer*), which extends above and below the beam, like an arrow-head on its staff. To the sides of the *dentāle*, directly behind the share, are fastened the double mould-boards (*aurēs*), which turned up a ridge on either side of the line drawn by the passage of the plough. Behind the mould-boards comes the curving pole (*tēmo*), supported by a truss, and at the extreme end the single guiding handle (*stīva*).


The Roman *irpex* was a plank set with teeth and drawn by oxen over the ground. Its use was not that of our harrow (the work of which was usually done by hand), but to clear the ground of small roots; so, though this is not expressly stated, its teeth were probably set at an



angle. A species of brush-harrow called *crātēs* was, however, employed. The *tribulum* was a platform studded with nails, drawn over the grain upon the threshing-floor to open the ears. Unyoked cattle were sometimes driven about over the threshing-floor for the same purpose, and flails (*perticae*) also were used (these were merely long, pliable rods), especially when the grain had been reaped just below the ear, and was, therefore, almost free of straw.

The proper mode of preparing the threshing-floor is described by all the authorities, but nowhere more clearly than by Virgil in the first Georgic.

The rooms containing the oil and wine presses also opened on the central court-yard. To the harvest of two hundred and forty *iūgera* of olive-orchards, Cato assigns three mills, one worked by a donkey, one by hand, and one so-called Spanish mill; but his estimates are confessedly made with a wide margin for accidents. These mills, which all bore the same name (*molae*), as those used for grinding grain, were probably very like the latter in construction. The lower stone (*mēta*) was immovable; the upper (*catillus*) turned about it exactly as in the



Trapetum (Rich).

former case; and by this means the fleshy part of the berry was detached from the stone and bruised, while the latter was left intact. The *trapētum* was a more elaborate machine for

performing the same office, and to these two Columella gives the preference over all other mills. When cleared

of stones, the pulp was put under the press (*torcular*), which consisted merely of boards forced down by a press-beam (*prēlum*), working like a long-armed lever. In the time of Pliny, this was replaced by the much more compact and effective screw-press. The juice expressed by the *torcular* was guided by the slope of the floor into one or more earthen jars sunk below its level, and from these the permanent receptacles were filled. The construction and working of the wine-press was very similar, if indeed the same machine were not used for both fruits.

That the Romans had a great many species of grain appears from the long catalogue of names furnished by the writers on agriculture, but it is no longer easy to determine the exact nature of all these varieties. Both autumn and spring sowing were practised, as with us, though the former was preferred. About a bushel of wheat (*triticum*) was used to a *iūgerum*, and this amount of land required four days' ploughing with oxen, one of harrowing, two days for the first hoeing, one for the second, one for weeding, and one and a half for harvesting. In this estimate the sowing is plainly included under the head of ploughing. The ground was ploughed three times; the first broke up the earth, the second cross-ploughed it, the third traced the drills in which the seed was sown by hand and harrowed<sup>1</sup> in. The first hoeing (*sarritio*) banked up the earth about the young grain and cleared it of weeds; the weeding (*runcatio*) consisted in lopping with a sickle the tops of the weeds, their roots not being disturbed. The cultivation of all grains followed these general lines.

<sup>1</sup> The *occatio* or harrowing was performed either by the *crātēs* or by the *rāstrum*.

Pulse formed an essential article of food both for man and beast, and ranked next in importance to the grains. The *faba*, the most useful kind of pulse, was evidently some variety of bean. It was often sown without any intermediate ploughing on land from which grain had been harvested, the seed being dropped apparently into the furrow between the ridges of stubble, which were then turned over upon it by the plough. When the beans were three inches high, they were banked up with the hoe, or else the board plough already described was run through between the rows, and afterwards they were two or three times cleared of weeds by the hoe — and this was the general manner of cultivating the other varieties of pulse.

The value of turnips (*rāpa*) as food for cattle and sheep was perfectly understood, and they were extensively raised.

A few words may here be given to the subject of rotation of crops as it was practised by the Roman farmer. Some of the richer parts of Campania bore a crop of grain every year. The elder Pliny mentions one field in the fork between the roads which diverged from Capua to Cumæ and Puteoli, which regularly bore spelt (*fār*) for two years, then panic<sup>1</sup> (*pānicum*) for one, and so on in perpetual rotation; but this was a prodigy even in fertile Campania. A recurrent succession of barley (*hordeum*), millet (*mīlium*), and turnips was more common, though this demanded a rich soil, and it was customary to manure for the millet when its turn came round. Another expedient was alternating spelt and spring beans, manuring the latter. Less fertile land lay fallow every

<sup>1</sup> Panic, though exhausting, was a summer grain

third year, common soil on alternate years, this being the method recommended by Virgil; and certain crops, such as lupine (*lupinus*), were sown merely to be ploughed in as a fertilizer.

There was always a vegetable garden (*hortus olitōrius*) on the Roman farm, where were to be found a great variety of pot-herbs (*herbae pulmentāriæ*), lettuce (*lactūca*), and other salads, cabbages (*brassicæ*) of many kinds, leeks (*porrum*) and onions (*caepa*), carrots (*pastināca*) and turnips (*rāpa*), asparagus and artichokes (*cardus*), beans (*faba*) and peas (*pīsum*), cucumbers (*cucumis*) and melons (*mēlo*).

**Market-gardening** was a flourishing industry, and the raising of flowers, notably violets and roses, provided a town were within easy reach, was strongly recommended. But the olive and the grape were, after all, the two most characteristic Roman crops.

If ten per cent was a fair interest on money invested in a vineyard, as Columella asserts, it is curious that viticulture should have gone even temporarily out of fashion, as it seems to have done at one period in the early days of the Empire. Then, as now, the soil preferred for a vineyard was gravelly, and, in starting a fresh one, new ground was broken if possible, or, at all events, that which had never borne vines before. That the young plants should be of good stock, was, of course, the first necessity; then a thorough and repeated working of the soil was required, and a careful cutting back of the shoots and roots of the vines.

**Practically, there were but two ways of training vines,** — on trellises and on trees. In the former case, the main stock of the vine was trained up a pole to the height of

five or six feet, where it was allowed to branch, and here a cross-bar (*iūgum*) was fastened to the pole. Over this the branches were thrown, and carried back to the ground, where they rooted, and formed new stock to replenish the vineyard. Among trees to which the vine might be trained, the elm was preferred, and Virgil announces in the very opening of the *Georgics*, that an important part of his pleasing task will be to describe the art of “marrying the vine to the elm.”

Its leaves, which had to be plucked in order to give sunshine to the grapes, were an excellent food for cattle; it grew easily in most soils, and could be severely trimmed without diminishing its vitality. When a tree was intended as the support of a vine, its trunk was kept smooth for eight feet above the ground. Three equidistant branches were then left, and the same number was allowed to grow, at intervals of three feet, to the top of the tree, care being always taken that the members of the successive layers should not come directly above one another.

The vines were set at varying distances apart, according to the quality of the soil, the nature of the climate, and the mode in which they were to be trained. Columella says<sup>1</sup> that nobody can help getting a *culleus*<sup>2</sup> of wine from a *iūgerum*; but in all cases the soil is required to be incessantly worked. From spring to winter the ground was spaded over at least once a month. One man was supposed equal to the care of seven *iūgera*, and the fettered slaves appear to have been often appointed to this task. At the vintage, of course, extra labor was called in. On the nineteenth of August, the *Vinālia*

<sup>1</sup> De Re Rus. iii. 3.

<sup>2</sup> See Table.

*Rūstica*, sacrifices were offered to Jupiter, and the *flāmen diālis*, with much solemnity, broke a bunch of grapes from a vine-branch, and declared the vintage begun. Practically, however, grapes appear to have been gathered as they ripened, without much regard to this festival; only no new wine might be taken into the city until after it had occurred.

Long before the grapes were gathered, the vintner must see that all the utensils were ready for the wine-making, cleanly washed and rinsed in salted, or, better still, in sea-water, while vessels of clay were, if necessary, daubed inside with pitch to render them impervious.

The grapes were first trodden by the feet, then twice pressed, and the final refuse, mixed with water, formed the beverage called *lora*, which was the winter drink of the slaves. If the must were to be kept sweet, jars were filled with it, tightly covered, then sunk in sand or water for a month or six weeks, after which it was warranted to remain unaltered in taste for a year at least. Much of the must was boiled down into a jelly used for flavoring and preserving poor wines. This boiling down was a most delicate operation. It was done by night in a great leaden vessel (brass and copper were thought to impart an unpleasant flavor), over a fire, slow at first, and then brisker, the liquid being constantly stirred to prevent burning, and carefully skimmed of all impurities. The resultant jelly received different names, *dēfrutum*, *sapa*,<sup>1</sup> etc., according to the proportion of the original must which had been boiled away.

The rest of the must was taken to the wine-cellar (*cella vināria*) and put into the *dōlia*, huge earthen jars

<sup>1</sup> Whence the Italian *sapa* and French *sabe*.




holding rather more than a hundred gallons. Here the must was allowed to ferment, and here it was doctored with the various ingredients used to flavor and preserve it. The chief of these were boiled-down must (*dēfrutum*, etc.), sea-water which had been bottled, and kept a number of years, lime, turpentine, and pitch. Aromatic herbs and spices were also sometimes employed.



Dolium (Rich).

The *cella vināria* was constructed with a dry earthen bed, and if the wine were weak, the *dōlia* were sunk deeply in the earth. Fermentation required about nine days, after which the *dōlia* were tightly covered and only looked at from time to time.

The common wines were drunk directly from the *dōlia*, and from these were also filled the ox- and goat-skins in which wine was transported to a distance. Finer wines were always bottled off in *amphorae*, with all sorts of superstitious precautions, and stored away, not as with us in the cellar, but in a dry room at the top of the house (*apothēca*).



Amphorae (Marquard).

Thus Horace in his gay ode to the Amphora,<sup>1</sup> calls upon

<sup>1</sup> Hor. Od. iii. 21.



the jar of choice Massic wine to *come down* from its place of rest and help him celebrate the festival of his friend Messala Corvinus. Sweet wines were also made from sun-dried grapes, and innumerable liqueurs of which wine formed the basis.

**Although the season of olive-gathering** came earlier in Roman days than now in Italy, oil was not made till the vintage was well over. The best way of all was to pick the olive by hand, but where this was impracticable they were gently beaten from the tree with osier-rods.

From the pulp of the olive were and are expressed two liquids, — oil proper, and that thin, watery fluid, dark and bitter, which was called *amurca* by the Romans, and used by them as manure. This came away from the olive with much less pressure than the oil, or else it oozed from the berry after it was gathered; and many farmers left the olives spread out upon a dry, sloping floor, for two or three days before they were pressed, on purpose to allow the *amurca* to run away and a slight fermentation to take place. Others considered this practice most injurious to the fruit. In any case the berries were carefully picked over, and each day's harvest not only cleaned by itself, but kept distinct during all the processes of oil-making. In general, the gentler the pressure to which the olive-pulp was subjected, the better the resultant oil, which was roughly divided into three grades. It was cleared of *amurca* by being poured from one pan to another, often to the number of thirty, after having been allowed to stand for a while and settle in each. In very cold weather, when the oil and *amurca* could not be separated in this way, a little salt or nitre was mixed with the liquid. When thoroughly clarified, the oil was

put into *dōlia* and tightly corked. Throughout its making the oil must have been carefully protected from the touch of smoke, which was thought as deleterious in this case as desirable for new-made wine.

Olives were also pickled and preserved in a variety of ways; and since the olive-tree commonly bore only every other year, it was customary to have two orchards furnishing alternate harvests. Once fairly started, an olive orchard demanded comparatively little labor; the ground about the trees was annually dug or ploughed, the suckers trimmed, and the roots cut back; but the trees were manured only every third year, and their branches trimmed once in eight or even more; on the year they did not bear, some other crop was raised between the trees.

Grafting was a common practice with all fruit-trees, the Roman method being substantially the same as our own.

In considering the Roman farmer's year as a whole, we find that he computed rainy days and festivals at forty-five, and reckoned on thirty days after the sowing when there was no field labor to be done. But on these thirty days, and on the stormy ones, there were ropes to make, baskets to weave, and other home-made utensils to prepare; while all the other implements of the husbandman — his "mute servants," as Varro<sup>1</sup> calls them — had to be repaired and thoroughly cleaned. Even on feast-days certain kinds of work were allowed, such as the clearing of drains and the mending of highways, so that only the December Saturnalia seem to have afforded a complete holiday to the slaves.

<sup>1</sup> Varr. Re Rus. i. 17.

On New Year's day, a little work of every kind was done for good luck; but then followed a time of comparative relaxation. In the latter half of January, the ground was cleared of brambles, and the trimming of the vineyards completed; while the autumn-sown grain and the beans, if they were sufficiently grown, were hoed for the first time. Early trees were now grafted, and the stock was planted. Vineyards were also cultivated, and young orchards set out, grass sown and ground broken, fields manured and osier-beds renewed. Vine-sets were also transplanted, if needful, and the late fruit-trees grafted.

In March, the vegetable garden was prepared, the autumn grains received their second hoeing, and the spring grains were sown. In April, came weeding, sheep-washing, the setting out of new vineyards, the trimming of old vines, and the olive-grafting.

May brought the earliest mowing, and in this month the earth was first spaded up about the olive-trees, and the vineyards dug over, this latter process being repeated each month until cold weather. The olives were also trimmed, the vine-shoots nipped; in warmer latitudes the sheep were shorn, and the lupins, which had been sown as fertilizer, were ploughed in. In June the first ploughing was finished and the second done, the threshing-floor was made ready, vetches mown, beans picked, and honey taken from the hives.

Grain-harvest took place in July, and the cutting of the straw and gathering of leaves for the winter fodder of cattle. In August, figs and grapes were dried for winter use, and brakes cut for litter.

September was, *par excellence*, the month of the vint-

age, and then, too, turnips were planted, and the later grains harvested. In October, winter grains were sown and harrowed in, trees trimmed, and the olive-picking begun.

November was devoted to a general cleaning-up of autumn work. The making of oil was finished in December, and the vines trained, and we may close the brief *résumé* of the work of the Roman agricultural year by a few general precepts from the Natural History of the elder Pliny<sup>1</sup>: "He is no farmer who buys what his estate can supply. He is a bad head of a household who does by day what can be done by night, — except in case of foul weather; he is a worse who does on working-days what is permitted on holidays; the worst of all is he who on a pleasant day chooses to work within doors rather than in the field."

<sup>1</sup> Plin. Nat. Hist. xviii. 6.

## CHAPTER VI.

## TRAVEL, TRANSPORTATION, AMUSEMENTS.

WHEN Rome was at the summit of her power, the entire extent of the Empire was provided with a system of public highways which rendered communication between the different parts of Europe easy and comparatively rapid. Three principal post-roads diverged from Rome, starting from three separate gates. From the Porta Capena,<sup>1</sup> at the southeastern angle of the city wall, the Via Appia ran over the Alban hills, and across the Pontine Marshes to Capua, where it divided. The right-hand branch led to Rhegium (Reggio), and thence by ferry to Messina and the principal cities of Sicily, one of which, Lilybæum (Capo di Boco), was the regular port of winter departure for Carthage and Africa. In summer the direct sea-passage from Ostia was usually preferred. From Carthage, roads of Roman construction led westward and communicated with Spain, and eastward to Asia, and also penetrated for some distance into the interior.

The left-hand road from Capua went to Brundisium (Brindisi). From this point, a twenty-four hours' voyage brought the traveller to Dyrrachium (Durazzo in European

<sup>1</sup> After the building of the Aurelian wall, from the Porta Appia, fifteen hundred yards further out.

Turkey), whence he might follow the Egnatian Way through Illyria, Macedonia, and Thrace to Constantinople; while branch roads led to other important points, and especially to Athens, and to Antioch, which was the centre of Eastern trade. Brundisium was also connected by a coast road with Ariminum (Rimini), the terminus of the Flaminian Way.

This very important road left Rome by the Porta Flaminia, on or near the site of the present Porta del Popolo, crossed the Tiber at the Mulvian bridge, where is now the Ponte Molle, and ran northward through mid-Italy, by way of Narnia and Spoletum (Narni and Spoleto) to Rimini, as aforesaid. From this point another coast road ran northward to Aquileia, — the starting-point for the Danubian provinces; while the Via Æmilia turned westerly and led by way of Bologna and Modena (Bononia and Mutina) to Milan (Mediolanum). From Modena, another great road led northward to Verona and the Brenner Pass.

The main highway to Western Europe was unquestionably the Aurelian, which struck the Mediterranean at Centum Cellæ (Civita Vecchia), and followed the coast from there as far as Arelas (Arles), in the Provincia, which was a seaport in Roman times, and from which point, Spain, France, and Britain were all easily reached. There was also certainly a way from Milan into Gaul by the passes of the Alps, though its exact course can no longer be determined. Traces of Roman work have, in fact, been found on nearly every Alpine pass now in use, and the "Itineraries" plainly mention those of Mont Genève, the Great and the Little St. Bernard, and the Splügen. There was another great

system of highways which connected Germany, Northern France, and England.

The model for all these mighty roads was the oldest and most frequented of them all, the *Via Appia*. Originally built by Appius Claudius in 312 B.C., it was restored and virtually reconstructed by the emperors Nerva and Trajan; and it was their road which, in the sixth century A.D., excited the wonder and admiration of Procopius, who found it broad enough for two teams to pass abreast, and paved with large blocks of foreign stone, so accurately fitted that no joining was visible. It is hardly probable that all the highroads we have enumerated were as magnificently constructed as the Appian Way, yet the time made by the regular post does not seem greatly to have varied on the different routes, and was everywhere much the same as that of the modern *diligence*.

The speed of government couriers was reckoned, for long distances, at something over one hundred English miles a day.<sup>1</sup> Private travelling, by hired conveyance, was necessarily slower. Cæsar, indeed, Plutarch tells us, accomplished the journey from Rome to the Rhone (796 Roman miles) within eight days, but then Cæsar's journeys were considered miracles of celerity. The private travellers of later times could sometimes make use of the government post, but only by special imperial permission.

Private letters were usually conveyed by foot-runners, or *tabellariî*, who made about twenty-five Roman miles a day, covering, for example, the 124 miles from Rome to Capua in about five days.

<sup>1</sup> The journey from Antioch to Constantinople, for example, 747 Roman miles, occupied not quite six days.



**Mānsiōnēs**, or night quarters, for the bearers of dispatches, were to be found at similar intervals, that is, about twenty-five Roman miles apart, and they must, in most instances, have been quite regularly distributed, since we find their number used as a measure of distance. Halting-places of a more sumptuous nature were provided for the Emperor and his especial deputies.

The support of the roads, as well as of the post-system of earlier times, fell entirely upon the districts through which the roads passed; and though some portion of this expense was later transferred to the imperial treasury, it always remained a heavy charge upon the provinces.

No public provision was made for private travellers, their needs being met by individual enterprise. There were men in most Italian cities who let out *raedae*, which were rather roomy four-wheeled carriages, and *cisia*, a species of light two-wheeled gig, as well as the horses or mules to draw them.



Cisium (Rich).

The offices of these *cisiārīi* or *iūmentārīi*, were at the city-gates,—for driving within the walls was almost unknown,—and here the bargain was made either for changing carriage and horses from stage to stage,

or for making the whole journey with the same team. Doubtless a man might also use his own conveyance, if he had one, with the horses or mules to be hired along the road.

In the latter days of the Republic, great pomp began

to be affected by wealthy travellers, and this increased to such a pitch that Nero's regular train consisted of a thousand wagons, while Poppæa took along with her five hundred she-asses for convenience of bathing in their milk, and tipped her horses' shoes with gold.

Seneca<sup>1</sup> observes satirically that "everybody travels nowadays with a troop of Numidian cavalry in front, and a band of scouts sent on ahead. . . . They all have mules, loaded with vessels of glass and murrha, and sculptured by the hand of famous craftsmen, for it would be beneath a man's dignity to load his packs with articles which would bear knocking about." And he also tells us, with true Stoic vanity, that he once made a two days' journey with a friend, attended by so few servants that a single vehicle sufficed for them all.

**The traveller of consequence avoided, if possible, passing a single night in any inn.** On the incessantly frequented route from Rome to Naples, he was almost sure either to have a villa of his own, or a friend whose hospitality he might demand. Failing these, he would take tents along and camp out, if the season were sufficiently mild, and doubtless it was the absence of distinguished patronage which made the inn of those days both so comfortless and so cheap. It is certain, however, that places of public entertainment, such as they were (*dēversōria*, *tabernae*, *meritōria*), existed all along the most frequented roads of the Empire, and that they were, in some cases, aided from the treasury. Neighboring proprietors often built them on speculation, letting them to a landlord, or managing them through their own slaves. At certain

<sup>1</sup> See Ep. cxxiii. 6.

places there would be a choice of inns, and Horace remarks<sup>1</sup> on the rival establishments of Forum Appii. *Popinae*, or restaurants, both *popinae sellariolae* where a regular table was laid, and the humbler kind where a lunch was taken standing, are mentioned so often as to lead us to infer, that the fashion of renting furnished rooms (*meritoriae*) and going out for one's meals was as common in ancient Rome as in Latin countries now.

In the rural inns it was always customary to pay a lump sum for board and lodging, and, indeed, one hardly sees how items could have been specified, when the total bill amounted to a half as, which Polybius says<sup>2</sup> was the regular charge in his days for one night's entertainment in the inns of Cisalpine Gaul. Among the discoveries at Pompeii is that of a tavern-sign on which is depicted the hostess reckoning the dues of a departing guest, of whom she demands for bread and wine one as, for other food, two asses, and for mule's provender the same.

**Tavern-signs** appear to have been regularly used, and birds and animals were favorite devices, from which, as now, the tavern took its name,—at the sign of the Stork, the Elephant, the great Eagle, the Camel, the Raven. Inscriptions were often painted on these signs, urging the claims of the house upon the traveller, and host or hostess would stand upon the threshold to solicit the patronage of the passer-by. The proverbial reputation of inn-keepers was very bad. They were supposed, as a matter of course, to water their wine, and steal the fodder of the animals they stabled; and an impression prevailed, exaggerated, one may hope, that they were ready, not merely to murder such guests as were sup-

<sup>1</sup> Hor. Sat. i. 5. 4.

<sup>2</sup> Polyb. ii. 157.

posed to have valuables about them, but to eat them as well. Galen, who repeats the charge, appends by way of ghastly commentary, and, as it would seem, from experience, that human flesh tastes much like that of swine. Even St. Augustine<sup>1</sup> confesses to having heard tales, which, however, he declines implicitly to believe, of Italian hostesses who put something into their cheeses, which turned those who partook of these dainties into beasts of burden, whom they then compelled to perform certain tasks, restoring them to their human semblance after these were completed.

**The customs-dues** appear to have been as much dreaded as they are by the returning European traveller of our own day, and there was a good deal of evasion on the one side, and of rudeness on the other. Soldiers' luggage was, however, free of duty, and a man's effects might be exempted by especial favor of the Emperor, as were those of the sophist Polemo of Smyrna, by Trajan.

**Highway robbers** abounded in the outlying provinces of the Empire, in all mountainous districts, and especially in the tract of forest which divided the Pontine marshes from the sea. Military expeditions were frequently sent against them, but without much permanent effect. When Septimius Severus disbanded the Prætorian guard, a good many of its members, and of the class from which it had been recruited, "took to the road," as the English phrase used to be; and toward the close of that Emperor's reign (that is to say, in the middle years of the third century A.D.), there was a famous bandit, bearing the obviously fictitious name of Felix Bulla, and commanding a band of six hundred men, whose history is an

<sup>1</sup> Aug. Civ. Dei xviii. 18.

opera ready made. His principal headquarters were in the neighborhood of Brindisi, where all tourists of apparent affluence, arriving either from the West or the East, were ordered to stand and deliver. His force was admirably organized, he was both bold and wary, and long avoided capture, but was at length betrayed into the hands of the Prefect Papinianus. "How came you to be a robber?" was the rather futile preliminary inquiry of his judge, to which the captive replied, "How came you to be a prefect?"<sup>1</sup> Felix Bulla was thrown to the beasts in the amphitheatre, but his race survived. Those who went southward from Rome by day, during the first century of our era, were, in general, safe enough, owing to the very press of travel upon the road. There was a constant succession of those pompous caravans described by Seneca, whose owners aped imperial luxury. The expense thus incurred was often literally ruinous, and some of those, who had thus flaunted upon the road, ended their days as gladiators, a profession which Nero had made rather fashionable. For the time being, however, the carriage horses of the ambitious tourist were well matched and well bred, and their leathern shoes were furnished with silver tips. Otherwise, the traveller made use of fast mules, which were no less costly. These animals had often rich purple housings, heavily embroidered, while their harnesses were studded with gold. The wagons were sumptuously decorated with gold and silver plates, on which the value of an entire estate might easily be spent, while their cushions and curtains were of silk or some equally expensive stuff.

<sup>1</sup> Dio Cass. lxxvi.

One of the vehicles most commonly used was the *carpentum*. It had two wheels and an arched awning, and was, in fact, only a luxurious development of the common farm-cart, which bore the same name, — the cover having been added for protection against rain and sun. This was the kind of carriage affected by those great ladies in



*Carpentum (Rich).*

whose favor was first relaxed that prohibition of the use of wheeled vehicles inside the walls of Rome, which had remained in force throughout the republican period. When so occupied, the *carpentum*, and a variety of the same called a *pilentum*, were always drawn by mules. They were so constructed as to hold two persons beside the driver. In the four-wheeled *raeda*, or *cārrūca*, the traveller had appliances for making himself most comfortable. Propped upon soft cushions, he whiled away the time with reading, writing, dice-throwing and other amusements. Martial advises the man who sets out on a long journey, to make Cicero his travelling companion, and the elder Pliny used to have both an amanuensis and a writing-table in his coach.

Smaller than the *carpentum*, but covered like it, and driven by the traveller himself, was the *covīnus*. There were also the open two-wheeled *essedum* and *cisium*, each of which had a single seat, accommodating the driver and one other person. The *cisium* seems, however, to have been lighter built, for the *essedum* was always drawn by a pair of animals, while the *cisium* had shafts, to one of



which an extra horse was often attached, or, if great speed were desired, three animals would be harnessed abreast, as in the Russian *troika*. The outside horses were called *fūnālēs*, or *fūnārīi*, from the rope with which they were attached to the *cisium*, much in the same manner as a third horse is attached to a street-car among ourselves. Five miles an hour was considered

great speed even for a *cisium*.

**Government couriers** usually rode one horse and led another. The Romans, until the fourth century, seem never to have used a saddle (*sella equestris*<sup>1</sup>); they rode either barebacked, or with a pad or cushion called the *ephippium*, similar to that always used by women, in which case, too, they seem to have ridden side-wise in feminine fashion. With or without the *ephippium*, the *strāgulum* (housing or caparison) was always



used. It was often made of the skin of a beast with the

<sup>1</sup> Several kinds of pack-saddles, however, existed long before this date.



fur on, and sometimes of leather, which, for use in the army was covered with plates of metal, and served as a protection for the horse — Virgil<sup>1</sup> gives such a caparison, “covered with brazen scales like feathers,” to the horse of Chlorus, the priest of Cybele, in the last battle for Latium. Housings of brightly colored woollen cloth were used for mere ornament, and a leathern band, adorned with plates of metal, often hung down over the breast. The general plan of the head-stall (*capistrum*) was very like ours; but whether for riding or driving, blinders and curb-bits were unknown. There was a special sort of invalid carriage in use at Rome from very early times, called *arcera*, from its resemblance to a large chest. The occupant lay within, upon cushions, while the driver was perched upon a little seat outside; but after the introduction of litters, the *arcera* was almost entirely superseded.

The *lectica*, or litter, used at first merely for the transport of the sick or dead, became later the favorite travelling carriage for women.

Its use by a man was long considered a mark of effeminacy, but in imperial times they became general. The wealth of the possessor of a *lectica* was evinced, not only by the richness of its ornamentation, but by the number of bearers, two,



*Lectica* (Rich).

four, six, or eight. We do not know just how they carried their burden, only that, when set down, it rested

<sup>1</sup> Virg. *Æn.* xi. 770-771.

on four wooden legs. It also had a roof, supported at the four corners, and there were curtains around the sides, which could be drawn at pleasure; or else the sides were shut in with windows made from plates of alabaster, or other translucent stone, such as may still be seen in some old Italian churches. The occupant either reclined upon a heap of cushions, or the *lectica* was fitted with a feather bed. The *basterna* was a litter, borne by two mules, one before and one behind. All these conveyances were doubtless to be seen any fine day on the Via Appia, as well as trains of sumpter-mules (*dossuārii*, *clitellārii*, *sarcinālēs*, etc.), and heavy carts bringing merchandise to the markets of Rome.

Except during the winter months, when the great majority of vessels was laid up in harbor, the Roman market was largely supplied by means of **the boat-service on the Tiber**, from the harbors of Ostia and Portus Trajani. A winter voyage is usually mentioned as a thing of horror, but in the pleasant months of the year it seems to have been a mode of travelling much favored by the ancients, and more expeditious than journeying by land. Although merchant vessels proper (*nāvēs onerārii*), such as those which brought the grain supply from Egypt and Sicily, were propelled by sails alone, it was in rowing that the Romans, like the Greeks, chiefly excelled. How they managed their many banks of oars, no modern is able perfectly to understand, and ships with ten banks or more, must certainly have been mere curiosities. There is even mention of one vessel with forty banks, but three to five were the usual number, and the Greek trireme could be depended upon to make eight miles an hour. The voyage from Brundisium to Dyrra-

chium (Brindisi to Durazzo), with good wind and weather, might be accomplished in twenty-four hours, but what appliances the luxurious Roman had for making himself comfortable on shipboard, even during this brief transit, we do not know. Cabins there were, in the hold of the vessel, and a tent-like contrivance was sometimes erected on deck, which would, doubtless, afford a pleasant and sufficient shelter on those starlit summer nights which were chosen by preference for the crossing to Illyria and other short trips. On the coasting vessels, both sails and oars were used, and they could make a speed of six to eight nautical miles an hour.

The Romans were, upon the whole, great travellers, and their customary journeys may be classed under the three heads of business, instruction, and pleasure. Seldom, if ever, has the world seen a more thoroughly organized and extensive commercial system, than that which had its focus in Rome, in the first centuries of our era. Never, of a certainty, since that time, has the same current coin been used over so vast a stretch of territory. Local coinage of silver and copper, for local purposes, there doubtless was, in many of the provinces; but, except in Egypt, where the Greek *drachma* always held its own, the Roman *dēnārius* became the monetary unit throughout the Empire. It seems, also, to have passed current among the neighboring independent nations, as a Bank of England note will do to-day upon the Continent of Europe. Tacitus<sup>1</sup> remarks, however, that the Germans always gave the preference to those silver coins with the stamp of the *āiga*, which had prevailed before Nero's day, and to which they were accustomed, while

<sup>1</sup> Tac. Ger. 5.

they looked with suspicion on later coinages. As for gold, all articles of merchandise were so cheap in Germany, that that metal was seldom required.

Like the merchant of the Middle Ages, his Roman predecessor seems to have travelled in person to the markets where he desired to buy or sell. Horace makes many allusions to the trader who "tempts the wintry sea, moving continually to and fro between the equator and the pole"; and Manilius describes the same adventurer as buying up the produce of the world, carrying his own wares into unknown lands, and ever acquiring fresh treasures under novel suns. These apparently poetic statements are corroborated by the monumental inscription of a merchant found at Hierapolis, which sets forth that he made seventy-two crossings between Malea on the Peloponnesos and Italy, while one C. Oc. Agathopus, declares upon his own gravestone at Pozzuoli, that, wearied out with travelling from East to West, he has here found repose at last. These merchant-voyages were not confined to the Mediterranean and Black Sea, but extended to the Atlantic, to the ports of Spain, France, England, and, very possibly, Ireland. The conquest of Egypt also opened the way to the East Indies. The regular route of the merchant led him first to Alexandria, starting whence in summer, he struck the mouth of the Nile, and sailed up that stream to Coptos,—a twelve days' voyage with favorable winds. At Coptos, his wares were transferred to the backs of camels, and the caravan set out for the shores of the Red Sea. Moving only by night, on account of the intense heat, and resting all day, it took nearly a fortnight to reach the coast, with which the Ptolomean canal formed another means of

communication. In Strabo's time, a fleet of a hundred and twenty vessels plied constantly between Myos-hormos, a Red Sea port, lying nearly opposite Mt. Sinai and the extremity of Arabia Petræa, and India; and each of these vessels, Pliny further informs us, had a company of archers on board, to protect the cargo against pirates. A voyage of thirty days brought the vessels either to Ocelis (Acila), in Arabia, at the lower extremity of the Red Sea, or to Cane, on the south coast of Arabia. It was forty days' journey hence, to the coast of Malabar, which, however, was in such bad repute for safety, that it was customary to prolong the voyage to a more southerly point. The whole expedition, from Alexandria to India and back, occupied from six to seven months, that is to say, from midsummer to some time in the following February. The incredible number of Roman coins found in India, testifies clearly enough to the extent of the Indo-Roman commerce. There is, indeed, some reason to suppose that a certain *dēnārius*, bearing the image of Augustus, with his adopted sons, Lucius and Gaius, was struck off for this trade only.

**The importations** from the East were much the same in Roman times as now, — silk, spices, pearls, ivory, and gold. The article of commerce most sought in the markets of Northern Europe was amber (*ēlectrum* or *sūcinum*), for which there was a great demand among the Romans, and, in quest of which the merchants often went far beyond the boundary of the Roman Empire. Tacitus tells<sup>1</sup> of a colony of Roman merchants, which the army ran across in Bohemia, who confessed that they had come there first in hopes of gain, and then

<sup>1</sup> Tac. Ann. ii. 62.

stayed on, till the new ties formed in this barbarous land had grown stronger than the old. There was also an excellent opening for trade in Gaul, whose inhabitants were always ready to give a slave for a cask of wine.

Wherever a permanent camp of Roman soldiers was established, the Roman merchant speedily found his way, and it would be hard to say which formed the more effective missionary of Roman civilization. Foreign merchants also visited Italy in large numbers, especially those of the Orient, which last came, in the process of time, so to throng all ports of the Empire, that in the fifth century Syrian and merchant appear to have become synonymous terms. "Here," writes<sup>1</sup> the Bishop Sidonius Apollinaris from Ravenna, in his whimsical description of that venerable city as a place where everything is topsy-turvy, "here priests let out money at usury, and Syrians sing psalms."

After Rome, the most important commercial centres were Corinth, Alexandria, and Arles, and certain places appear also then, as now, to have had a monopoly of the trade in certain articles. Thus Alexandria was said to supply the whole world with glass and paper, and Spain sent shiploads of quince marmalade in all directions. The Romans imported their beloved fish sauces largely from Antibes, and preferred the fine linen of Berytus (Beirut) to that of any other make.

Great stress was laid upon travel as putting a finishing touch to the education of a distinguished youth, whose mind was supposed to be expanded by the mere sight of novel scenes. Rich young Romans were sent to study (theoretically) for a year or more away from home,

<sup>1</sup> Sid. Ap. Ep. i. 1.



either in some Italian city or preferably in Greece. Often they followed from place to place some philosopher whose tenets they had embraced; for the rhetoricians and sophists were perpetually on the move, and their nomad life was adopted by other classes of people. Not only quack-doctors, but physicians in good and regular standing, travelled about the world, and took pride in the breadth of their experience. So also did portrait-painters and skilled artisans of all kinds, and unquestionably there were numbers of strolling troupes of actors, musicians, and athletes.

A sea-voyage and change of air were favorite prescriptions with the physicians of those days, and recommended for almost all ailments, — pulmonary weakness, habitual pain in the head, low spirits, and paralysis. Egypt was one of the favorite health resorts; a residence among pine-woods was often recommended; milk cures were to be found at many seaside resorts, such as Stabiæ (Castellamare), whilst almost all the medicated springs we know were frequented in Roman times.

There were also many religious pilgrimages to the temples of distinguished divinities, or to oracles of old and high repute; while on occasions like that of the Olympic games in Greece, or any particularly gorgeous gladiatorial show at Rome, the influx of pilgrims from abroad was often tremendous.

**The Roman also travelled as a mere tourist,** most of all to Greece, whose beautiful monuments every self-respecting citizen of the later Republic felt that he ought once, at least, to have seen. There could hardly be a Grecian town so insignificant as not to boast some temple which, over and above its religious character, partook of



that of a museum, with glorious works of art dating from the greatest period, and relics of demi-gods and heroes. Though somewhat shamefaced about accepting them implicitly, the Roman traveller was always deeply interested in objects which claimed connection with that great epic war under the walls of Troy, which had led to the building of Rome. Enthusiasts in this line even went to Asia Minor on an express hunt for Trojan relics, while Egypt, after its conquest, attracted larger and larger numbers of the curious year by year. The traveller of classic times had few guide-books, but he could hardly reach a city where he would not find a living guide prepared to take him about, and show him all that was worth seeing. These *valets-de-place*, though not yet called by the name of the most versatile of Romans, were often antiquarians of education and position.

But while the Roman of the Augustan Age had often a highly cultivated taste in the matter of art, his enjoyment of the beauties of nature was much more limited. Those grander aspects and phenomena of the outer world, which are so thrilling to the modern mind, were simply uncomfortable and repugnant to him; and this is probably why, despite his love of change and restless desire to enlarge his borders, the Roman was never a very ardent explorer. Certain of the gentler aspects and humbler charms of nature—cool springs with mossy banks, broad, green meadows and quiet sheets of water, shady groves and fair garden-beds—he did love intensely, as countless passages in the Latin poets show; and such he would have about his country-house, or if, like Atticus, he were rich enough, even in the city. But his villa was his first extravagance, and always his peculiar

pet and pride. "In all the length and breadth of this Empire," says Seneca,<sup>1</sup> "there is no lake whose borders are not studded with the roofs of Roman nobles, no river-bank where they have not built." All along the Mediterranean, far south from Ostia, these villas lined the coast, crowding close upon one another at favorite sites, like Baiaë. The inland estates, like those of the younger Pliny, near the sources of the Tiber in Umbria (the modern Città di Castello), were of much greater extent; but even so, they were almost continuous.

It is difficult to say how many distinct properties a Roman of rank might not possess in late republican or early imperial times. If Cicero and Pliny, who have told us so much about their various installations, are to be taken as representative cases, one would say that four or five huge country-seats, and as many lesser villas, would be a moderate allowance, while the dates of the letters of these two show how incessantly they moved from one place to another. Sometimes, no doubt, they did so at the bidding of their affairs. Often they were impelled by mere restlessness and love of change.

"Hence are vague journeyings undertaken," says Seneca<sup>2</sup> in his discourse on Tranquillity of Spirit, "and divers coasts are visited, but everywhere, whether on land or on sea, we discover that levity of mind which is always disgusted with the present. Now we seek Campania, and anon, growing disgusted with its delicacies, we make for the wilderness and explore the forests of Bruttium and Lucania. But the craving for something pleasant revives in the desert, and our dainty eyes must needs have some relief from the tedious squalor of those

<sup>1</sup> Sen. Ep. lxxxix. 21.

<sup>2</sup> Sen. De Tran. An. ii.

rude spots. Tarentum is the place! — we praise its harbor, its exquisite winter climate, and its fine old mansions. Finally we bend our steps toward the city of cities. Too long have our ears missed the din of the streets, the plaudits of the theatre. We are ready even for a taste of human blood. Thus journey follows journey, and scene succeeds to scene, and so it is, as the poet Lucretius says, that ‘every man would from himself escape.’”

The restless being described in this passage was, of course, a spoiled child of fortune, but never at any period of his history was the Roman very ingenious in devising for himself home amusements and simple recreations. It was not quite natural for him to play. The mimes and songs and dances of primitive times had almost all a religious significance. They appeal to the gods, and were laudatory or propitiatory in their character. There are, indeed, allusions in Virgil’s roseate picture of the good old times to something like the rustic sports of “Merrie England,” — “leaping upon greased and inflated hides, in the fair meadows,” and the like;<sup>1</sup> and Cicero and Suetonius both speak of casting lots by means of the game called “*micare digitis*,” which consisted of throwing out under cover a certain number of fingers for your adversary to guess, and which was much the same as the *mora* of modern Italy. But even these elementary amusements, though ancient, were, perhaps, not indigenous, while the dramatic representations and games of the circus, which came to exercise so enthralling a fascination over the town-bred Roman of later times, were certainly an importation from Greece. These monster shows however, of which the great majority were organ-

<sup>1</sup> Virg. Geor. ii. 382.

ized and exhibited for political purposes, belong to the public rather than the private life of the Roman.

It remains to say a few words concerning the games of children and youths. The former, like the rising generation always and everywhere, had their dolls and their hobby-horses, their toy houses and carts. They skipped stones, they spun tops (*turbinēs*), they walked upon stilts (*grāllae*). They had also active games of emulation or skill, in which the best fellow won, and Horace quotes in his first epistle, the boys who say, "If you beat, you shall be king" (*rēx eris, sī rēctē faciēs*), while the rather vulgar catchword of a boys' foot race, "*occupet extrēmum scabiēs*" (a murrain seize the hindmost), is applied by the same humorous author in his *Ars Poetica* to the freaks of a too froward literary ambition.

Nuts were such very favorite playthings with a Roman boy, that the expression *nucēs relinquere* came to be synonymous with the putting away of childish things, as we have already seen in the case of the young bridegroom, of whom largess of nuts was demanded by the *gamins* who followed his bridal procession. Many different games were played with these cheap and convenient counters, such as the *lūdus castellōrum*, which required four nuts, of which three had to be so arranged that the fourth could be balanced upon, without displacing them; which done, all the four accrued to the deft player; and the game of *pār impār*, which explains itself, being precisely the universal "odd or even?"

The youth who had outgrown nuts or marbles played ball, either by himself, with one, two, or three balls, or with one or more associates, who had to play by turn (*datātīm lūdere*), and must be equally expert in throwing

(*dare* or *mittere*), catching (*excipere*), and returning (*remittere* or *repercutere*). The *trigōn* was a triangular game of ball sufficiently dignified to be played upon the Campus Martius by grown men, and difficult enough to require much practice. The chief peculiarity of the *trigōn* was that the balls were not delivered in regular order, but flung to any player at the caprice of the server, and each of the three players had to catch and throw simultaneously. The *sphaeromachia* was a still more elaborate game of ball, in which the players took sides, and their ground was marked out somewhat as for lawn-tennis.

Children of a yet larger growth amused themselves with the innumerable games of hazard which depend upon the throwing of dice (*tesserae* or *tālī*). *Tesserae* were cubical, and marked exactly like the dice of to-day. They were shaken upon a flat surface from a cup or dice-box, which went by many names, — *turricula*, *fritillus*, *ōrca*. Three dice were usually thrown, and the high-

est throw was, of course, triple sixes. *Tālī* were originally made from the ankle-bones of animals, whence their name. They were numbered upon four sides only, being rounded on the other two.

Four was the number regu-



Fritillus (Rich).

larly thrown, and the highest cast, called *Venus*, was that in which the four different numbers, one, three, four, and six came uppermost (two and five were never marked upon *tālī*). There were also several games played with *calculī* (balls or pellets) upon a board (*tabula*), a favorite one being the so-called *lūdus latrun-*

*culārius*, which bore some faint resemblance to chess, and where victory seems to have consisted in capturing and disabling as many thieves (*latrōnēs*) as possible. But war was, after all, the Roman's favorite pastime, and no manner of contest upon a mimic field commanded his ardent interest.





# APPENDIX.

## I.

### ROMAN MEASURES OF LENGTH WITH ENGLISH EQUIVALENTS.

#### A. *Smaller Measures.*

Digitus . . . . .	=	.7281 in.
1½ Digiti = Uncia . . . . .	=	.9708 in.
4 Digiti or 3 Unciae = Palmus . . . . .	=	2.9124 in.
3 Palmi = Palmus Major (late) . . . . .	=	8.7372 in.
4 Palmi = Pes . . . . .	=	11.6496 in.
5 Palmi = Palmipes . . . . .	=	1 ft. 2.562 in.
6 Palmi = Cubitus . . . . .	=	1 ft. 5.4744 in.

#### B. *Larger Measures.*

Pes . . . . .	=	11.6496 in.
2½ Pedes = Gradus . . . . .	=	2 ft. 5.124 in.
2 Gradus = Passus . . . . .	=	4 ft. 10.248 in.
2 Passus = Decempeda or Pertica . . . . .	=	9 ft. 8.496 in.
12 Perticae = Actus <sup>1</sup> . . . . .	=	116 ft. 5.952 in.
1000 Passus = Mille Passuum . . . . .	=	4854 ft. = .9193 mile.

## II.

### ROMAN SQUARE MEASURE.

Pes Quadratus	=	.94245 sq. ft.
480 Ped. Quad. = Actus Simplex	=	1 sq. R. 180.127 sq. ft.
5 Act. Simp. = Uncia <sup>2</sup>	=	8 sq. R. 83.885 sq. ft.
6 Unciae = Actus Quadratus	=	1 rood 9 sq. R. 231.07 sq. ft.
2 Act. Quad. = Iugerum <sup>3</sup>	=	2 roods 19 sq. R. 189.89 sq. ft.

<sup>1</sup> The *Actus* was the regulation length of furrow in ploughing with oxen, and was to be drawn without breathing space.

<sup>2</sup> That is twelfth part of Iugerum.

<sup>3</sup> Or very nearly five-eighths of our acre.

## III.

## ROMAN LIQUID MEASURE.

	Ligula . . . . .	=	.024 pts.
4 Ligulae	= Cyathus (Uncia of Sextarius)	=	.096 pts.
3 Cyathi	= Quartarius ( $\frac{3}{12}$ " " )	=	.289 pts.
2 Quartarii	= Hemina ( $\frac{6}{12}$ " " )	=	.578 pts.
2 Heminae	= Sextarius . . . . .	=	1.155 pts.
6 Sextarii	= Congius . . . . .	= 3 qts.	.934 pts.
4 Congii	= Urna . . . . .	= 13 qts.	1.735 pts.
2 Urnae	= Amphora . . . . .	= 27 qts.	1.471 pts.
20 Amphorae	= Culeus . . . . .	= 138 gal. 2 qts.	1.53 pts.

## IV.

## ROMAN DRY MEASURE.

	Sextarius <sup>1</sup>	= . . . . .	.993 pts.
8 Sextarii	= Semimodius	= . . . . . 3 qts.	1.944 pts.
2 Semimodii	= Modius <sup>2</sup>	= . . . . . 7 qts.	1.888 pts.

## V.

## ROMAN WEIGHTS.

A. *Uncial Divisions of the As.*

		Grammes.	Oz.	Grains (Avoir.).
	Uncia <sup>3</sup> . . . . .	= 27.288	=	421.108
$1\frac{1}{2}$ Unciae	= Sescuncia . . . . .	= 40.932	= 1	194.163
$1\frac{1}{3}$ Sescuncia	= Sextans = 2 unciae	= 54.576	= 1	404.716
$1\frac{1}{2}$ Sextantes	= Quadrans = 3 unciae	= 81.864	= 2	388.324
$1\frac{1}{3}$ Quadrantes	= Triens = 4 unciae	= 109.152	= 3	371.932
$1\frac{1}{4}$ Trientes	= Quincunx = 5 unciae	= 136.44	= 4	355.54

<sup>1</sup> The Sextarius of dry and liquid measure was of the same capacity, and the same subdivisions were made use of.

<sup>2</sup> Or, for rough calculation, the Modius equals the peck, and the Sextarius the pint.

<sup>3</sup> The Uncia differs from the ounce avoirdupois (437.5 grains) by 16.392 grains.

			Grammes.	Oz.	Grains (Avoir.).
$1\frac{1}{5}$ Quincunces	= Semis	= 6 unciae	= 163.728	= 5	339.148
$1\frac{1}{6}$ Semes	= Septunx	= 7 unciae	= 191.016	= 6	322.756
$1\frac{1}{2}$ Septunces	= Bes	= 8 unciae	= 218.304	= 7	306.364
$1\frac{1}{8}$ Besses	= Dodrans	= 9 unciae	= 245.592	= 8	289.972
$1\frac{1}{9}$ Dodrantes	= Dextans	= 10 unciae	= 272.88	= 9	273.580
$1\frac{1}{10}$ Dextantes	= Deunx	= 11 unciae	= 300.16	= 10	257.188
$1\frac{1}{11}$ Deunces	= As (Libra)	= 12 unciae	= 327.45	= 11	240.796

*B. Divisions of the Uncia.*

			Grammes.		Grains. (Avoir.).
	Siliqua	=	.189	=	2.924
3 Siliquae	= Obolus	=	.568	=	8.773
2 Oboli	= Scrupulum	=	1.137	=	17.546
2 Scrupula	= Semisextula	=	2.274	=	35.092
3 Scrupula	= Drachma	=	3.411	=	52.638
4 Scrupula	= Sextula	=	4.548	=	70.185
6 Scrupula	= Sicilicus	=	6.822	=	105.277
8 Scrupula	= Duella	=	9.096	=	140.369
12 Scrupula	= Semuncia	=	13.644	=	210.554
2 Semunciae	= Uncia	=	27.288	=	421.108
12 Unciae	= As (Libra)	=	327.45	=	5053.296

## VI.

## ROMAN MONEY.

*A. B.C. 268-217.*

			Weight in Grains (Avoir.).		Value in Money.
	As (copper) <sup>1</sup>	=	1754.613	=	\$ .01968
$2\frac{1}{2}$ Asses	= Sestertius (silver)	=	17.546	=	\$ .0492
2 Sestertii	= Quinarius (silver)	=	35.092	=	\$ .0984
2 Quinarii	= Denarius (silver) <sup>2</sup>	=	70.184	=	\$ .1968

<sup>1</sup> In still earlier times the *As* of money, like the *As* of weight, contained 5053.296 grains. The relative value of silver and copper 250:1.

<sup>2</sup> Denarius =  $\frac{1}{72}$  Libra.

*B. Coinage of 217 B.C.*

			Weight in Grains (Avoir.).		Value.
		As (copper) <sup>1</sup>	= 419.986	=	\$.0105
4 Asses	=	Sestertius (silver)	= 15.0395	=	\$.042
4 Sestertii	=	Denarius (silver) <sup>2</sup>	= 60.158	=	\$.168

*C. Coinage of Augustus.*

			Weight in Grains (Avoir.).		Value.
		As (copper)	= 240.632 <sup>3</sup>	=	\$.01305
4 Asses	=	Sestertius <sup>4</sup> (alloy)	= 481.264	=	\$.0522
4 Sestertii	=	Denarius (silver)	= 60.112	=	\$.2088
25 Denarii	=	Aureus <sup>5</sup> (gold)	= 120.224	=	\$5.22

<sup>1</sup> Silver to copper, 112 : 1.

<sup>2</sup> Denarius =  $\frac{1}{8}$  Libra.

<sup>3</sup> It is not absolutely certain that the As in weight equalled four Denarii.

<sup>4</sup> Often coined as a piece of four Asses, as we speak of our dime as a ten-cent piece.

<sup>5</sup> The Aureus, though nominally weighing  $\frac{1}{8}$  Libra throughout imperial times, became more and more debased by alloy and in size, till in the time of Caracalla it was worth about \$4.40.

The relative value of the same weight of the different metals in the time of Augustus was, according to Mommsen : —

Copper to gold, 1 : 666 $\frac{2}{3}$ .

Alloy to gold, 1 : 333 $\frac{1}{3}$ .

Silver to gold, 1 : 12 $\frac{1}{2}$ .

Copper to silver, 1 : 53 $\frac{1}{3}$ .

Alloy to silver, 1 : 26 $\frac{2}{3}$ .

Copper to alloy, 1 : 2.

TABLE VII.

MONTHS OF THE JULIAN CALENDAR WITH ENGLISH EQUIVALENTS.

	Januarius. Sextilis. (Augustus.) December.	Februarius.	Martius. Maius. Iulius. October.	Aprilis. Iunius. September. November.
1	Kal. Ian.	Kal. Feb.	Kal. Mar.	Kal. Apr.
2	iv. Non. Ian.	iv. Non. Feb.	vi. Non. Mar.	iv. Non. Apr.
3	iii. " "	iii. " "	v. " "	iii. " "
4	Prid. " "	Prid. " "	iv. " "	Prid. " "
5	Non. Ian.	Non. Feb.	iii. " "	Non. Apr.
6	viii. Id. "	viii. Id. Feb.	Prid. " "	viii. Id. "
7	vii. " "	vii. " "	Non. Mar.	vii. " "
8	vi. " "	vi. " "	viii. Id. Mar.	vi. " "
9	v. " "	v. " "	vii. " "	v. " "
10	iv. " "	iv. " "	vi. " "	iv. " "
11	iii. " "	iii. " "	v. " "	iii. " "
12	Prid. " "	Prid. " "	iv. " "	Prid. " "
13	Id. Ian.	Id. Feb.	iii. " "	Id. Apr.
14	xix. Kal. Feb.	xvi. Kal. Mar.	Prid. " "	xviii. Kal. Mar.
15	xviii. " "	xv. " "	Id. Mar.	xvii. " "
16	xvii. " "	xiv. " "	xvii. Kal. Apr.	xvi. " "
17	xvi. " "	xiii. " "	xvi. " "	xv. " "
18	xv. " "	xii. " "	xv. " "	xiv. " "
19	xiv. " "	xi. " "	xiv. " "	xiii. " "
20	xiii. " "	x. " "	xiii. " "	xii. " "
21	xii. " "	ix. " "	xii. " "	xi. " "
22	xi. " "	viii. " "	xi. " "	x. " "
23	x. " "	vii. " "	x. " "	ix. " "
24	ix. " "	vi. " "	ix. " "	viii. " "
25	viii. " "	v. " "	viii. " "	vii. " "
26	vii. " "	iv. " "	vii. " "	vi. " "
27	vi. " "	iii. " "	vi. " "	v. " "
28	v. " "	Prid. " "	v. " "	iv. " "
29	iv. " "		iv. " "	iii. " "
30	iii. " "		iii. " "	Prid. " "
31	Prid. " "		Prid. " "	

To February was added, every fourth year, an extra day (*dies intercalaris*), which had its place after the vii. Kal. Mar., *i.e.* Feb. 23d.

TABLE VIII.  
THE ROMAN DAY.

	Summer Solstice.	Winter Solstice.
Sunrise . . . . .	4.27 A. M.	7.33 A. M.
1st hour ends . . . . .	5.42 $\frac{1}{2}$ "	8.17 $\frac{1}{2}$ "
2d " " . . . . .	6.58 "	9.2 "
3d " " . . . . .	8.13 $\frac{1}{2}$ "	9.46 $\frac{1}{2}$ "
4th " " . . . . .	9.29 "	10.31 "
5th " " . . . . .	10.44 $\frac{1}{2}$ "	11.15 $\frac{1}{2}$ "
6th " " . . . . .	12. M.	12. M.
7th " " . . . . .	1.15 $\frac{1}{2}$ P. M.	12.44 $\frac{1}{2}$ P. M.
8th " " . . . . .	2.31 "	1.29 "
9th " " . . . . .	3.46 $\frac{1}{2}$ "	2.13 $\frac{1}{2}$ "
10th " " . . . . .	5.2 "	2.58 "
11th " " . . . . .	6.17 $\frac{1}{2}$ "	3.42 $\frac{1}{2}$ "
12th " " . . . . .	7.33 "	4.27 "

Length of day hour at summer solstice, 75 $\frac{1}{2}$  minutes.

" " night " " " " 44 $\frac{1}{2}$  "

" " day " " winter " " 44 $\frac{1}{2}$  "

" " night " " " " 75 $\frac{1}{2}$  "

# INDEX.

---

- Abacus*, 53, 60, 61.  
 Agricultural implements, 120-124.  
 Agriculture, 105-134.  
*Alae*, 32.  
*Asses*, 113.  
*Atrium*, 28-32, 35, 46.  
  
 Baths, 48-50.  
 Beans, 126.  
 Bees, 119.  
*Bibliothēca*, 36.  
 Books, 36, 37.  
 Bread, 77-79.  
 Brides, 12, 13.  
*Bulla*, 57, 58, 64.  
 Burial places, private, 22; public, 25.  
  
*Candēlābra*, 41, 42.  
 Carriage-hire, 138.  
 Cattle, 110-112.  
*Cēna*, 47, 50, 51, 53-55, 75.  
 Children, 57-66.  
*Clāvus lātus*, 64, 96.  
 Clients, 74-76.  
 Cloaks, 98, 99, 108.  
 Clothing, 88-104, 108.  
*Columbāria*, 25.  
  
*Cōmissātiō*, 76.  
 Commemoration of the dead, 23, 26.  
 Commerce, centres of, 150.  
 Cremation, 22-24, 26.  
 Crops, rotation of, 15.  
*Cubicula*, 34, 36, 38.  
*Culīna*, 34.  
 Cultivation of the olive, 130-132; of the vine, 86, 127-129.  
 Custom-dues, 143.  
  
 Day, Roman, divisions of, 43-45, 164; how passed, 45, 46.  
 Divorce, 15-17.  
 Dress, 88-104, 108.  
 Dyes, 93, 94.  
  
 Education, 58, 59, 150, 151.  
  
 Fabrics, cotton, 90; linen, 89; mixed, 90, 103; silk, 90, 91; woollen, 88, 89.  
 Farms, 105-107.  
*Fauces*, 33.  
 Fish, 83-85, 119.  
 Flats, 38.  
 Flour, 78, 79.  
 Food, 77-88, 108.



- Fruit, 81, 82.  
 Fulling, 93.  
 Funerals, private, 24, 25 ; public, 17-24.  
 Furniture, 39-43, 51-54.  
  
 Game, 83, 119.  
 Games, 154-157.  
 Goats, 116.  
 Grafting, 132.  
 Grain, 79, 125.  
*Grammaticus*, 62, 63.  
 Guests, 72, 73.  
 Guides, 152.  
  
 Hair, dressing of the, 12, 99, 100, 103, 104.  
 Head-gear, 100.  
 Hens, 117, 118.  
 Highways, chief, from Rome, 135, 137 ; how maintained, 13 ; robbers on, 141.  
 Honey, 85.  
 Horses, 112, 113, 144, 145.  
*Hospitium*, 72, 73.  
 Hour, Roman, 44, 45, 164.  
 House, Roman, 28-39, 48.  
  
*Iēntāculum*, 46.  
*Imāginēs*, 20, 21, 28.  
 Interment, 22, 25, 26.  
*Iūs suffrāgīū*, 65 ; *ōsculī*, 9.  
  
 Jewellery, 102, 104.  
  
*Lavātrīna*, 48.  
*Lectī*, 39-41.  
 Letters, 39, 40, 137.  
*Libertus*, 7, 74.  
*Litterator*, 59, 60.  
  
 Litters, 145, 146.  
 Looms, 92.  
*Lūstrātiō*, 57.  
  
*Mansiōnēs*, 138.  
*Manus*, 2, 9, 10.  
 Market-gardens, 127.  
 Marriage, 8-17.  
*Mēnsae*, 41, 51, 52.  
 Merchants, 148, 149.  
*Merīdātiō*, 47.  
 Mills, for grain, 79-81 ; for oil, 124, 125.  
 Money, 61, 147, 161, 162.  
 Mourning, 23, 26.  
 Mules, 117, 146.  
  
 Names, of men, 3-5, 7, 8, 57, 64 ;  
     of slaves and freedmen, 6, 7 ;  
     of women, 5, 6, 8.  
  
 Oil, 77, 85, 86, 124, 125, 131, 132.  
 Olive-raising, 130-132.  
*Ostium*, 30, 35.  
  
*Paedagōgus*, 63.  
*Palla*, 103.  
 Peacocks, 119.  
*Peristylum*, 34.  
 Pigeons, 118.  
 Pigs, 116, 117.  
*Pinacothēca*, 36.  
 Post, public, and private, 137.  
*Prandium*, 47.  
 Press, for oil and wine, 125.  
 Pulse, 126.  
  
*Rhētor*, 63, 64.  
 Road-making, 137.

- Sacrarium*, 34.  
*Salūtātiō*, 46.  
 Sandals, 102.  
 Sheep, 114–116.  
 Shoes, 101.  
 Slaves, 6, 7, 38, 53, 66–72, 77,  
     107–109.  
 Snails, 119.  
 Spinning, 91.  
*Spōnsālia*, 11.  
*Stola*, 103.  
  
 Table-ware, 42, 53, 54.  
*Tablinum*, 32, 33.  
*Tīrōcinium*, 65.
- Toga*, 64–66, 93, 95–98, 103.  
 Travelling, 138, 142–154.  
  
 Vegetables, 81, 82, 127.  
 Vehicles, 138, 143, 145.  
 Vessels, 146, 147.  
*Vīlicus*, 107, 108.  
 Vine culture, 127–129.  
  
 Wedding ceremonies, 13–15.  
 Wine, 55, 56, 85–88, 125, 129–131.  
 Writing-tablets, 39, 40.  
  
 Year, division of, 132–134, 163.



# THE STUDENTS' SERIES OF LATIN CLASSICS.

UNDER THE EDITORIAL SUPERVISION OF

ERNEST MONDELL PEASE, A.M.,

*Leland Stanford Junior University,*

AND

HARRY THURSTON PECK, PH.D., L.H.D.,

*Columbia College.*

---

This Series contains the Latin authors usually read in American schools and colleges, and also others well adapted to class-room use, but not heretofore published in suitable editions. The several volumes are prepared by special editors, who aim to revise the text carefully and to edit it in the most serviceable manner. Where there are German editions of unusual merit, representing years of special study under the most favorable circumstances, these are used, with the consent of the foreign editor, as a basis for the American edition. In this way it is possible to bring out text-books of the highest excellence in a comparatively short period of time.

The editions are of two kinds, conforming to the different methods of studying Latin in our best institutions. Some contain in the introductions and commentary such a careful and minute treatment of the author's life, language, and style as to afford the means for a thorough appreciation of the author and his place in Latin literature. Others aim merely to assist the student to a good reading knowledge of the author, and have only the text and brief explanatory notes at the bottom of each page. The latter are particularly acceptable for sight reading, and for rapid reading after the minute study of an author or period in one of the fuller editions. For instance, after a class has read a play or two of Plautus and Terence carefully, with special reference to the peculiarities of style, language, metres, the methods of presenting a play, and the like, these editions will be admirably suited for the rapid reading of other plays.

The Series also contains various supplementary works prepared by competent scholars. Every effort is made to give the books a neat and attractive appearance.

The following volumes are now ready or in preparation : —

- CAESAR, Gallic War, Books I-V.** By HAROLD W. JOHNSTON, Ph.D.  
Professor in the Indiana University.
- CATULLUS, Selections,** based upon the edition of Riese. By THOMAS  
B. LINDSAY, Ph.D., Professor in Boston University.
- CICERO, Select Orations.** By B. L. D'OOGHE, A.M., Professor in the  
State Normal School, Ypsilanti, Mich.
- CICERO, De Senectute et de Amicitia.** By CHARLES E. BENNETT,  
A.M., Professor in the Cornell University. *Ready.*
- CICERO, Tusculan Disputations, Books I and II.** By Professor  
PECK.
- CICERO, De Oratore, Book I,** based upon the edition of Sorof. By  
W. B. OWEN, Ph.D., Professor in Lafayette College. *Ready.*
- CICERO, Select Letters,** based in part upon the edition of Süpfle-  
Böckel. By Professor PEASE.
- EUTROPIUS, Selections.** *Ready.*
- GELLIUS, Selections.** By Professor PECK.
- HORACE, Odes and Epodes.** By PAUL SHOREY, Ph.D., Professor in  
the Chicago University. *Ready.*
- HORACE, Satires and Epistles,** based upon the edition of Kiessling.  
By JAMES H. KIRKLAND, Ph.D., Professor in Vanderbilt Uni-  
versity. *Ready.*
- JUVENAL, Satires.** By JAMES C. EGBERT, Jr., Ph.D., Adjunct Pro-  
fessor of Latin, and NELSON G. MCCREA, Ph.D., Instructor in  
Latin, Columbia University.
- LIVY, Books XXI and XXII,** based upon the edition of Wölfflin. By  
JOHN K. LORD, Ph.D., Professor in Dartmouth College. *Ready.*
- LIVY, Book I,** for rapid reading. By Professor LORD. *Ready.*
- LUCRETIUS, De Rerum Natura, Book III.** By W. A. MERRILL, Ph.D.,  
Professor in the University of California.
- MARTIAL, Selections.** By CHARLES KNAPP, Ph.D., Professor in  
Barnard College.
- NEPOS, for rapid reading.** By ISAAC FLAGG, Ph.D., Professor in the  
University of California. *Ready.*
- NEPOS, Selections.** By J. C. JONES, A.M., Professor in the University  
of Missouri.

**OVID, Selections from the Metamorphoses**, based upon the edition of Meuser-Egeu. By B. L. WIGGINS, A.M., Professor in the University of the South.

**JVID, Selections**, for rapid reading. By A. L. BONDURANT, A.M., Professor in the University of Mississippi.

**PETRONIUS, Cena Trimalchionis**, based upon the edition of Büchele. By W. E. WATERS, Ph.D., President of Wells College.

**PLAUTUS, Captivi**, for rapid reading. By GROVE E. BARBER, A.M., Professor in the University of Nebraska. *Ready*

**PLAUTUS, Menaechmi**, based upon the edition of Brix. By HAROLD N. FOWLER, Ph.D., Professor in the Western Reserve University. *Ready.*

**PLINY, Select Letters**, for rapid reading. By SAMUEL BALL PLATNER, Ph.D., Professor in the Western Reserve University. *Ready.*

**QUINTILIAN, Book X and Selections from Book XII**, based upon the edition of Krüger.

**SALLUST, Catiline**, based upon the edition of Schmalz. By CHARLES G. HERBERMANN, Ph.D., LL.D., Professor in the College of the City of New York. *Ready.*

**SENECA, Select Letters**. By E. C. WINSLOW, A.M.

**TACITUS, Annals, Book I and Selections from Book II**, based upon the edition of Nipperdey-Andresen. By E. M. HYDE, Ph.D., Professor in Lehigh University.

**TACITUS, Agricola and Germania**, based upon the editions of Schweizer-Sidler and Dräger. By A. G. HOPKINS, Ph.D., Professor in Hamilton College. *Ready.*

**TACITUS, Histories, Book I and Selections from Books II-V**, based upon the edition of Wolff. By EDWARD H. SPIEKER, Ph.D., Professor in the Johns Hopkins University.

**TERENCE, Adelphoe**, for rapid reading. By WILLIAM L. COWLES, A.M., Professor in Amherst College. *Ready.*

**TERENCE, Phormio**, based upon the edition of Dziatzko. By HERBERT C. ELMER, Ph.D., Assistant Professor in the Cornell University. *Ready.*

**CIBULLUS AND PROPERTIUS, Selections**, based upon the edition of Jacoby. By HENRY F. BURTON, A.M., Professor in the University of Rochester.

- VALERIUS MAXIMUS**, Fifty Selections, for rapid reading. By CHARLES S. SMITH, A.M., Late College of New Jersey. *Ready.*
- VELLEIUS PATERCULUS**, *Historia Romana*, Book II. By F. E. ROCKWOOD, A.M., Professor in Bucknell University. *Ready.*
- VERGIL**, Books I-VI. By JAMES H. KIRKLAND, Ph.D., Professor of Latin in Vanderbilt University, and WILLIAM H. KIRK, Ph.D., Professor of Latin in Rutgers College.
- VERGIL**, The Story of Turnus from Aen. VII-XII, for rapid reading. By MOSES SLAUGHTER, Ph.D., Professor in University of Wisconsin. *Ready.*
- VIRI ROMAE**, Selections. With Prose Exercises. By G. M. WHICHER, A.M., Teachers' Normal College, New York City. *Ready.*
- LATIN COMPOSITION**, for college use. By WALTER MILLER, A.M., Professor in the Leland Stanford Jr. University. *Ready.*
- LATIN COMPOSITION**, for advanced classes. By H. R. FAIRCLOUGH, A.M., Professor in the Leland Stanford Jr. University.
- HAND-BOOK OF LATIN SYNONYMS**. By Mr. MILLER.
- A FIRST BOOK IN LATIN**. By HIRAM TUELL, A.M., late Principal of the Milton High School, Mass., and HAROLD N. FOWLER, Ph.D., Western Reserve University. *Ready.*
- A BEGINNER'S BOOK IN LATIN**. By TUELL and FOWLER. *Ready.*
- A NEW LATIN COMPOSITION**, for schools. By M. GRANT DANIELL, A.M., formerly Principal of Chauncy Hall School, Boston. *Ready.*
- A NEW GRADATIM**. By M. C. SMART, A.M., Principal of Claremont (N.H.) High School. *Ready.*
- THE PRIVATE LIFE OF THE ROMANS**, a manual for the use of schools and colleges. By HARRIET WATERS PRESTON and LOUISE DODGE. *Ready.*
- GREEK AND ROMAN MYTHOLOGY**, based on the recent work of Stending. By KARL P. HARRINGTON, A.M., Professor in the University of Maine, and HERBERT C. TOLMAN, Ph.D., Professor in Vanderbilt University. *Ready.*
- ATLAS ANTIQUUS**, twelve maps of the ancient world, for schools and colleges. By Dr. HENRY KIEPERT, M.R. Acad. Berlin. *Ready.*

---

BENJ. H. SANBORN & CO., Publishers,  
Boston, Chicago, London.









# DATE DUE

OC 24 '69

NO 7 '69


DE 1 '69

NO 29 '76

DE 13 '76

NO 20 '79

DE 19 '81



3 1927 00106393 9

2

913.37  
P92Preston, Harriet W.  
The private life of  
the Romans.

DATE

ISSUED TO

APR 1 - 57

*4-5 / 18*  
*P. Starnes*913.37  
P92

